

ADDENDUM No. 1

for

**Rehabilitate Runway 17-35
Bid # FY22-805-49**

at the Manchester – Boston Regional Airport

Due to be opened 2:30 p.m., on April 19, 2022

Date: March 31, 2022

The attention of firms submitting proposals for the work named above is called to the following modifications to the documents as were issued.

The items set forth herein, whether of clarification, omission, addition and/or substitution, shall be included and form a part of the Proposer's submitted materials and the corresponding contract when issued. No claim for additional compensation, due to lack of knowledge of the contents of this Addendum will be considered.

All Proposer's are advised that receipt of this notice and all attached material must be duly acknowledged in the space provided on the signature page of the proposal documents, and **by the insertion of this sheet, signed, and submitted with your Proposal package.**

This form must be signed and attached to the original copy of your submission.

The attached sheets contain information or clarifications requested or discussed.

Receipt of Addendum No. 1 to the REQUEST FOR PROPOSALS for **Rehabilitate Runway 17-35**
at the MANCHESTER-BOSTON REGIONAL AIRPORT is hereby acknowledged.

COMPANY NAME: _____

SIGNED BY: _____

NAME AND TITLE PRINTED: _____

TELEPHONE: _____ FAX: _____

GENERAL

In general, this addendum is accomplishing the following:

1. Revises the bid opening date as stated.
2. Answers to questions to date.
3. The Runway 35 Service Road is added to the project as Volume 4 plan set as well as three new specifications are provided. Volume 4 work is designated as Additive Alternate #6.
4. The phasing drawings are updated for the addition of Phase 4.
5. Miscellaneous updates are made to clarify other items and notes.

Addendum No. 2 is planned to be issued soon. Addendum No. 2 will update the Bid Proposal form for the addition of Additive Alternate #6 and other changes to the project documents.

QUESTIONS/CLARIFICATIONS

Addendum Item No.1 -

Q1: What are the night working hours for the PH 5 grooving? Can't seem to find the exact hours in the P&S?

A1: Night work hours for Phases 4, 5 and 6 are 7:00 PM to 7:00 AM.

Q2: Will the FAA / City of Manchester consider offering items to cover Fuel and Asphalt Escalation on this project? With the volatile market we are currently in, predicting out where costs will be a year from now is leaving quite a bit of risk on the contractor's plate.

A2: No. FAA Order 5100.38D, Table C-2, Table Item #40 lists "Price Escalation Increases" as a prohibited cost for construction.

Q3: Pending submittal / lead times, would it be possible for the contractor to begin phase 7/8 for the retaining wall work fall of 2022? How does this affect the total job duration of 99 days, as it currently states that this work is concurrent with phase 3?

A3: Yes. Additional time for the retaining wall has been added. Revised phasing plans are provided.

Q4: With the volatility of the energy market Brox Industries respectfully asks the FAA to consider an escalation clause for Liquid Asphalt and Diesel fuel. This is common practice on State jobs with both State and Federal funds. At the prebid we were explained the milling and paving portion were for the 2023 season. This is difficult to forecast that far out

A4: An escalation clause is not included. FAA Order 5100.38D, Table C-2, Table Item #40 lists "Price Escalation Increases" as a prohibited cost for construction.

Q5: During the prebid a question was asked about starting the repairs to the retaining wall in 2022 if a contract is executed with the low bidder. Has any additional thought been given to this request??

A5: Yes. Revised phasing plans are provided.

Q6: Just wondering if I could have a copy of the pre-bid sign-in?

A6: See attached Pre-bid Sign-in.

Q7: Would the Airport consider including a fuel adjustment allowance? The price of fuel has been fluctuating wildly lately. It would likely save MHT in the long run to take the risk off the contractors.

A7: No. See above replay regarding the escalation clause as a prohibited cost.

Q8: Would the Airport consider including an asphalt adjustment allowance? The price of asphalt has been fluctuating wildly lately. It would likely save MHT in the long run to take the risk off the contractors.

A8: No. See above replay regarding the escalation clause as a prohibited cost.

Q9: There is another large project bidding at the Airport on 4/6. Could this bid date be moved?
A9: *Bid date is moved to April 19 @ 2:30PM for the addition of the Runway 35 Service Road.*

PROJECT MANUAL

Addendum Item No.2 -

Advertisement for Bids:

REMOVE and REPLACE the first sentence of the sixth paragraph with the following:

“Bids will be publicly opened and read aloud on **April 19, 2022, at 2:30 pm** at the Airport administrative offices boardroom located on the third floor of the Airport terminal at One Airport Road, Manchester, NH.”

Addendum Item No.3 -

Information for Bidders, 1.01 RECEIPT AND OPENING BIDS

REMOVE and REPLACE the second sentence of paragraph 1.01 with the following:

“Bids will be received by the Manchester-Boston Regional Airport Administration Office at One Airport Road Manchester, NH until **2:30 pm on April 19, 2022**, and then at said office publicly opened and read aloud.”

Addendum Item No.4 -

Information for Bidders, 1.03 PREPARATION OF BID & METHOD OF AWARD

REMOVE and REPLACE the third paragraph with the following:

“The Contract will be awarded to the Contractor with the lowest qualified total bid for the Base Bid plus Additive Alternates No. 1 through No. 6.

If such bids exceed the available funding, the Contract will be awarded to the Contractor with the lowest qualified bid for the Base Bid plus Additive Alternates No. 1 through No. 5.”

Addendum Item No.5 -

Information for Bidders, 1.08 TIME OF COMPLETION AND LIQUIDATED DAMAGES

REMOVE and REPLACE the 2nd paragraph with the following:

“The second Notice to Proceed will be for the construction. The bidder must agree to commence work on a date to be specified in the following written Notice to Proceed of the Owner and to fully complete the project within the calendar days as specified on Drawing No. G-100. Bidder must agree to pay to the Owner as liquidated damages the sum of two thousand dollars (\$2,000.00) for each and every calendar day the work remains incomplete beyond the above specified time.”

Addendum Item No.6 -

Bid Proposal:

A revised bid proposal will be issued in the next addendum to account for the new Additive Alternate #6 Runway 35 Service Road work as well as updates to quantities for the Base Bid and Additive Alternates #1 through #5.

Addendum Item No.7 -

Technical Specifications:

REMOVE and REPLACE the Technical Specifications table of contents with the attached Table of Contents Technical Specifications.

Addendum Item No.8 -

Technical Specifications:

ADD the Geotechnical Report from SW Cole for the Runway 35 Service Road to the Project Manual Appendices.

Addendum Item No.9 -

Technical Specifications:

ADD the below technical specifications.

1. M-003 Stream Alteration and Permit Conditions
2. P-154 Subbase Course
3. F-163 Wildlife Deterrent Fence Skirt

DRAWINGS

Addendum Item No.10 -

REMOVE and REPLACE the below drawings.

1. T-001 PROJECT TITLE SHEET
2. G-002 INDEX OF DRAWINGS, GENERAL PROJECT ABBREVIATIONS AND LEGEND
3. G-003 PROJECT GENERAL NOTES
4. G-004 CONSTRUCTION ACCESS PLAN AND NOTES
5. G-100 GENERAL CONSTRUCTION SAFETY AND PHASING PLAN AND NOTES
6. G-105 PHASES 7 & 8 CONSTRUCTION SAFETY PHASING PLAN AND NOTES
7. G-106 PHASE 9 CONSTRUCTION SAFETY AND PHASING PLAN AND NOTES
8. G-203 CONSTRUCTION SAFETY AND PHASING DETAILS - 3

Addendum Item No.11 -

ADD the following drawings:

1. G-107 PHASE 10 CONSTRUCTION SAFETY AND PHASING PLAN & NOTES
2. VOLUME 4 RECONSTRUCT AND REHABILITATE A PORTION OF THE SERVICE ROAD

Addendum Item No.12 -

DRAWING NO. G-101. REVISE "Phase 1 Notes", Note 3 as follows:

"THIS PHASE MUST BE COMPLETED PRIOR TO THE START OF PHASE 2. PHASE 2 STARTS IMMEDIATELY AFTER THIS PHASE. THIS PHASE MUST RUN INDEPENDENTLY WITH ALL OTHER CONSTRUCTION PHASES."

Addendum Item No.13 -

DRAWING NO. G-202. ADD Note 3 to Detail 2 as follows:

"3. COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1."

Addendum Item No.14 -

DRAWING NOS. C-101 to C-110. REMOVE AND REPLACE "Existing Conditions Notes", Note 2, 1st sentence as follows:

"2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES (SEE UTILITY LOCATING ALLOWANCE ITEM FOR PAYMENT), INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE RPR OF HIS OPERATIONAL PLANS."

Addendum Item No.15 -

DRAWING NOS. C-101 to C-110. ADD Note 7 as follows:

"7. PAVEMENT CORE DATA IS PROVIDED IN THE PROJECT MANUAL APPENDICES."

Addendum Item No.16 -

DRAWING NOS. C-201 to C-208. REMOVE AND REPLACE "Civil Site Preparation Notes", Note 5, 1st sentence as follows:

"5. THE CONTRACTOR SHALL FLUSH/CLEAN OUT EXISTING UNDERDRAIN ON BOTH SIDES AND FOR THE FULL LENGTH OF RUNWAY 17-35 AND WITHIN THE PROJECT LIMITS FOR RUNWAY 6-24 (SEE PAY ITEM M-006-1)."

END OF ADDENDUM #1



DATE: March 17, 2022

MEETING: Rehabilitation of Runway 17/35 Pre-Bid Meeting

[illegible]

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

TABLE OF CONTENTS - TECHNICAL SPECIFICATIONS

G-001	Special Work Requirements (Includes CSPP and SPCD)
G-002	Record Documents
G-003	Gate Guard Allowance
G-004	Maintenance and Protection of Traffic
G-005	Engineer Field Office
C-100	Contractor Quality Control Program (CQCP)
C-102	Temporary Air and Water Pollution, Soil Erosion, and Siltation Control
C-105	Mobilization
C-110	Method of Estimating Percentage of Material Within Specification Limits (PWL)
M-001	Construction Access Modifications
M-002	Runway Standby Time
M-003	Stream Alteration and Permit Conditions
M-004	Mechanically Stabilized Earth Walls
M-005	Riprap & Geotextiles
M-006	Flush & Cleanout Underdrains
M-007	Stormwater Pollution Prevention Plan
M-008	Crack Repairs for Bituminous Pavements
P-101	Preparation/Removal of Existing Pavements
P-152	Excavation, Subgrade and Embankment
P-154	Subbase Course
P-209	Crushed Aggregate Base Course
P-401	Asphalt Mix Pavement
P-403	Asphalt Mix Pavement Surface Course
P-603	Emulsified Asphalt Tack Coat
P-605	Joint Sealants for Pavements
P-606	Adhesive Compounds, Two Component for Sealing Wires and Lights in Pavement
P-608	Emulsified Asphalt Sealcoat
P-610	Concrete for Miscellaneous Structures
P-620	Runway and Taxiway Marking
P-621	Saw-Cut Grooves
D-701	Pipe for Storm Drains and Culverts
D-751	Manholes, Catch Basins, Inlets, and Inspection Holes
D-752	Concrete Culverts, Headwalls, and Miscellaneous Drainage Structures
L-105	Alterations, Removal, and Demolition
L-108	Underground Power Cable for Airports
L-110	Airport Underground Electrical Duct Banks and Conduits
L-115	Electrical Manholes and Junction Structures
L-125	Installation of Airport Lighting Systems
L-140	Runway Weather Information System
L-150	Modifications to FAA Approach Lighting Systems
T-901	Seeding
T-905	Topsoil
T-908	Mulching
F-162	Chain-Link Fence
F-163	Wildlife Deterrent Fence Skirt
Appendices:	
Appendix A	Existing Pavement Cores
Appendix B	Partial In-Pavement Light Base Survey
Appendix C	Reconstruct Runway 35 Service Road (Geotechnical) Report

REPORT

19-1233 S

May 19, 2020

Explorations and Geotechnical Engineering Services

Reconstruct Runway 35 End of Service Road
Manchester-Boston Regional Airport
Manchester, New Hampshire

Prepared For:
Hoyle, Tanner & Associates, Inc.
Attention: Suzanne Sheppard, PE
150 Dow Street
Manchester, NH 03101

Prepared By:
S. W. Cole Engineering, Inc.
13 Delta Drive #8
Londonderry, NH 03053
T: 603-716-2111



- *Geotechnical Engineering*
- *Construction Materials Testing and Special Inspections*
- *GeoEnvironmental Services*
- *Test Boring Explorations*

www.swcole.com

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1 Scope and Purpose	1
1.2 Site and Proposed Construction	1
2.0 EXPLORATION AND TESTING.....	2
2.1 Explorations.....	2
2.3 Laboratory Testing.....	2
3.0 SUBSURFACE CONDITIONS	2
3.1 Soil and Bedrock	2
3.2 Groundwater.....	3
4.0 EVALUATION AND RECOMMENDATIONS	3
4.1 General Findings	3
4.2 Design Review and Construction Testing	3
5.0 CLOSURE	4
Appendix A	Limitations
Appendix B	Figures
Appendix C	Exploration Logs & Key
Appendix D	Laboratory Test Results

19-1233 S

May 19, 2020

Hoyle, Tanner & Associates, Inc.
Attention: Suzanne Sheppard, PE
150 Dow Street
Manchester, NH 03101

Subject: Explorations and Geotechnical Engineering Services
Reconstruct Runway 35 End of Service Road
Manchester-Boston Regional Airport
Manchester, New Hampshire

Dear Suzy:

In accordance with our Proposal, dated August 28, 2019, we have performed subsurface explorations for the subject project. This report summarizes our findings and geotechnical recommendations and its contents are subject to the limitations set forth in Appendix A.

1.0 INTRODUCTION

1.1 Scope and Purpose

The purpose of our services was to obtain subsurface information at the site in order to develop geotechnical recommendations relative to earthwork and pavement associated with the proposed construction. Our scope of services included test boring explorations, soils laboratory testing, a geotechnical analysis of the subsurface findings, and preparation of this report.

1.2 Site and Proposed Construction

We understand that the project involves reconstruction of about 6,700 linear feet of the perimeter service road on the Runway 35 end of the airport. About 2,600 linear feet of the service road is experiencing pavement distress and undermining during rain events and spring thaw, and is proposed for reconstruction. The remaining portions are in better condition and a mill and overly is conceived in these areas.

Existing site features are shown on the “Exploration Location Plan” attached in Appendix B.

2.0 EXPLORATION AND TESTING

2.1 Explorations

Seven test borings (B-1 through B-7) were made at the site on May 5, 2020 by S. W. Cole Explorations, LLC. The exploration locations were selected and established in the field by Hoyle, Tanner & Associates, Inc. The approximate exploration locations are shown on the “Exploration Location Plan” attached in Appendix B. Logs of the explorations and a key to the notes and symbols used on the logs are attached in Appendix C. The elevations shown on the logs were estimated based on topographic information shown on the “Exploration Location Plan”.

2.3 Laboratory Testing

Soil samples obtained from the explorations were returned to our laboratory for further classification and testing. Moisture content test results are noted on the logs. The results of hydrometer analyses are attached in Appendix D.

3.0 SUBSURFACE CONDITIONS

3.1 Soil and Bedrock

Test borings B-1 through B-7 were made through the existing pavement. The test borings encountered 3 to 3 ¾ inches of asphalt pavement. The asphalt layers were bonded at test borings B-1 and B-5 through B-7. The asphalt layers were delaminated at test borings B-2 through B-4. Photos of the asphalt cores are presented in Appendix C.

Under the asphalt a soils profile generally consisting of silty gravelly sand (aggregate base) overlying silty fine sands with varying amounts of gravel and trace to some levels of clay. Test Borings B-1 through B-4 encountered refusal surfaces (probable boulder or bedrock) from 3 to 5 feet. Test Boring B-6 encountered refusal surface (probable bedrock or boulder) at 9.6 feet. Test Boring B-5 and B-7 were terminated at the target depth of 10 feet.

Not all the strata were encountered at each exploration; refer to the attached logs for more detailed subsurface information.

3.2 Groundwater

Saturated soils were encountered at test borings B-5 through B-7 at depths varying from 6 to 8 feet. Groundwater likely becomes perched on the relatively impervious glacial till and bedrock encountered at the test borings. Long term groundwater information is not available. It should be anticipated that groundwater levels will fluctuate, particularly in response to periods of snowmelt and precipitation, as well as changes in site use.

4.0 EVALUATION AND RECOMMENDATIONS

4.1 Frost Considerations

Based on the subsurface findings, the proposed construction appears feasible from a geotechnical standpoint. The principle geotechnical considerations include:

- The design frost penetration depth for the Manchester, New Hampshire area is 4 feet.
- Based on samples tested, the base material contains percent passing the No. 200 sieve ranging from about 10 to 20 percent. The base material is consider slightly to moderately frost susceptible.
- Based on samples tested, the subgrade soils contains percent passing the No. 200 sieve ranging from about 15 to 33 20 percent. The subgrade soils at the site are considered moderately frost susceptible.
- Although saturated soils (interpreted to the groundwater or perched water) do not occur until depths of 6 to 8 feet, the subgrade soils are considered poorly draining and water entering the pavement section will be slow to drain into the subgrade. Without proper daylighting gravity drainage of the base section to ditches or use of underdrains, collection of water increases frost susceptibility and decreases the strength of the subgrade soils.

4.2 Construction Testing

A soils and asphalt testing program should be implemented during construction to observe compliance with the design concepts, plans, and specifications. S.W.COLE is available to observe earthwork activities and pavement subgrades, as well as to provide testing of soils and asphalt construction materials.


5.0 CLOSURE

It has been a pleasure to be of assistance to you with this phase of your project. We look forward to working with you during the construction phase of the project.

Sincerely,


S. W. Cole Engineering, Inc.

Antonio J. Santiago, E.I.T.
Geotechnical Engineer

A handwritten signature in blue ink, appearing to read 'Chad Bartlett Michaud', is written over a red diagonal line.

Digitally signed by
Chad Michaud
DN: cn=Chad Michaud,
o=S. W. Cole
Engineering, Inc., ou,
email=cmichaud@swc
ole.com, c=US
Date: 2020.05.19
17:51:37 -04'00'

Chad B. Michaud, P.E.
Senior Geotechnical Engineer



AJS:cbm

APPENDIX A

Limitations

This report has been prepared for the exclusive use of Hoyle, Tanner & Associates, Inc. for specific application to the proposed Reconstruct Runway 35 End of Service Road on Manchester-Boston Regional Airport in Manchester, New Hampshire. S. W. Cole Engineering, Inc. (S.W.COLE) has endeavored to conduct our services in accordance with generally accepted soil and foundation engineering practices. No warranty, expressed or implied, is made.

The soil profiles described in the report are intended to convey general trends in subsurface conditions. The boundaries between strata are approximate and are based upon interpretation of exploration data and samples.

The analyses performed during this investigation and recommendations presented in this report are based in part upon the data obtained from subsurface explorations made at the site. Variations in subsurface conditions may occur between explorations and may not become evident until construction. If variations in subsurface conditions become evident after submission of this report, it will be necessary to evaluate their nature and to review the recommendations of this report.

Observations have been made during exploration work to assess site groundwater levels. Fluctuations in water levels will occur due to variations in rainfall, temperature, and other factors.

S.W.COLE's scope of services has not included the investigation, detection, or prevention of any Biological Pollutants at the project site or in any existing or proposed structure at the site. The term "Biological Pollutants" includes, but is not limited to, molds, fungi, spores, bacteria, and viruses, and the byproducts of any such biological organisms.

Recommendations contained in this report are based substantially upon information provided by others regarding the proposed project. In the event that any changes are made in the design, nature, or location of the proposed project, S.W.COLE should review such changes as they relate to analyses associated with this report. Recommendations contained in this report shall not be considered valid unless the changes are reviewed by S.W.COLE.

APPENDIX B

Figures

Boring Locations

Hoyle, Tanner Project #: 030089
MHT Reconstruct/Rehabilitate Service Road
May, 2020

Legend



Approx. Boring Location



APPENDIX C

Exploration Logs and Key



BORING LOG

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

BORING NO.: B-1
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 3.0 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety / N/A HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A / N/A CORE BARREL: N/A
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): No free-water observed.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS: Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S	⊗	0.3-1	8/8			0.3 3 3/4 inches Asphalt Pavement (Bonded)		
			1D	⊗	1-1.5	6/3	50		Dark brown, silty gravelly SAND some clay (FILL) (SM)		
									1.0 Brown, SAND some gravel some silt (SW-SM)		

Auger Refusal at 3.0 feet
Probable bedrock or boulder.

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: B-1



BORING LOG

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

BORING NO.: B-2
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 3.5 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A / N/A CORE BARREL:
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): No free-water observed.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS: Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S		0.3-1	8/8			0.3 3 1/2 inches Asphalt Pavement (Delaminated)		
			1D		1-2	12/8	28-50		1.0 Dark brown, silty gravelly SAND some clay (FILL) (SM) Dense, brown gravelly silty SAND trace clay (TILL) (SM)		

Auger Refusal at 3.5 feet
Probable bedrock or boulder.

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: B-2



BORING LOG

BORING NO.: **B-3**
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 5.0 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A /N/A CORE BARREL:
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): No free-water observed.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS:
Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S	×	0.3-1	8/8			0.3 3 inches Asphalt Pavement (Delaminated)		
			1D	×	1-3	24/16	12-20-28		1.0 Dark brown, silty gravelly SAND some clay (FILL) (SM)		
			2D	×	3-3.4	5/5	50/5"		Dense, gray silty SAND some clay some gravel (SC-SM)		

Auger Refusal at 5.0 feet
Probable bedrock or boulder.

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: **B-3**



BORING LOG

BORING NO.: **B-4**
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 5.0 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A / N/A CORE BARREL:
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): No free-water observed.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS:
Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S		0.3-1.5	14/14			0.3		3 inches Asphalt Pavement (Delaminated) Dark brown, SAND and GRAVEL some silt trace clay (FILL) (SM)
			1D		1.5-3.5	24/14	13-35- 32-48	w =10.1 %	1.5		Dense, gray silty SAND some clay some gravel (SC-SM)
			2D		4-4.8	9/6	48- 50/3"	w =7.2 %			
5											

Auger Refusal at 5.0 feet
Probable bedrock or boulder.

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: **B-4**



BORING LOG

CLIENT: Hoyle, Tanner & Associates, Inc.
 PROJECT: Reconstruct Runway 35 End of Service Road
 LOCATION: Manchester-Boston Regional Airport, Manchester, NH

BORING NO.: B-5
 SHEET: 1 of 1
 PROJECT NO. 19-1233
 DATE START: 5/5/2020
 DATE FINISH: 5/5/2020

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 10.0 LOGGED BY: Antonio Santiago
 DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
 RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
 HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A /N/A CORE BARREL:
 HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
 WATER LEVEL DEPTHS (ft): 6 ft Soil samples saturated below 6 feet.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS: Water Level
 At time of Drilling
 At Completion of Drilling
 After Drilling
 D = Split Spoon Sample
 U = Thin Walled Tube Sample
 R = Rock Core Sample
 V = Field Vane Shear
 Pen. = Penetration Length
 Rec. = Recovery Length
 bpf = Blows per Foot
 mpf = Minute per Foot
 WOR = Weight of Rods
 WOH = Weight of Hammer
 RQD = Rock Quality Designation
 PID = Photoionization Detector
 S_v = Field Vane Shear Strength, kips/sq.ft.
 q_u = Unconfined Compressive Strength, kips/sq.ft.
 Ø = Friction Angle (Estimated)
 N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S		0.3-1.5	14/14			0.3 3 1/2 inches Asphalt Pavement (Bonded) Dark brown, gravelly SAND some silt trace clay (FILL) (SW-SM)		
			1D		1.5-3.5	24/14	20-23- 40-32	w =6.2 %	1.5 Dense, brown SAND some gravel some silt (FILL) (SM)		
								w =6.9 %			
			2D		4-6	24/16	15-23- 30-20		3.0 Dense, brown silty SAND trace gravel trace clay (SM)		
								w =9.8 %			
			3D		6-8	24/12	22-24- 30-28				
			4D		8-10	24/14	25-26- 26-29				

Bottom of Exploration at 10.0 feet

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: B-5



BORING LOG

BORING NO.: **B-6**
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 9.6 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A / N/A CORE BARREL:
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): 8 ft Soil samples saturated below 8 feet.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS: Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
5			1S		0.3-1.5	14/14			0.3		3 inches Asphalt Pavement (Bonded)
											Dark brown, gravelly SAND some silt trace clay (FILL) (SM)
			1D		1.5-3.3	21/12	20-22-30-50/3"	w = 7.1 %	1.5		Dense to Loose, brown gravelly silty SAND trace clay (FILL) (SM)
								w = 6.7 %			
			2D		4-4.8	9/3	6-50/3"				
			3D		6-8	24/6	2-2-6-8				
									7.0		Medium dense to dense, brown gravelly SAND some silt (SW-SM)
			4D		8-9.6	19/14	20-22-30-50/1"				

Split Spoon Refusal at 9.6 feet
Probable bedrock or boulder.

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: **B-6**



BORING LOG

CLIENT: Hoyle, Tanner & Associates, Inc.
PROJECT: Reconstruct Runway 35 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

BORING NO.: B-7
SHEET: 1 of 1
PROJECT NO. 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

Drilling Information

LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 10.0 LOGGED BY: Antonio Santiago
DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger
RIG TYPE: Truck Mounted Acker AUGER ID/OD: N/A / 4 1/2 in SAMPLER: Standard Split-Spoon
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A / N/A CORE BARREL:
HAMMER EFFICIENCY FACTOR: HAMMER DROP (inch): 30
WATER LEVEL DEPTHS (ft): 6 ft Soil samples saturated below 6 feet.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS: Water Level
At time of Drilling
At Completion of Drilling
After Drilling
D = Split Spoon Sample
U = Thin Walled Tube Sample
R = Rock Core Sample
V = Field Vane Shear
Pen. = Penetration Length
Rec. = Recovery Length
bpf = Blows per Foot
mpf = Minute per Foot
WOR = Weight of Rods
WOH = Weight of Hammer
RQD = Rock Quality Designation
PID = Photoionization Detector
S_v = Field Vane Shear Strength, kips/sq.ft.
q_u = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

Elev. (ft)	Depth (ft)	Casing Pen. (bpf)	SAMPLE INFORMATION					Graphic Log	Sample Description & Classification	H ₂ O Depth	Remarks
			Sample No.	Type	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD				
			1S		0.3-2	20/20			0.3 3 1/2 inches Asphalt Pavement (Bonded) Dark brown, gravelly silty SAND trace (FILL) (SM)		
			1D		2-4	24/14	30-18- 24-20	w = 7 %	2.0 Dense, brown silty SAND some gravel trace clay (FILL) (SM)		
			2D		4-6	24/4	8-9-12- 14	w = 6.6 %	3.5 Medium dense loose, brown silty SAND some gravel (SM)		
			3D		6-8	24/6	4-4-3-1				
			4D		8-10	24/0	1-1-4-6				

Bottom of Exploration at 10.0 feet

Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: B-7



B-1



B-2






B-3







B-5





B-6





B-7

KEY TO NOTES & SYMBOLS

Test Boring and Test Pit Explorations

Stratification lines represent the approximate boundary between soil types and the transition may be gradual.

Key to Symbols Used:

w	-	water content, percent (dry weight basis)
q _u	-	unconfined compressive strength, kips/sq. ft. - laboratory test
S _v	-	field vane shear strength, kips/sq. ft.
L _v	-	lab vane shear strength, kips/sq. ft.
q _p	-	unconfined compressive strength, kips/sq. ft. – pocket penetrometer test
O	-	organic content, percent (dry weight basis)
W _L	-	liquid limit - Atterberg test
W _P	-	plastic limit - Atterberg test
WOH	-	advance by weight of hammer
WOM	-	advance by weight of man
WOR	-	advance by weight of rods
HYD	-	advance by force of hydraulic piston on drill
RQD	-	Rock Quality Designator - an index of the quality of a rock mass.
γ _T	-	total soil weight
γ _B	-	buoyant soil weight

Description of Proportions:

Trace:	0 to 5%
Some:	5 to 12%
"Y"	12 to 35%
And	35+%
With	Undifferentiated

Description of Stratified Soils

Parting:	0 to 1/16" thickness
Seam:	1/16" to 1/2" thickness
Layer:	1/2" to 12" thickness
Varved:	Alternating seams or layers
Occasional:	one or less per foot of thickness
Frequent:	more than one per foot of thickness

REFUSAL: Test Boring Explorations - Refusal depth indicates that depth at which, in the drill foreman's opinion, sufficient resistance to the advance of the casing, auger, probe rod or sampler was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

REFUSAL: Test Pit Explorations - Refusal depth indicates that depth at which sufficient resistance to the advance of the backhoe bucket was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

Although refusal may indicate the encountering of the bedrock surface, it may indicate the striking of large cobbles, boulders, very dense or cemented soil, or other buried natural or man-made objects or it may indicate the encountering of a harder zone after penetrating a considerable depth through a weathered or disintegrated zone of the bedrock.

APPENDIX D

Laboratory Test Results


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-2, 1S, 0.3-1'

Project Number: 19-1233
Lab ID: 4248M
Date Received: 4/30/2020
Date Completed: 5/7/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount	Passing (%)
3"	76	100		0.06016	16.9	
2"	50	100		0.04316	16.1	
1½"	38.1	100		0.03124	14.3	
1"	25	94		0.03124	14.3	
¾"	19	91		0.02259	12.5	
½"	12.5	87		0.01618	11.6	
¼"	6.3	84		0.01206	9.8	
No. 4	4.75	69		0.00873	8.0	
No. 10	2	55		0.00629	6.2	
No. 20	0.85	44		0.00448	4.9	
No. 40	0.425	37		0.00320	4.0	
No. 60	0.25	31		0.00225	2.7	
No. 100	0.15	26		0.00133	2.2	
No. 200	0.075	20.2				



Particle Distribution: Gravel (3" - No. 4) **31.0%** Fines (0.074 - 0.005) **14.7%**
 Sand (No. 4 - No. 200) **48.8%** Clay (<0.005) **5.5%**

Comments: Moisture (%) = 7.5



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-2, 1D, 1-2'

Project Number: 19-1233
Lab ID: 4249M
Date Received: 4/30/2020
Date Completed: 5/7/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06471	14.4	
2"	50	100		0.04633	13.3	
1½"	38.1	100		0.03343	11.1	
1"	25	100		0.03343	11.1	
¾"	19	95		0.02392	10.0	
½"	12.5	87		0.01724	8.3	
¼"	6.3	82		0.01273	7.2	
No. 4	4.75	76		0.00907	6.1	
No. 10	2	69		0.00648	4.4	
No. 20	0.85	61		0.00461	3.3	
No. 40	0.425	51		0.00326	2.2	
No. 60	0.25	39		0.00230	2.2	
No. 100	0.15	29		0.00134	1.7	
No. 200	0.075	20.0				



Particle Distribution: Gravel (3" - No. 4) **24.2%** Fines (0.075 - 0.005) **16.7%**
 Sand (No. 4 - No. 200) **55.8%** Clay (<0.005) **3.3%**

Comments: Moisture (%) = 7.3



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: info@londonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-4, 1S, 0.3-1.5'

Project Number: 19-1233
Lab ID: 4250M
Date Received: 4/30/2020
Date Completed: 5/7/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06388	11.0	
2"	50	100		0.04672	9.1	
1½"	38.1	93		0.03343	7.9	
1"	25	84		0.03343	7.9	
¾"	19	80		0.02392	7.1	
½"	12.5	71		0.01724	5.5	
¼"	6.3	68		0.01273	4.7	
No. 4	4.75	58		0.00907	4.3	
No. 10	2	49		0.00648	3.2	
No. 20	0.85	41		0.00456	2.4	
No. 40	0.425	33		0.00326	1.6	
No. 60	0.25	24		0.00233	1.2	
No. 100	0.15	18		0.00136	0.8	
No. 200	0.075	12.8				



Particle Distribution: Gravel (3" - No. 4) **42.4%** Fines (0.074 - 0.005) **10.0%**
Sand (No. 4 - No. 200) **44.8%** Clay (<0.005) **2.8%**

Comments: Moisture (%) = 10.1



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: info@londonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SC-SM
Material Source: B-4, 1D, 1.5-3.5'

Project Number: 19-1233
Lab ID: 4251M
Date Received: 4/30/2020
Date Completed: 5/11/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06686	27.7	
2"	50	100		0.04842	23.9	
1½"	38.1	100		0.03423	22.7	
1"	25	100		0.03423	22.7	
¾"	19	100		0.02439	20.2	
½"	12.5	98		0.01745	17.6	
¼"	6.3	97		0.01288	15.1	
No. 4	4.75	95		0.00907	12.6	
No. 10	2	86		0.00648	11.3	
No. 20	0.85	77		0.00458	10.1	
No. 40	0.425	64		0.00330	6.3	
No. 60	0.25	53		0.00233	5.0	
No. 100	0.15	43				
No. 200	0.075	33.0				



Particle Distribution: Gravel (3" - No. 4) **5.5%** Fines (0.075 - 0.005) **22.3%**
 Sand (No. 4 - No. 200) **61.5%** Clay (<0.005) **10.7%**

Comments: Moisture (%) = 7.2



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SW-SM
Material Source: B-5, 1S, 0.3-1.5'

Project Number: 19-1233
Lab ID: 4252M
Date Received: 4/30/2020
Date Completed: 5/11/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount (%)	Passing (%)
3"	76	100		0.06767	9.7	
2"	50	100		0.04879	7.7	
1½"	38.1	100		0.03528	6.3	
1"	25	95		0.03528	6.3	
¾"	19	90		0.02513	4.8	
½"	12.5	86		0.01796	3.9	
¼"	6.3	76		0.01305	3.4	
No. 4	4.75	67		0.00923	3.4	
No. 10	2	60		0.00653	2.9	
No. 20	0.85	49		0.00466	1.9	
No. 40	0.425	37		0.00333	1.5	
No. 60	0.25	24		0.00235	1.0	
No. 100	0.15	16				
No. 200	0.075	10.2				



Particle Distribution: Gravel (3" - No. 4) **32.9%** Fines (0.074 - 0.005) **7.8%**
 Sand (No. 4 - No. 200) **56.9%** Clay (<0.005) **2.4%**

Comments: Moisture (%) = 6.2



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-5, 1D, 1.5-3.5'

Project Number: 19-1233
Lab ID: 4253M
Date Received: 4/30/2020
Date Completed: 5/11/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount	Passing (%)
3"	76	100		0.06388	20.7	
2"	50	100		0.04576	19.2	
1½"	38.1	100		0.03303	16.3	
1"	25	100		0.03303	16.3	
¾"	19	100		0.02411	12.6	
½"	12.5	100		0.01704	11.8	
¼"	6.3	100		0.01288	9.6	
No. 4	4.75	97		0.00907	8.1	
No. 10	2	92		0.00648	6.7	
No. 20	0.85	80		0.00461	5.2	
No. 40	0.425	62		0.00330	3.7	
No. 60	0.25	48		0.00233	3.0	
No. 100	0.15	37				
No. 200	0.075	26.0				



Particle Distribution: Gravel (3" - No. 4) **2.8%** Fines (0.075 - 0.005) **20.1%**
 Sand (No. 4 - No. 200) **71.2%** Clay (<0.005) **5.9%**

Comments: Moisture (%) = 6.9



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-5, 2D, 4-6'

Project Number: 19-1233
Lab ID: 4254M
Date Received: 4/30/2020
Date Completed: 5/12/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06162	25.0	
2"	50	100		0.04478	22.2	
1½"	38.1	100		0.03235	20.0	
1"	25	100		0.03235	20.0	
¾"	19	100		0.02336	16.8	
½"	12.5	100		0.01672	15.0	
¼"	6.3	99		0.01235	13.6	
No. 4	4.75	95		0.00890	11.1	
No. 10	2	89		0.00636	9.3	
No. 20	0.85	80		0.00448	7.9	
No. 40	0.425	66		0.00320	6.4	
No. 60	0.25	52				
No. 100	0.15	40				
No. 200	0.075	29.1				



Particle Distribution: Gravel (3" - No. 4) **5.0%** Fines (0.075 - 0.005) **24.1%**
Sand (No. 4 - No. 200) **65.9%** Clay (<0.005) **5.0%**

Comments: Moisture (%) = 9.8



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: info@londonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-6, 1S, 0.3-1.5'

Project Number: 19-1233
Lab ID: 4255M
Date Received: 4/30/2020
Date Completed: 5/12/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06248	14.2	
2"	50	100		0.04576	12.0	
1½"	38.1	100		0.03303	10.3	
1"	25	95		0.03303	10.3	
¾"	19	91		0.02364	9.0	
½"	12.5	83		0.01704	7.3	
¼"	6.3	78		0.01273	6.0	
No. 4	4.75	66		0.00907	4.7	
No. 10	2	55		0.00648	3.9	
No. 20	0.85	46		0.00461	2.6	
No. 40	0.425	38		0.00326	2.1	
No. 60	0.25	28				
No. 100	0.15	21				
No. 200	0.075	15.1				



Particle Distribution: Gravel (3" - No. 4) **34.1%** Fines (0.074 - 0.005) **11.8%**
Sand (No. 4 - No. 200) **50.8%** Clay (<0.005) **3.3%**

Comments: Moisture (%) = 7.1



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-6, 1D, 1.5-3.5'

Project Number: 19-1233
Lab ID: 4256M
Date Received: 4/30/2020
Date Completed: 5/14/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount	Passing (%)
3"	76	100		0.06549	16.4	
2"	50	100		0.04785	13.3	
1½"	38.1	100		0.03450	10.7	
1"	25	100		0.03450	10.7	
¾"	19	97		0.02467	9.5	
½"	12.5	92		0.01764	7.6	
¼"	6.3	89		0.01312	5.7	
No. 4	4.75	83		0.00934	4.4	
No. 10	2	78		0.00667	2.8	
No. 20	0.85	70		0.00471	2.2	
No. 40	0.425	58				
No. 60	0.25	41				
No. 100	0.15	29				
No. 200	0.075	19.6				



Particle Distribution: Gravel (3" - No. 4) **16.7%** Fines (0.075 - 0.005) **17.1%**
Sand (No. 4 - No. 200) **63.7%** Clay (<0.005) **2.5%**

Comments: Moisture (%) = 6.7



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-7, 1S, 0.3-2'

Project Number: 19-1233
Lab ID: 4257M
Date Received: 4/30/2020
Date Completed: 5/12/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount	Passing (%)
3"	76	100		0.06388	16.6	
2"	50	100		0.04672	13.7	
1½"	38.1	100		0.03343	12.0	
1"	25	99		0.03343	12.0	
¾"	19	98		0.02411	10.3	
½"	12.5	95		0.01724	8.9	
¼"	6.3	92		0.01282	7.2	
No. 4	4.75	83		0.00916	5.7	
No. 10	2	73		0.00653	4.6	
No. 20	0.85	61		0.00461	3.4	
No. 40	0.425	48				
No. 60	0.25	35				
No. 100	0.15	25				
No. 200	0.075	18.6				



Particle Distribution: Gravel (3" - No. 4) **16.6%** Fines (0.075 - 0.005) **14.6%**
Sand (No. 4 - No. 200) **64.7%** Clay (<0.005) **4.0%**

Comments: Moisture (%) = 7.0



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com


Report of Hydrometer

ASTM D422-63 (07)

Project Name: Reconstruct Runway 35 End of Service Road
Project Location: Manchester-Boston Regional Airport
Client: Hoyle, Tanner & Associates, Inc.
Material Description: SM
Material Source: B-7, 1D, 2-4'

Project Number: 19-1233
Lab ID: 4258M
Date Received: 4/30/2020
Date Completed: 5/14/2020
Tested By: A. Michaud

Sieve Analysis				Hydrometer Analysis		
Sieve Size	Standard Designation (mm)	Amount Passing (%)	Specification (name)	Particle Size (mm)	Amount Passing (%)	
3"	76	100		0.06686	#N/A	
2"	50	100		0.04934	11.2	
1½"	38.1	100		0.03528	8.6	
1"	25	100		0.03528	8.6	
¾"	19	100		0.02540	6.5	
½"	12.5	97		0.01809	5.0	
¼"	6.3	95		0.01321	4.3	
No. 4	4.75	93		0.00944	3.6	
No. 10	2	90		0.00666	2.2	
No. 20	0.85	84		0.00471	1.4	
No. 40	0.425	68				
No. 60	0.25	45				
No. 100	0.15	27				
No. 200	0.075	15.5				



Particle Distribution: Gravel (3" - No. 4) **6.9%** Fines (0.075 - 0.005) **13.7%**
Sand (No. 4 - No. 200) **77.5%** Clay (<0.005) **1.8%**

Comments: Moisture (%) = 6.6



Reviewed By

13 Delta Drive, Unit 8, Londonderry, NH 03053 • P: (603) 716.2111 • F: (603) 716.2112 • E: infolondonderry@swcole.com

SOIL ANALYSIS

TEST BORING	DEPTH OF SAMPLE	GRADATION (% PASSING)										LL	PI	USC
		3"	2"	1"	3/4"	1/2"	3/8"	No. 4	No. 10	No. 40	No. 100	No. 200	% FINER THAN 0.02 mm ₁	
B-2	0.3-1.0'	100	100	94	91	87		69	55	37	25	20.2	12.0	SM
B-2	1-2'	100	100	100	95	87		76	69	51	29	20.0	9.0	SM
B-4	0.3-1.5'	100	100	84	80	71		58	49	33	18	12.8	6.7	SM
B-4	1.5-3.5'	100	100	100	100	98		95	86	64	43	33.0	18.5	SC-SM
B-5	0.3-1.5'	100	100	95	90	86		67	60	37	16	10.2	4.2	SW-SM
B-5	1.5-3.5'	100	100	100	100	100		97	92	62	37	26.0	12.1	SM
B-5	4-6'	100	100	100	100	100		95	89	66	40	29.1	15.9	SM
B-6	0.3-1.5'	100	100	95	91	83		66	55	38	21	15.1	8.1	SM
B-6	1.5-3.5'	100	100	100	97	92		83	78	58	29	19.6	8.2	SM
B-7	0.3-2'	100	100	99	98	95		83	73	48	25	18.6	9.5	SM
B-7	2-4'	100	100	100	100	97		93	90	68	27	15.5	5.4	SM

¹Note: "Percent finer than 0.02 mm" applies only when material is used above frost line

SUBGRADE CHARACTERISTICS

AVERAGE FROST PENETRATION DEPTH (in) 48	SUBSURFACE DRAINAGE		FROST DESIGN METHOD (choose one)			
	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	CP	LSP	RSS	NONE X
COMMENTS (Attach sketch showing location of borings) TEST BORING EXPLORATION RESULTS	SUBMITTED BY		TITLE		DATE	
	Chad B. Michaud, P.E.		Sen Geotech Eng.		5/19/2020	
	APPROVED BY		TITLE		DATE	
	APPROVED BY		FAA ENGINEER		DATE	

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

Item M-003 Stream Alteration and Permit Conditions

DESCRIPTION

003-1.1 This item shall consist of all stream alterations as described on the contract plans and within this specification item.

Refer to Appendix A of this item for New Hampshire Department of Environmental Services (NHDES) project specific conditions. A copy of the permit and the Rare Turtle pamphlet shall be posted in a secure manner in a prominent place at the site.

The Engineer will be responsible for all monitoring as detailed in items 18, 19 and 20 of the permit.

The Contractor shall be responsible for following project-specific condition items 1-17 and general condition items 1-10 listed in the permit.

MATERIALS

003-2.1 Stream Bed Native Materials. Stream simulation materials must be consistent with the bed materials identified in the reference reach, and shall be well-mixed with cobbles, gravels and fines that are washed in during installation to prevent subsurface stream flow. Stream bed materials shall not include angular riprap unless specifically identified on the approved plan and approved by the NHDES Wetlands Bureau.

003-2.2 Mulch. Mulch used within the area being restored shall be natural straw or equivalent non-toxic, non-seed-bearing organic material.

003-2.3 Rip Rap. Rip rap shall be NHDOT Class I and Class VII as shown on the contract drawings.

003-2.4 Wetland Seed Mix. Refer to Dwg. ER1.2 for wetland seed mix.

CONSTRUCTION METHODS

003-3.1 Stream Bed Native Materials. See Item T-905-1.

003-3.2 Dewatering. Refer to notes on Dwg. WI1.1 and in the permit conditions.

003-3.3 Invasive Species. Any excavate that isn't reused on site should be assumed to include invasive species seed and must be handled per the NHDOT Best Management Practices for the Control of Invasive and Noxious Plant Species (2018). There shall be no separate payment made for handline of invasive species, rather this shall be considered incidental to the unclassified excavation item.

003-3.4 Rip Rap. Rip rap shall adhere to NHDOT specification Section 583.

003-3.5 Wetland Seed Mix. See methods on the contract plans and in Item T-901 Seeding.

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

003-4.1 Stream Bed Native Material. Payment will be made at the contract unit price per square yard for native stream bed material obtained on site, measured in its original position and stripped or excavated. This price shall be full compensation for furnishing all materials and for all preparation,

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

placing and spreading of the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

003-4.2 Rip Rap Class I. Payment will be made at the contract unit price per square yard for Class I rip rap. This price shall be full compensation for furnishing all materials and for all preparation, placing and spreading of the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

003-4.3 Rip Rap Class VII. Payment will be made at the contract unit price per square yard for Class VII rip rap. This price shall be full compensation for furnishing all materials and for all preparation, placing and spreading of the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

003-4.4 Water Diversion. Payment will be made at the lump sum contract unit price for water diversion. This price shall be full compensation for furnishing all materials and for all preparation, placing and spreading of the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item in accordance with the contract plans, NHDOT permit conditions, and these specifications.

Payment will be made under:

Item M-003-1	Stream Bed Native Material	per square yard
Item M-003-2	Rip Rap Class I	per square yard
Item M-003-3	Rip Rap Class VII	per square yard
Item M-003-4	Water Diversion	per lump sum

END OF ITEM M-003

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

APPENDIX A

Wetlands And Non-Site Specific Permit 2021-03352

Seeking Reports of Rare Turtles Pamphlet

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

Item P-154 Subbase Course

DESCRIPTION

154-1.1 This item shall consist of a subbase course composed of granular materials constructed on a prepared subgrade or underlying course in accordance with these specifications, and in conformity with the dimensions and typical cross-section shown on the plans.

MATERIALS

154-2.1 Materials. The subbase material shall consist of hard durable particles or fragments of granular aggregates. The material may be obtained from gravel pits, stockpiles, or may be produced from a crushing and screening plant with proper blending. The materials from these sources shall meet the requirements for gradation, quality, and consistency. The material shall be free from vegetative matter, excessive amounts of clay, and other objectionable substances; uniformly blended; and be capable of being compacted into a dense, stable subbase.

The subbase material shall exhibit a California Bearing Ratio (CBR) value of at least 20 when tested in accordance with ASTM D1883. The subbase material shall meet the gradation specified in the table below.

Subbase Gradation Requirements

Sieve designation	Percentage by weight passing sieves	Contractor's Final Gradation	Job Control Grading Band Tolerances ¹ (Percent)
	Subbase Aggregate		
3 inch (75 mm)	100		0
1 1/2 inch (37.5 mm)			0
3/4 inch (19.0 mm)	70-100		±10
No. 10 (2.00 mm)	20-100		±10
No. 40 (425 µm)	5-60		±5
No. 200 (75 µm)	0-10		±5

¹The "Job Control Grading Band Tolerances" shall be applied to "Contractor's Final Gradation" to establish the job control grading band.

Manchester • Boston Regional Airport Rehabilitate Runway 17-35

The portion of the material passing the No. 40 (425 μ m) sieve shall have a liquid limit of not more than 25 and a plasticity index of not more than six (6) when tested in accordance with ASTM D4318.

154-2.2 Sampling and testing.

a. Aggregate base materials. Samples shall be taken by the Contractor per ASTM D75 for initial aggregate subbase requirements and gradation. Material shall meet the requirements in paragraphs 154-2.1. The Contractor shall submit to the Resident Project Representative (RPR) certified test results showing that the aggregate meets the Material requirements of this section. Tests shall be representative of the material to be used for the project.

b. Gradation requirements. The Contractor shall take at least [one] aggregate subbase sample per day in the presence of the RPR to check the final gradation. Samples shall be taken from the in-place, un-compacted material at sampling locations determined by the RPR on a random basis per ASTM D3665. Sampling shall be per ASTM D75 and tested per ASTM C136 and ASTM C117. Results shall be furnished to the RPR by the Contractor each day during construction. Material shall meet the requirements in paragraph 154-2.1.

154-2.3 Separation Geotextile. Not used.

154-2.4 Geogrid. Not used.

CONSTRUCTION METHODS

154-3.1 General. The subbase course shall be placed where designated on the plans or as directed by the RPR. The material shall be shaped and thoroughly compacted within the tolerances specified.

Granular subbases which, due to grain sizes or shapes, are not sufficiently stable to support the construction equipment without movement, shall be mechanically modified to the depth necessary to provide stability as directed by the RPR. The mechanical modification shall include the addition of a fine-grained medium to bind the particles of the subbase material sufficiently to furnish a bearing strength, so the course will not deform under construction equipment traffic.

154-3.2 Preparing underlying course. Prior to constructing the subbase course, clean the underlying course or subgrade of all foreign substances. The surface of the underlying course or subgrade shall meet specified compaction and surface tolerances in accordance with Item P-152. Correct ruts, soft yielding spots in the underlying courses, and subgrade areas having inadequate compaction and/or deviations of the surface from the specified requirements, by loosening and removing soft or unsatisfactory material, adding approved material, reshaping to line and grade, and recompacting to specified density requirements. For cohesionless underlying courses or subgrades containing sands or gravels, as defined in ASTM D2487, the surface shall be stabilized prior to placement of the overlying course by mixing the overlying course material into the underlying course, and compacting by approved methods. The stabilized material shall be considered as part of the underlying course and shall meet all requirements for the underlying course. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained in a satisfactory condition until the overlying course is placed. The underlying course shall be checked and accepted by the RPR before placing and spreading operations are started.

To protect the subgrade and to ensure proper drainage, spreading of the subbase shall begin along the centerline of the pavement on a crowned section or on the high side of pavements with a one-way slope.

154-3.3 Control Strip. The first half-day of subbase construction shall be considered as a control strip for the Contractor to demonstrate, in the presence of the RPR, that the materials, equipment, and construction processes meet the requirements of this specification. The sequence and manner of rolling necessary to obtain specified density requirements shall be determined. The maximum compacted thickness may be increased to a maximum of 12 inches (300 mm) upon the Contractor's demonstration

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

that approved equipment and operations will uniformly compact the lift to the specified density. The RPR must witness this demonstration and approve the lift thickness prior to full production.

Control strips that do not meet specification requirements shall be reworked, re-compacted, or removed and replaced at the Contractor's expense. Full operations shall not begin until the control strip has been accepted by the RPR. The Contractor shall use the same equipment, materials, and construction methods for the remainder of construction, unless adjustments made by the Contractor are approved in advance by the RPR.

154-3.4 Placement. The material shall be placed and spread on the prepared underlying layer by spreader boxes or other devices as approved by the RPR, to a uniform thickness and width. The equipment shall have positive thickness controls to minimize the need for additional manipulation of the material. Dumping from vehicles that require re-handling shall not be permitted. Hauling over the uncompacted base course shall not be permitted. The material shall not be placed when the underlying course is soft or yielding.

The material shall meet gradation and moisture requirements prior to compaction. Material may be free-draining and the minimum moisture content shall be established for placement and compaction of the material.

The material shall be constructed in lifts as established in the control strip, but not less than 4 inches (100 mm) nor more than 12 inches (300 mm) of compacted thickness.

When more than one lift is required to establish the layer thickness shown on the plans, the construction procedure described here shall apply to each lift. No lift shall be covered by subsequent lifts until tests verify that compaction requirements have been met. The Contractor shall rework, re-compact and retest any material placed which does not meet the specifications.

154-3.5 Compaction. The subbase material shall be compacted, adjusting moisture as necessary, to be within $\pm 2\%$ of optimum moisture. The field density of the compacted material shall be at least 100% of the maximum density as specified in paragraph 154-3.9a. If the specified density is not attained, the area of the lift represented by the test shall be reworked and/or re-compacted and additional random tests made. This procedure shall be followed until the specified density is reached. Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.

154-3.6 Weather limitation. Material shall not be placed unless the ambient air temperature is at least 40°F (4°C) and rising. Work on subbase course shall not be conducted when the subgrade is wet or frozen or the subbase material contains frozen material.

154-3.7 Maintenance. No base or surface course shall be placed on the subbase until the subbase has been accepted by the RPR. The Contractor shall maintain the completed course in satisfactory condition throughout placement of subsequent layers. When material has been exposed to excessive rain, snow, or freeze-thaw conditions, the Contractor shall verify that materials still meet all specification requirements before placement of additional material. Equipment may be routed over completed sections of subbase course, provided the equipment does not damage the subbase course and the equipment is routed over the full width of the completed subbase course. Any damage to the subbase course from routing equipment over the subbase course shall be repaired by the Contractor at their expense.

154-3.8 Surface tolerance. In those areas on which a subbase or base course is to be placed, the surface shall be tested for smoothness and accuracy of grade and crown. Any portion lacking the required smoothness or failing in accuracy of grade or crown shall be scarified to a depth of at least 3 inches (75 mm), reshaped and re-compacted to grade until the required smoothness and accuracy are obtained and approved by the RPR. The Contractor shall perform all final smoothness and grade checks in the presence of the RPR. Any deviation in surface tolerances shall be corrected by the Contractor at the Contractor's expense.

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

a. Smoothness. The finished surface shall not vary more than $\pm 1/2$ inch (12 mm) when tested with a 12-foot (3.7-m) straightedge applied parallel with and at right angles to the centerline. The straightedge shall be moved continuously forward at half the length of the 12-foot (3.7-m) straightedge for the full length of each line on a 50-foot (15-m) grid.

b. Grade. The grade and crown shall be measured on a 50-foot (15-m) grid and shall be within ± 0.05 feet (15 mm) of the specified grade.

154-3.9 Acceptance sampling and testing. The aggregate base course shall be accepted for density and thickness on an area basis. Two test shall be made for density and thickness for each 1200 square yards. Sampling locations will be determined on a random basis per ASTM D3665.

a. Density. The RPR shall perform all density tests.

Each area shall be accepted for density when the field density is at least 100% of the maximum density of laboratory specimens compacted and tested per ASTM D698. The in-place field density shall be determined per ASTM D6938 using Procedure A, the direct transmission method, and ASTM D6938 shall be used to determine the moisture content of the material. The machine shall be calibrated in accordance with ASTM D6938. If the specified density is not attained, the area represented by the failed test shall be reworked and/or recompacted and two additional random tests made. This procedure shall be followed until the specified density is reached. Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.

When the material has greater than 30 percent retained on the $3/4$ inch (19.0 mm) sieve, use methods in ASTM D698 and the procedures in AASHTO T180 Annex for correction of maximum dry density and optimum moisture for oversized particles.

b. Thickness. The thickness of the base course shall be within +0 and -1/2 inch (12 mm) of the specified thickness as determined by depth tests taken by the Contractor in the presence of the RPR for each area. Where the thickness is deficient by more than 1/2-inch (12 mm), the Contractor shall correct such areas at no additional cost by scarifying to a depth of at least 3 inches (75 mm), adding new material of proper gradation, and the material shall be blended and recompacted to grade. The Contractor shall replace, at his expense, base material where depth tests have been taken.

METHOD OF MEASUREMENT

154-4.1 Subbase course shall be measured by the number of cubic yards of subbase course material placed and compacted to specified density and plan thickness requirements in the completed course. The quantity of subbase course material shall be measured in final position based upon depth tests or cores taken as directed by the RPR, at the rate of two test per each 1200 square yards of subbase course. On individual depth measurements, thicknesses more than 1/2 inch (12 mm) in excess of that shown on the plans shall be considered as the specified thickness plus 1/2 inch (12 mm) in computing the yardage for payment. Subbase materials shall not be included in any other excavation quantities.

BASIS OF PAYMENT

154-5.1 Payment shall be made at the contract unit price per cubic yard for subbase course. This price shall be full compensation for furnishing all materials; for all preparation, hauling, and placing of these materials; and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-154-5.1	Subbase Course	per cubic yard
----------------	----------------	----------------

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C117	Standard Test Method for Materials Finer than 75- μm (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C136	Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D75	Standard Practice for Sampling Aggregates
ASTM D698	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft ³ (600 kN-m/m ³))
ASTM D1556	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D1557	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft ³ (2,700 kN-m/m ³))
ASTM D2487	Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D4253	Standard Test Methods for Maximum Index Density and Unit Weight of Soils Using a Vibratory Table
ASTM D4759	Practice for Determining the Specification Conformance of Geosynthetics
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D6938	Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)

American Association of State Highway and Transportation Officials (AASHTO)

M 288	Geotextile Specification for Highway Applications
-------	---

END OF ITEM P-154

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

Item F-163 Wildlife Deterrent Fence Skirt

DESCRIPTION

163-1.1 This item shall consist of furnishing and installing chain-link fence fabric underground along an existing chain link fence or wildlife fabric fence, constructing concrete pads at existing fence gates in accordance with these specifications and the details shown on the drawings and in conformity with the lines and grades shown on the plans or established by the RPR.

MATERIALS

163-2.1 Chain link fence fabric. The fabric shall be woven with a 9-gauge galvanized steel wire in a 2-inch (50 mm) mesh and shall meet the requirements of ASTM A392, Class II. The fabric shall be 5 feet (1.5 m) wide.

163-2.2 Barbed wire. Barbed wire shall be 2-strand 12-1/2 gauge zinc-coated wire with 4-point barbs and shall conform to the requirements of ASTM A121, Class 3.

163-2.3 Wire ties and tension wires. Wire fabric ties, wire ties, and tension wire for a given type of fabric shall be the same material as the fabric type. The tension wire shall be 7-gauge coiled spring wire coated similarly to the respective wire fabric being used.

Wire fabric ties shall be hog rings of galvanized steel wire not less than 9-gauge.

All material shall conform to Federal Specification RR-F-191/4.

163-2.4 Miscellaneous fittings and hardware. Miscellaneous steel fittings and hardware for use with zinc-coated steel fabric shall be of commercial grade steel or better quality, wrought or cast as appropriate to the fitting or hardware, and sufficient in strength to provide a balanced design when used with fabric, posts, and wires of the specified quality. All steel fittings and hardware shall be protected with a zinc coating applied in conformance with ASTM A153.

163-2.5 Concrete pads at gates. Concrete shall be of a commercial grade with a minimum 28-day compressive strength of 3,000 psi (2670 kPa).

163-2.6 Marking. Each roll of fabric shall carry a tag showing the kind of base metal, kind of coating, the gauge of the wire, the length of fencing in the roll, and the name of the manufacturer. Posts, wire, and other fittings shall be identified as to manufacturer, kind of base metal, and kind of coating.

163-2.7 Weed control material. A commercially available weed control material shall be applied at the manufacturer's recommended rate.

CONSTRUCTION METHODS

163-3.1 General. The fence shall be constructed in accordance with the details on the plans and as specified here using new materials. All work shall be performed in a workmanlike manner satisfactory to the RPR. The Contractor shall layout the fence line based on the plans. The work shall progress in this manner and at the close of the working day the newly constructed fence shall be tied to the existing fence.

163-3.2 Clearing fence line. All brush, stumps, logs, and other debris which would interfere with the construction of the fence shall be removed on either side of the fence centerline before starting fencing

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

operations. The material removed and disposed of shall not constitute a pay item and shall be considered incidental to fence construction.

163-3.3 Installing fabric. Excavate ground to the depth required for proper installation of the fabric. Obtain RPR's approval of depth of excavation before placing the wire fabric. Place the fabric and lap splice it to existing fence fabric and tie with wire ties at 2-foot (0.6-m) spacing. Cut wire fabric around fence post footing to allow proper placement. Backfill with native soil to original grade and compact. Gate concrete pads shall be installed at each gate or as shown on the plans.

163-3.4 Weed control application. Weed control material shall be applied over an area 5 feet (1.5 m) wide, measured from the fence centerline, and over the wildlife fence. Apply weed control material as recommended by the manufacturer's instructions and in compliance with state and local regulations.

163-3.5 Electrical grounds. Electrical grounds shall be constructed **at 500 feet (150 m) intervals and as specified on the contract plans**. The ground shall be accomplished with a copper clad rod 8 feet (2.4 m) long and a minimum of 5/8 inches (16 mm) in diameter driven vertically until the top is 6 inches (150 mm) below the ground surface. A No. 6 solid copper conductor shall be clamped to the rod and to the fence in such a manner that each element of the fence is grounded. Installation of ground rods shall not constitute a pay item and shall be considered incidental to fence construction. The Contractor shall comply with FAA-STD-019, Lightning and Surge Protection, Grounding, Bonding and Shielding Requirements for Facilities and Electronic Equipment, paragraph 4.2.3.8, Lightning Protection for Fences and Gates, when fencing is adjacent to FAA facilities.

163-3.6 Cleaning up. The Contractor shall remove from the vicinity of the completed work all tools, buildings, equipment, etc., used during construction. All disturbed areas shall be seeded per Item T-901.

METHOD OF MEASUREMENT

163-4.1 Chain link fence with wildlife deterrent. Chain-link fence with wildlife deterrent shall be measured for payment by the linear foot to the nearest foot. Measurement shall be along the fence from center to center of end or corner posts, excluding the length occupied by gate openings. All fencing shall comply with Item F-162 of these specifications.

163-4.1 Fence Removal. Chain-link fence removal shall be measured for payment by the linear foot to the nearest foot. Measurement shall be along the fence from center to center of end or corner posts, excluding the length occupied by gate openings. Payment shall include restoring the area, including excavation of posts and foundations, backfill and disposal of all materials. Seeding and topsoil included in this item if outside the area of unclassified excavation, otherwise seeding and topsoil will be paid for under T-901 and T-905.

BASIS OF PAYMENT

163-5.1 Chain link fence with wildlife deterrent. Payment for chain-link fence with wildlife deterrent shall be made at the contract unit price per linear foot. This price shall be full compensation for furnishing materials, all labor (including preparation, excavation, backfill, fill, and installation), equipment, tools, and incidentals necessary to complete this item.

163-5.2 Fence Removal. Payment for chain-link fence removal shall be made at the contract unit price per linear foot. This price shall be full compensation for furnishing materials, all labor (including preparation, excavation, and backfill), equipment, tools, and incidentals necessary to complete this item.

**Manchester • Boston Regional Airport
Rehabilitate Runway 17-35**

Payment will be made under:

Item F-163-1	Chain link Fence with Wildlife Deterrent	per linear foot
Item F-163-2	Remove Fence	per linear foot

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM A121	Standard Specification for Metallic-Coated Carbon Steel Barbed Wire
ASTM A153	Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A392	Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric

Federal Specifications (FED SPEC)

FED SPEC RR-F-191/4 Fencing, Wire and Post, Metal (Chain-Link Fence Accessories)
--

FAA Standard

FAA-STD-019	Lightning and Surge Protection, Grounding, Bonding and Shielding Requirements for Facilities and Electronic Equipment
-------------	---

FAA Orders

5300/38	AIP Handbook
---------	--------------

END OF ITEM F-163

MANCHESTER - BOSTON REGIONAL AIRPORT (MHT)

MANCHESTER, NEW HAMPSHIRE

CONSTRUCTION PLANS FOR REHABILITATE RUNWAY 17-35

AIP NO. 3-33-0011-TBD-2022

CITY BID NO. FY22-805-49

VOLUME 1 : REHABILITATE RUNWAY 17-35

VOLUME 2 : REHABILITATE EXISTING MALS AND ALSF-2 LIGHTING SYSTEMS


**VOLUME 3 : REHABILITATE MECHANICALLY STABILIZED EARTH RETAINING WALL
AND RELATED IMPROVEMENTS**

VOLUME 4 : RECONSTRUCT AND REHABILITATE A PORTION OF THE SERVICE ROAD



One Airport Road, Suite 300
Manchester, New Hampshire 03103
www.flymanchester.com

AUTHORITY / OWNER



LOCATION MAP

Jacobs

2 Executive Park Drive, Suite 205
Bedford, NH 03110
(603) 666-7181 fax-(603) 666-7185

PROJECT DESIGNER

**ISSUED FOR BID
MARCH 2022**

Jacobs - V:\nhh10\1job\2021\LE2X89205 - MHT RW 17-35\700 CADD\G003_General Notes.dwg [G-003] March 30, 2022 - 10:08am [dantorelli]

PROJECT GENERAL NOTES:

THESE NOTES ARE INTENDED TO HIGHLIGHT THE REQUIREMENTS SET FORTH IN THE PROJECT SPECIFICATIONS. IN ALL CASES REQUIREMENTS OF THE PROJECT SPECIFICATIONS SHALL GOVERN.

WEEKLY AND DAILY SCHEDULES REQUIRED

- 1. THIS PROJECT IS LOCATED ADJACENT TO ACTIVE TAXIWAYS AND RUNWAYS, THEREFORE ALL CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED IN A MANNER ACCEPTABLE TO THE RESIDENT PROJECT REPRESENTATIVE (RPR), AIRPORT OPERATIONS AND THE FEDERAL AVIATION ADMINISTRATION (FAA) TO PROVIDE ACCEPTABLE LEVELS OF SAFETY FOR ALL AIRPORT OPERATIONS. PERIODIC MEETINGS WILL BE HELD TO COORDINATE THE ACTIVITIES OF THIS CONTRACT WITH OTHER AIRPORT OPERATIONS.
- 2. THE CONTRACTOR SHALL PREPARE AND SUBMIT A WEEKLY SCHEDULE OF OPERATIONS FOR THE FOLLOWING WORK WEEK. THE SCHEDULE SHALL BE GIVEN TO THE RPR AT THE END OF THE WORK WEEK PRECEDING THE WORK WEEK COVERED BY THE SCHEDULE. THE WEEKLY SCHEDULES ARE SUBJECT TO APPROVAL OF THE RPR. THE CONTRACTOR SHALL UPDATE THE RPR PRIOR TO THE START OF WORK EACH DAY OF CONSTRUCTION ACTIVITIES FOR THE NEXT 24 HOUR PERIOD.
- 3. THE CONTRACTOR SHALL SUBMIT A SAFETY PHASING PLAN UPON NOTIFICATION OF AWARD. THE CONTRACTOR'S SAFETY PLAN SHALL BE IN CONFORMANCE WITH THE CONSTRUCTION SAFETY AND PHASING PLAN INCLUDED IN THE PROJECT MANUAL. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN THIS MANUAL.

ENVIRONMENTAL PROTECTION

- 1. THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE AND LOCAL LAWS AND REGULATIONS CONTROLLING POLLUTION OF THE ENVIRONMENT. THE CONTRACTOR SHALL IMPLEMENT ALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE NEW HAMPSHIRE STORMWATER MANUAL VOLUME 3 EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EROSION CONTROL MEASURES AT NO EXTRA COST WHEN INSTRUCTED BY THE RPR AND COMPLYING WITH EPA 2022 CONSTRUCTION GENERAL PERMIT, IF APPLICABLE, DURING CONSTRUCTION.
- 2. HAUL ROUTES AND ROADS USED BY THE CONTRACTOR FOR ACCESS OR HAULING SHALL BE KEPT CLEAN AND ACCESSIBLE TO ALL OTHER AIRPORT TRAFFIC FOR THE ENTIRE DURATION OF THE PROJECT. HAUL TRUCKS AND DUMP TRUCKS MUST USE LOAD COVERS AND MUST BE LOADED BY THE CONTRACTOR SUCH THAT NO SPILLAGE OCCURS DURING TRANSIT ON THE STATE, MUNICIPAL, OR AIRPORT ROADWAYS, RUNWAYS, TAXIWAYS, AND APRONS. NO SEPARATE PAYMENT SHALL BE MADE FOR KEEPING THE HAUL ROUTES AND ROADS CLEAR AND ACCESSIBLE.
- 3. THE CONTRACTOR SHALL CONTROL DUST AND DEBRIS FROM HIS OPERATION TO A LEVEL ACCEPTABLE TO THE RPR AND HAVE ON THE PROJECT SITE AT ALL TIMES TWO VACUUM SWEEPERS, WATERING TRUCKS, AND OTHER EQUIPMENT NECESSARY TO CONTROL DUST AT ALL TIMES. ALL METHODS FOR CONTROLLING DUST SHAL BE SUBJECT TO THE RPR APPROVAL. DUST CONTROL SHALL BE STRICTLY MONITORED DUE TO ITS IMPACT ON AIRCRAFT SAFETY. FAILURE TO PROPERLY CONTROL DUST OR RESPOND TO ANY REQUEST TO DO SO WILL RESULT IN CONSTRUCTION ACTIVITIES BEING STOPPED.

CONTRACTOR'S MATERIAL STAGING AREA

- 1. THE CONTRACTOR SHALL USE THE AREA SHOWN ON THE PLANS FOR THE MATERIAL AND EQUIPMENT STAGING AREA. THE CONTRACTOR IS RESPONSIBLE FOR ANY AND ALL IMPROVEMENT OF THE DESIGNATED AREA, THAT IS NECESSARY FOR THE UTILIZATION OF THE AREA. THE CONTRACTOR SHALL BE PREPARED TO CONDUCT WEEKLY CLEANING OF THE STAGING AREA. THE CONTRACTOR SHALL CONTROL DUST IN THE STAGING AREA. THE CONTRACTOR IS RESPONSIBLE FOR RESTORING TO ORIGINAL CONDITION ANY AREAS USED FOR THE CONTRACTOR'S OPERATION AND CONTROLLING DUST AT NO ADDITIONAL COST TO THE OWNER. THERE WILL BE NO SEPARATE PAYMENT FOR THIS WORK. ALL WORK NECESSARY TO USE THE STAGING AREA SHALL BE DEEMED INCIDENTAL TO THE OVERALL PROJECT COST.
- 2. THE CONTRACTOR, WITH THE APPROVAL OF THE RPR AND AIRPORT OPERATIONS, SHALL ESTABLISH THE EXACT LIMITS OF THE CONTRACTOR'S STAGING AREAS AT THE LOCATIONS DESIGNATED ON THE CONTRACT DRAWINGS FOR MATERIAL STOCKPILING. ALL REQUIRED UTILITIES FOR THE CONTRACTOR'S STAGING AREA SHALL BE ARRANGED AND PROMPTLY PAID FOR BY THE CONTRACTOR DIRECTLY WITH THE APPROPRIATE UTILITY AGENCY. UTILITY ARRANGEMENTS SHALL BE SUBJECT TO THE APPROVAL OF THE RPR. NO SEPARATE PAYMENT SHALL BE MADE FOR ANY ITEM REQUIRED FOR THE CONTRACTOR TO ENCLOSE AND SET UP HIS OPERATIONAL AREAS. ADDITIONALLY, THE CONTRACTOR SHALL RESTORE THE SITES TO THE ORIGINAL CONDITIONS UPON COMPLETION OF THE CONTRACT WORK, TO THE SATISFACTION OF THE RPR AND AIRPORT OPERATIONS, AT NO ADDITIONAL COST TO THE OWNER.
- 3. ALL MATERIALS AND EQUIPMENT SHALL BE STORED AND PARKED, WHEN NOT IN USE, AT THE CONTRACTOR'S STORAGE AREAS SHOWN ON THE PLANS. TEMPORARY STOCKPILES SHALL BE CONTAINED WITH PERIMETER CONTROLS AND SEEDED, AS NEEDED. REFER TO DETAIL 5 ON SHEET C-621 FOR ADDITIONAL INFORMATION.
- 4. STOCKPILED MATERIAL SHALL BE CONSTRAINED IN A MANNER TO PREVENT ITS MOVEMENT BY WIND, JET BLAST, OR PROPELLER WASH.
- 5. THE MAXIMUM ALLOWABLE HEIGHT OF CONSTRUCTION EQUIPMENT IN STAGING AREA IS 20' ABOVE GROUND SURFACE. THE CONTRACTOR SHALL OBTAIN PERMISSION FROM THE RPR FOR ANY EQUIPMENT THAT WILL EXCEED 20' IN HEIGHT AND IMPACT THE F.A.R. PART 77 SURFACE.

HAUL ROADS

- 1. THE CONTRACTOR'S ACCESS ROUTE TO THE PROJECT SITES LOCATED AT THE AIRPORT IS AS SHOWN ON SHEET G-004 CONSTRUCTION ACCESS PLAN AND NOTES.
- 2. ALL PAVED HAUL ROADS OR ACCESS ROADS SHALL BE KEPT CLEAN AT ALL TIMES TO PREVENT THE ACCUMULATION OF DIRT AND MUD AND THE GENERATION OF DUST BY VACUUMING, WASHING, WATERING OR OTHER METHODS DIRECTED BY THE AIRPORT OPERATIONS.
- 3. UNPAVED HAUL ROADS, IF ANY, SHALL BE MAINTAINED BY BLADING AND FILLING WHEN DIRECTED BY THE RPR. DUST SHALL BE CONTROLLED AT ALL TIMES.
- 4. ALL HAUL ROADS DISTURBED SHALL BE RESTORED TO THEIR ORIGINAL CONDITION OR BETTER BEFORE THE CONTRACT WILL BE CONSIDERED COMPLETE. ALL RESTORATION AND DUST CONTROL ON HAUL ROADS SHALL BE AT THE CONTRACTOR'S EXPENSE AND ARE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT COST.

FLAGGERS

- 1. THE USE OF AIRFIELD FLAGGERS WILL NOT BE REQUIRED ON THIS PROJECT. THE OWNER WILL PROVIDE ESCORTS ACROSS ACTIVE AIRPORT PAVEMENTS. CONTRACTOR RESPONSIBLE FOR PROVIDING ANY FLAGGERS REQUIRED FOR ENTERING OR EXITING ON PUBLIC ROADWAYS. NO ADDITIONAL PAYMENT WILL BE MADE FOR FLAGGERS RATHER IT SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT COST.

RADIO CONTROL

- 1. THE CONTRACTOR SHALL HAVE TWO-WAY RADIO COMMUNICATION BETWEEN THE RADIO CONTROL VEHICLE AND HIS/HER FIELD OFFICE, SUPERINTENDENT'S VEHICLE, RPR, FLAG PERSONS, AND AIRPORT OPERATIONS ESCORT VEHICLES. NO FAA FREQUENCY WILL BE USED FOR THIS PURPOSE. THESE RADIOS SHALL BE MAINTAINED AND OPERATED AT THE CONTRACTOR'S EXPENSE.

UNDERGROUND UTILITIES, CABLES, AND EXISTING STRUCTURES

- 1. THE APPROXIMATE LOCATIONS OF KNOWN UTILITIES AND UNDERGROUND CABLES ARE SHOWN ON THE DRAWINGS. PRIOR TO COMMENCEMENT OF ANY EXCAVATION THE CONTRACTOR SHALL COORDINATE ALL WORK ON AND IN THE VICINITY OF THE UNDERGROUND UTILITIES AND CABLES WITH THE FOLLOWING AGENCIES AS APPROPRIATE.
 - 1.1. DIG SAFE: 811 OR (888) 344-7233
 - 1.2. CONSOLIDATED COMMUNICATIONS: (844) 968-7224
 - 1.3. COMCAST: (603) 889-6718
 - 1.4. NATIONAL GRID: (800) 233-5325
 - 1.5. EVERSOURCE: (800) 362-7764
 - 1.6. THE FEDERAL AVIATION ADMINISTRATION - TECH OPS: (603) 621-1762
 - 1.7. AIRPORT - OPERATIONS AND MAINTENANCE: (603) 624-6349
 - 1.8. TOWN OF LONDONDERRY - WATER AND SEWER DEPARTMENTS:(603) 624-6494
- 2. THE CONTRACTOR SHALL SUBMIT THE DIG SAFE REFERENCE NUMBER TO THE RPR AFTER EACH DIG SAFE REQUEST. DIG SAFE REFERENCE NUMBERS SHALL BE UPDATED EVERY 30 DAYS. THE CONTRACTOR SHALL BE AWARE OF ALL PERMITS AND THEIR ASSOCIATED EXPIRATION DATE. THE CONTRACTOR SHALL MAINTAIN ALL REQUIRED PERMITS THROUGHOUT THE CONSTRUCTION DURATION.
- 3. CONTRACTOR SHALL HIRE A PRIVATE UTILITY LOCATION SERVICE TO MARK OUT ANY UTILITIES NOT COVERED BY DIGSAFE.
- 4. WORK AROUND THE EXISTING UNDERGROUND UTILITIES SHALL BE PERFORMED IN A MANNER THAT WILL AVOID DAMAGES TO THE UTILITIES. PRIOR TO COMMENCING WITH WORK, THE CONTRACTOR SHALL ACCURATELY LOCATE OR GET THE APPROPRIATE UTILITY COMPANY TO LOCATE ABOVE AND BELOW GROUND UTILITIES WHICH MAY BE AFFECTED BY THE WORK. THE CONTRACTOR SHALL PROTECT ALL UTILITIES NOT DESIGNATED FOR REMOVAL, RELOCATION, OR REPLACEMENT IN THE COURSE OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE 72 HOURS OF ADVANCED NOTICE TO THE UTILITY OWNER, THE RPR, AND FAA PRIOR TO BEGINNING CONSTRUCTION IN THE VICINITY OF THE EXISTING UTILITY LINE.
- 5. PRIOR TO THE CLOSE OF WORK EACH DAY, THE CONTRACTOR SHALL VERIFY THAT ALL LIGHTING CIRCUITS IN THE WORK AREA ARE OPERATIONAL.
- 6. THE CONTRACTOR SHALL REPAIR AT HIS/HER OWN EXPENSE, ANY UNDERGROUND CABLES OR UTILITIES DAMAGED BY THE CONTRACTOR'S OPERATIONS INCLUDING ANY DAMAGE DONE BY DRIVING HIS/HER EQUIPMENT OVER EXISTING UNDERGROUND CABLES OR UTILITIES. THE REPAIR OF FAA CABLES SHALL BE INSPECTED AND APPROVED BY THE FAA.
- 7. THE CONTRACTOR SHALL PROTECT ALL NAVAIDS, EDGE LIGHTS, ELECTRICAL MANHOLES, JUNCTION CANS, DRAINAGE INLETS AND MANHOLES DURING CONSTRUCTION. ANY DAMAGE TO THE EXISTING STRUCTURES DURING CONSTRUCTION MUST BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE
- 8. THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS AND DIMENSIONS IN THE FIELD PRIOR TO COMMENCING WITH ANY FABRICATION, ORDERING OF MATERIAL, OR PERFORMING WORK. THE CONTRACTOR SHALL NOTIFY THE RPR IMMEDIATELY OF ANY CONDITIONS OR DIMENSIONS THAT WOULD HAMPER THE PERFORMANCE OF THE WORK, IN ACCORDANCE WITH THE CONTRACT DRAWINGS AND SPECIFICATIONS.
- 9. INTERRUPTION TO EXISTING AIRFIELD UTILITIES SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND/OR AT THE DIRECTION OF THE RPR.

MAINTENANCE OF THE CONSTRUCTION SITE

- 1. THE CONTRACTOR SHALL MAINTAIN THE PROJECT SITE TO PREVENT ATTRACTION OF WILDLIFE. THE CONTRACTOR SHALL KEEP ALL TRASH RECEPTACLES CLOSED AND ELIMINATE PONDING OF WATER TO ELIMINATE ATTRACTING BIRDS AND OTHER WILDLIFE.
- 2. THE CONTRACTOR SHALL KEEP THE CONSTRUCTION SITE FREE OF PAPER, BOXES, AND OTHER DEBRIS, WHICH COULD BE BLOWN ONTO THE RUNWAY AND TAXIWAYS.
- 3. ALL AIRPORT PAVEMENTS SHALL BE KEPT CLEAR AND CLEAN AT ALL TIMES. ALL ROCKS, MUD, AND OTHER DEBRIS CARRIED ONTO THE AIRPORT PAVEMENT BY THE CONTRACTOR'S EQUIPMENT MUST BE REPORTED TO THE RPR OR TO AIRPORT OPERATIONS. THE AIRPORT OPERATIONS WILL THEN CLOSE THE AFFECTED AREA TO AIR TRAFFIC AND THE CONTRACTOR WILL IMMEDIATELY SWEEP THE AREA TO THE SATISFACTION OF AIRPORT OPERATIONS OR RPR.
- 4. THE CONTRACTOR SHALL MAINTAIN, AT THE CONSTRUCTION SITE, THE EQUIPMENT FOR THE APPLICATION OF WATER TO CONTROL DUST WITHIN THE CONSTRUCTION SITE AND ON HAUL ROADS. THE EQUIPMENT SHALL BE EQUIPPED WITH A SHUTOFF CONTROL VALVE WHICH CAN BE OPERATED FROM THE CAB BY THE OPERATOR. THE CONTRACTOR SHALL APPLY WATER FOR DUST CONTROL AS NECESSARY TO PREVENT DUST FROM LEAVING THE CONSTRUCTION SITE AND/OR HAUL ROADS AND BEING A HAZARD TO AIRCRAFT AND THE PUBLIC. THE RPR MAY DIRECT THE IMPLEMENTATION OF DUST CONTROL. THE COST OF ALL WATER AND OTHER DUST CONTROL MEASURES WILL NOT BE PAID FOR SEPARATELY, RATHER IT SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT COST.

- 5. THE CONTRACTOR SHALL MAINTAIN AT THE JOB SITE AT ALL TIMES WHILE THE CONSTRUCTION UNDER THIS CONTRACT IS IN PROGRESS, A SELF-PROPELLED, SELF-CONTAINED SWEEPER WITH NOT LESS THAN A 10-FOOT BROOM WITH A 4 CUBIC YARD CAPACITY APPROVED BY THE RPR. THE SWEEPER SHALL OPERATE AS NECESSARY TO KEEP ACTIVE AIRCRAFT PAVEMENTS, ACCESS ROADS AND THE WORK AREAS CLEAN. AT THE CLOSE OF EACH WORKDAY, ALL ACTIVE AIRCRAFT PAVEMENTS AND THE AIRPORT PAVED ROADS USED OR SOILED BY THE CONTRACTOR SHALL BE SWEPT. ALL COSTS ASSOCIATED WITH THIS ITEM SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 6. THE CONTRACTOR SHALL ESTABLISH A SYSTEM OF VISUAL AIDS FOR MARKING AND DELINEATING THE LIMITS OF REQUIRED CLEARANCES ADJACENT TO ACTIVE TAXIWAYS, RUNWAYS, AND NAVIGATIONAL AIDS DURING CONSTRUCTION. THE SYSTEM SHALL BE EASILY DISTINGUISHABLE DURING BOTH DAY AND NIGHTTIME WORK. A DETAILED PLAN OF MATERIALS AND PROCEDURES THAT THE CONTRACTOR PROPOSES TO USE SHALL BE SUBMITTED TO THE RPR FOR APPROVAL PRIOR TO THE START OF ANY WORK UNDER THIS CONTRACT COMPLIANCE WITH THE APPROVED PLAN WILL BE STRICTLY ENFORCED. THIS PLAN, ALONG WITH ALL TEMPORARY VISUAL AIDS AS NOTED, SHALL BE IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G, OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION, DATED 12/13/17. THE RPR MAY REQUIRE CHANGES TO THE ESTABLISHED PLAN WHENEVER IT IS NECESSARY FOR THE PROTECTION OF AIRPORT OPERATIONS. THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE SPECIFICATIONS FOR FURTHER INFORMATION REGARDING RESTRICTIONS AND PENALTIES.

DISPOSAL OF SURPLUS AND UNSUITABLE MATERIALS

- 1. UNLESS OTHERWISE STATED, ALL SURPLUS MATERIALS AND UNSUITABLE MATERIALS INCLUDING MILLINGS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND LEGALLY DISPOSED OF OFF AIRPORT PROPERTY. NO SEPARATE MEASUREMENT AND PAYMENT WILL BE MADE FOR THE DISPOSAL, BUT RATHER THE DISPOSAL SHALL BE INCIDENTAL TO THE ITEM WHICH PRODUCED THE SURPLUS MATERIAL.
- 2. ALL EQUIPMENT, MANPOWER, TRAFFIC CONTROL, SIGNS, BARRICADES, GATES AND OTHER ITEMS NECESSARY FOR THE SAFE AND EFFICIENT HAULING OF EXCESS MATERIALS IS THE RESPONSIBILITY OF THE CONTRACTOR AND INCIDENTAL TO THE COST OF THE ITEM WHICH GENERATED THE MATERIAL TO BE DISPOSED OF.
- 3. ALL SURPLUS LOAM SHALL BE TURNED OVER TO THE AIRPORT AT A STOCKPILE LOCATION ON AIRPORT PROPERTY. FINAL LOCATION ON AIRPORT PROPERTY OF STOCKPILE TO BE DETERMINED DURING CONSTRUCTION.
- 4. ALL TAXIWAY LIGHT FIXTURES AND SIGN FIXTURES TEMPORARILY REMOVED SHALL BE STORED AT THE AIRPORT MAINTENANCE FACILITY, TO BE REINSTALLED BY THE CONTRACTOR.
- 5. THE CONTRACTOR SHALL HAUL ALL EXCAVATED / DEMOLISHED MATERIALS AND MILLED ASPHALT MATERIALS OFF AIRPORT PROPERTY FOR LEGAL DISPOSAL. THE CONTRACTOR MAY STOCKPILE ONE WORK SHIFT'S WORTH OF DEMOLISHED ASPHALT MATERIALS AND EXCAVATED MATERIAL IN THE STAGING AREA AT A TIME. THE DEMOLISHED ASPHALT MATERIALS AND EXCAVATED MATERIALS MUST BE HAULED OFFSITE THE FOLLOWING DAY PRIOR TO THE NEXT WORK SHIFT COMMENCING. THERE SHALL NOT BE MORE THAN ONE WORK SHIFT'S WORTH OF DEMOLISHED ASPHALT MATERIAL AND EXCAVATED MATERIAL STOCKPILED IN THE STAGING AREA UNLESS OTHERWISE APPROVED BY THE RPR.

OPEN TRENCHES OR EXCAVATIONS

- 1. ALL CONSTRUCTION ACTIVITIES WITHIN OR ADJACENT TO RUNWAYS, TAXIWAYS, APRONS, PROTECTED SURFACES AND NAVIGABLE AIRSPACE SHALL COMPLY WITH CURRENT 14 CFR PART 139 AND 14 CFR PART 77 REQUIREMENTS, ADVISORY CIRCULAR A/C NO. 150/5370-2 (CURRENT VERSION) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", AND AIRPORT OPERATIONAL REQUIREMENTS.
- 2. OPEN TRENCHES, EXCAVATIONS AND STOCKPILED MATERIALS SHALL BE PROMINENTLY MARKED. THESE OBSTACLES SHALL BE PROMINENTLY LIGHTED DURING HOURS OF RESTRICTED VISIBILITY AND DARKNESS.

GENERAL PROJECT COORDINATION NOTES

- 1. UNLESS OTHERWISE NOTED, WORK WITHIN ANY AIRPORT SAFETY AREAS SHALL REQUIRE A TAXIWAY OR RUNWAY CLOSURE UNLESS OTHERWISE NOTED IN THE PLANS. THE CONTRACTOR, THROUGH THE RPR AND AIRPORT OPERATIONS, MUST REQUEST TAXIWAY AND RUNWAY CLOSURES. THESE REQUESTS MUST BE MADE 72 HOURS IN ADVANCE AND INDICATE THE AREAS NEEDED AND A SCHEDULE OF OPERATIONS AND TIME(S) REQUIRED FOR OPERATIONS WITHIN THE AREA. ALL TAXIWAY AND RUNWAY CLOSURE REQUESTS ARE CONTINGENT ON REVIEW AND APPROVAL BY THE RPR AND AIRPORT OPERATIONS. THE AIRPORT RESERVES THE RIGHT TO SHIFT ANY APPROVED SCHEDULED CLOSURE PERIODS TO ALLEVIATE AIRCRAFT CONGESTION WHEN WEATHER CONDITIONS DICTATE.
- 2. THE CONTRACTOR SHALL COOPERATE WITH OTHER CONTRACTORS WORKING IN THE AREA AND AT ALL TIMES WILL COORDINATE HIS OR HER EFFORTS TO MAINTAIN THE NECESSARY CONSTRUCTION ACCESS ROUTES AND TO ASSURE THAT ALL CONTRACTS CONTINUE ON A TIMELY BASIS.
- 3. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL LAWS AND REGULATIONS THAT ARE PERTINENT TO THIS WORK. THE CONTRACTOR SHALL HAVE THE RESPONSIBILITY TO OBTAIN AND PAY ALL COSTS ASSOCIATED WITH THE PERMITS AND LICENSES REQUIRED TO ACCOMPLISH THIS WORK.
- 4. OPEN FLAME WELDING OR TORCH CUTTING OPERATIONS ARE PROHIBITED UNLESS ADEQUATE FIRE SAFETY PRECAUTIONS ARE PROVIDED AND THESE OPERATIONS HAVE BEEN AUTHORIZED BY THE AIRPORT. IF THESE ACTIVITIES ARE REQUIRED, THE CONTRACTOR MUST COORDINATE WITH AIRPORT OPERATIONS IN ADVANCE SO THAT THE LIMITATIONS AND REQUIREMENTS CAN BE IDENTIFIED AS WELL AS ANY ADDITIONAL AIRPORT PROCEDURES COMPLETED.
- 5. THE CONTRACTOR SHALL COMPLY WITH ALL CURRENT VEHICLE OPERATIONAL ORDERS AND INSTRUCTIONS PROVIDED BY THE FAA AND ATCT. THE ORDERS AND INSTRUCTIONS ARE CONTAINED IN THE CONSTRUCTION SAFETY AND PHASING PLAN (CSPP) IN THE PROJECT MANUAL. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE SURE ALL THE SUBCONTRACTORS, SUPPLIERS, VENDORS, ETC. RECEIVE AND COMPLY WITH THE REQUIREMENTS IN THESE PUBLICATIONS.

- 6. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL SUBMIT TO THE RPR A NAME AND PHONE NUMBER OF TWO INDIVIDUALS WHO WILL BE AVAILABLE ON A 24 HOUR CALL BASIS FOR EMERGENCY BARRICADE AND BARRICADE LIGHTING MAINTENANCE. THESE INDIVIDUALS SHALL PROVIDE MAINTENANCE AND REPAIR OF TEMPORARY ELECTRICAL SYSTEMS AND WIRING.

GENERAL PROJECT SECURITY NOTES

- 1. ALL PERSONS ENTERING THE SECURITY IDENTIFICATION DISPLAY AREA (SIDA) ARE REQUIRED TO DISPLAY AN IDENTIFICATION BADGE ISSUED BY THE AIRPORT OR TO BE ESCORTED AT ALL TIMES BY AN APPROVED ESCORT DISPLAYING AN AIRPORT-ISSUED IDENTIFICATION BADGE. THE SIDA IS DEFINES AS ALL AREA INSIDE THE AIRPORT SECURITY FENCE.
- 2. VEHICLES ENTERING THE AOA ARE SUBJECT TO SEARCH AND INSPECTION PRIOR TO ENTERING. THE PROCEDURES WILL BE OUTLINED BY THE RPR AND AIRPORT OPERATIONS, AND CONTRACTORS ARE EXPECTED TO FAMILIARIZE THEMSELVES WITH AND COMPLY WITH THESE PROCEDURES.
- 3. VEHICLES ENTERING THE SIDA MUST DISPLAY ALL NECESSARY IDENTIFICATION AS OUTLINED IN FAA AC 150/537-2G OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION. ONLY PERSONS HOLDING A VALID SIDA DRIVER'S BADGE MAY DRIVE UNDER ESCORT WITHIN THE SIDA.
- 4. CONTRACTOR PERSONNEL MUST OBTAIN SECURITY BADGES FROM THE AIRPORT SECURITY OFFICE IN ORDER TO PERFORM THE WORK. THE CONTRACTOR WILL BE REQUIRED TO BADGE ALL EMPLOYEES EXPECTED TO WORK MORE THAN ONE DAY AT THE PROJECT SITE UNLESS OTHERWISE APPROVED BY THE AIRPORT. ONE (1) BADGED EMPLOYEE MAY ESCORT UP TO FIVE (5) UN-BADGED EMPLOYEES THAT WILL BE ON-SITE FOR ONE DAY OR LESS. ESCORTED EMPLOYEES MUST REMAIN IN CLOSE PROXIMITY TO THE BADGED EMPLOYEE AND CANNOT BE LEFT UNATTENDED ON THE AIRFIELD.
- 5. BEFORE RECEIVING A BADGE, EMPLOYEES MUST SUBMIT THEIR FINGER PRINTS AND COMPLETE A BADGE APPLICATION FORM. A CRIMINAL BACKGROUND CHECK WILL BE CONDUCTED FOR EACH APPLICANT. AFTER APPROVAL, THE APPLICANT MUST COMPLETE A COMPUTER-BASED TRAINING FOR SUBJECTS INCLUDING AIRPORT SECURITY AND AIRSIDE DRIVING REQUIREMENTS. THE BASIC TRAINING MODULES TAKE APPROXIMATELY 2 HOURS. UPON COMPLETION, A PHOTO IDENTIFICATION BADGE WILL BE ISSUED. THE BADGE MUST BE WORN ABOVE THE WAIST WHILE ON AIRPORT PROPERTY.

BASE BID, ADDITIVE ALTERNATE AND OPTION DESCRIPTION

THE PROJECT BID INCLUDES A BASE BID, 5 ALTERNATES AND AN OPTION. REFER TO THE BIDDING PROPOSAL FOR THE QUANTITIES ASSOCIATED WITH EACH. THE BELOW IS A SUMMARY OF THE BASE BID, ALTERNATE AND OPTION.

- 1. BASE BID (RUNWAY):
 - a. REFER TO PLAN VOLUMES 1 AND 2.REFER TO PHASES 1 THROUGH 7 FOR THE PHASING.
 - b. REHABILITATE THE PAVEMENTS 9,250-FOOT-LONG RUNWAY BY 150 FEET WIDE.
 - c. REHABILITATE ALL RUNWAY AND SHOULDER PAVEMENTS WITHIN THE RUNWAY-RUNWAY INTERSECTION.
 - d. FAA IN-PAVEMENT APPROACH LIGHT UPGRADES WITHIN THE 9,250-FOOT-LONG RUNWAY.
 - e. AIRPORT LIGHTING & SIGNAGE REPLACEMENTS & RELATED AIRFIELD ELECTRICAL.
 - f. RWIS UPGRADES AND SENSOR INSTALLATION.
 - g. REHABILITATE THE SOUTH TAXIWAY A RETAINING WALL AND DETENTION POND IMPROVEMENTS SHOWN IN PHASE 7 OF THE PHASING PLANS.
- 2. ALTERNATE #1 (RUNWAY SHOULDERS):
 - a. REFER TO PLAN VOLUMES 1 AND 2.
 - b. REFER TO PHASES 1 THROUGH 6 FOR THE PHASING.
 - c. REHABILITATE THE RUNWAY PAVEMENT SHOULDERS 9,250-FOOT-LONG BY 25 FEET WIDE ON BOTH SIDES.
 - d. FAA IN-PAVEMENT APPROACH LIGHT UPGRADES WITHIN THE SHOULDER PAVEMENT.
- 3. ALTERNATE #2 (RUNWAY BLAST PADS):
 - a. REFER TO PLAN VOLUMES 1 AND 2.
 - b. REFER TO PHASES 1 THROUGH 6 FOR THE PHASING.
 - c. REHABILITATE THE RUNWAY PAVEMENT BLAST PADS 200 FEET BY 200 FEET ON BOTH ENDS.
 - d. FAA IN-PAVEMENT APPROACH LIGHT UPGRADES WITHIN THE BLAST PAD PAVEMENT.
- 4. ALTERNATE #3 (REHABILITATE THE TAXIWAY A RETAINING WALL)
 - a. REFER TO VOLUME III OF THE PLANS.
 - b. REFER TO PHASE 8 FOR THE PHASING.
 - c. INSTALLS DRAINAGE BEHIND THE EXISTING WALL AND ENLARGES THE DOWNSTREAM OPEN CHANNEL CONVEYANCES.
- 5. ALTERNATE #4 (RWIS RPU UPGRADES NOT IN THE BASE BID)
 - a. REFER TO VOLUME 1 OF THE PLANS
 - b. REFER TO REFER TO PHASE 3 FOR THE PHASING.
 - c. UPGRADES RUNWAY WEATHER INFORMATION SYSTEM (RWIS) RPU COMPONENTS FOR RUNWAY 6-24, TAXIWAY M AND TERMINAL RPUS.
- 6. ALTERNATE #5 (ELECTRICAL MANHOLE DRAINAGE)
 - a. REFER TO VOLUME 1 OF THE PLANS.
 - b. REFER TO PHASE 9 OF THE PHASING PLANS.
 - c. INSTALLS DRAINAGE OUTLETS IN CERTAIN EXISTING ELECTRICAL MANHOLES TO THE EXISTING DRAINAGE NETWORK.
- 7. ALTERNATE #6 (RECONSTRUCT AND REHABILITATE SERVICE ROAD)
 - a. REFER TO VOLUME 4 OF THE PLANS.
 - b. REFER TO PHASE 10 OF THE PHASING PLANS.
 - c. INSTALLS STORM DRAINAGE IMPROVEMENTS, REHABILITATES A PORTION OF THE EXISTING SERVICE ROAD AND INSTALLS NEW AIRPORT SECURITY FENCING.
- 8. OPTION
 - a. IN LIEU OF ALTERNATES #1 AND #2, THE SHOULDERS AND BLAST PADS ARE SEALCOATED.
 - b. WORK WILL OCCUR AS SHOWN DURING PHASE 1 THROUGH 6.

PROJECT DESIGNER:



2 Executive Park Drive
Suite 200
Manchester, NH 03110
PHONE: (603) 666-7181
FAX: (603) 666-7185

SCALE: NTS

DATE: MARCH 2022

DESIGNED BY: DJA

DRAWN BY: DJA

CHECKED BY: JAM

APPROVED: JWG



MANCHESTER • BOSTON
REGIONAL AIRPORT

REHABILITATE RUNWAY 17-35

BY DJA

REVISIONS

DESCRIPTION

ADDENDUM – 1

DATE 3/30/2022

REV NO. 1

PROJ. NO.: E2X89205




J.E. FILE:

DRAWING NO.

G-003


REV

ISSUED FOR BID - NOT FOR CONSTRUCTION



PROJECT DESIGNER:					
<div>Jacobs</div> <div>2 Executive Park Drive Bedford, NH 03110 Tel: (603) 886-7181 Fax: (603) 866-7185</div>					
SCALE:	1"=400'				
DATE:	MARCH 2022				
DESIGNED BY:	DJA				
DRAWN BY:	DJA				
CHECKED BY:	JAM				
APPROVED:	JWG				
<div>MANCHESTER • BOSTON REGIONAL AIRPORT</div>					
REHABILITATE RUNWAY 17-35					
CONSTRUCTION ACCESS PLAN AND NOTES					
REVISONS					
REV. NO.	DATE	DESCRIPTION	BY		
A	3/30/2022	ADDENDUM -- 1	DJA		
PROJ. NO.: E2X89205					
JE FILE:					
DRAWING NO.					
G-004					
					REV

Jacobs - \vnh110\1\job\2021\LE2X89205 - MHT RW 17-35\700 CADD\G100 - General Safety and Phasing Plan and Notes.dwg [G-100] March 30, 2022 - 12:04pm [danorelli]



GENERAL CONSTRUCTION SAFETY AND PHASING PLAN

RUNWAY SAFETY AREA (RSA) AND TAXIWAY OBJECT FREE AREA (TOFA) NOTES:

1. THE RUNWAY SAFETY AREA (RSA) IS A DEFINED SURFACE SURROUNDING THE RUNWAY. THE RSA WIDTH IS 500 FEET AND THE ROFA WIDTH IS 800 FEET, CENTERED ON THE RUNWAY CENTERLINE. THE RSA EXTENDS BEYOND THE END OF THE RUNWAY. WORK WITHIN THE RSA SHALL BE COMPLETED WHEN THE RUNWAY IS CLOSED.
2. THE TAXIWAY OBJECT FREE AREA (TOFA) IS A DEFINED SURFACE SURROUNDING THE TAXIWAY. THE TOFA WIDTH IS 259 FEET, CENTERED ON THE TAXIWAY CENTERLINE. WORK WITHIN THE TOFA SHALL BE COMPLETED WHEN THE TAXIWAY IS CLOSED.
3. AT THE END OF EACH WORK SHIFT, PRIOR TO ANY AIRPORT MOVEMENT AREA RE-OPENING TO AIRCRAFT, THE ROFA AND TOFA SHALL BE:
 - A. CLEARED AND GRADED AND HAVE NO RUTS, HUMPS, DEPRESSIONS, OR OTHER SURFACE VARIATIONS.
 - B. DRAINED BY GRADING OR OTHER TEMPORARY MEASURES TO PREVENT WATER ACCUMULATION.
 - C. CAPABLE, UNDER DRY CONDITIONS, OF SUPPORTING AIRCRAFT RESCUE AND FIRE FIGHTING (ARFF) EQUIPMENT, AND THE OCCASIONAL PASSAGE OF AN AIRCRAFT WITHOUT CAUSING STRUCTURAL DAMAGE TO THE AIRCRAFT.
4. FREE OF OBJECTS, EXCEPT FOR OBJECTS THAT NEED TO BE IN THE TOFA DUE TO THEIR FUNCTION. IN NO CASE SHALL ANY OBJECTS EXCEED 3 INCHES ABOVE GRADE.
5. SHOULDER TRANSVERSE GRADES AND THE FIRST 10 FEET OUTSIDE THE SHOULDER SHALL BE A MAXIMUM OF MINUS 5%. OUTSIDE OF THE FIRST 10 FEET OF THE SHOULDER SHALL BE A MAXIMUM OF MINUS 3%. TRANSITIONS BETWEEN DIFFERENT GRADIENTS SHALL BE WARPED SMOOTHLY.
6. ANY STRUCTURES AND/OR DROP-OFFS IN EXCESS OF 3" SHALL BE RAMPED PRIOR TO THE END OF EACH WORK SHIFT. TEMPORARY RAMPING SHALL BE GRADED AS STATED IN NOTE E.

GENERAL CONSTRUCTION SAFETY AND PHASING NOTES:

1. THE CONTRACTOR SHALL SUBMIT TO THE OWNER AND RPR A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) FOR APPROVAL. THE SPCD SHALL BE PREPARED IN ACCORDANCE WITH THE FAA APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP) INCLUDED IN THE CONTRACT SPECIFICATIONS. THE SPCD SHALL INCLUDE A WRITTEN METHOD OF OPERATIONS THAT DETAIL THE PRECAUTIONS PROPOSED FOR THE CONTROL OF VEHICLE TRAFFIC INCLUDING SIGNS, ESCORTS AND ANY OTHER MEASURES PROPOSED. THE CONTRACTOR SHALL FOLLOW THE APPROVED PLAN EXPLICITLY AFTER APPROVAL. THE OWNER MAY CLOSE THE WORK AT ANY TIME THE APPROVED PLAN IS VIOLATED SO AS NOT TO ENDANGER THE AIRPORT OR AIRCRAFT OPERATIONS. SUCH A CLOSURE SHALL NOT BE CONSIDERED A VALID REASON FOR EXTENDING THE CONTRACT TIME OR ANY CLAIM FOR EXTRAS BY THE CONTRACTOR. REFER TO ADVISORY CIRCULAR A/C NO. 150/5370-2G "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION" FOR AIRFIELD CONSTRUCTION SAFETY REQUIREMENTS.
2. NO CONSTRUCTION MAY OCCUR WITHIN THE RUNWAY SAFETY AREA (RSA) AND TAXIWAY SAFETY AREA (TSA) WHILE RUNWAY 17-35, RUNWAY 6-24, AND TAXIWAYS ARE OPEN FOR AIRCRAFT OPERATIONS.
3. AT THE END OF EACH WORK PERIOD, THE TAXIWAYS WILL BE OPENED TO AIRCRAFT TRAFFIC UNLESS OTHERWISE NOTED IN THE PLANS.
4. THE CONTRACTOR SHALL ENSURE ADEQUATE TIME FOR THE ASPHALT MAT TO COOL AS STATED IN THIS PARAGRAPH TO ACCEPT AIRCRAFT TRAFFIC UPON OPENING. THE POTENTIAL FOR AIRCRAFT TRAFFIC TO CAUSE RUTTING OF THE NEWLY PLACED MAT IS A FUNCTION OF THE STABILITY OF THE MIX, WHICH VARIES WITH MAT SURFACE TEMPERATURE, MAT THICKNESS, AND ASPHALT CONTENT. AIRCRAFT TRAFFIC SHOULD NOT BE ALLOWED ON NEWLY PLACED MAT UNTIL IT COOLS TO 140 DEGREES F.
5. THE CONTRACTOR SHALL INSTALL ALL EROSION CONTROL MEASURES PRIOR TO THE START OF ANY CONSTRUCTION.
6. THE CONTRACTOR SHALL COMPLETE ALL WORK ASSOCIATED WITH EACH PHASE WITHIN THE CALENDAR DAYS PROVIDED FOR EACH PHASE. THE CONTRACT DURATION IS CONTINGENT ON THE START OF THE WORK. THE CONTRACTOR MAY START WORK IN 2022 FOR PHASES 7, 8, AND 10. IF THE CONTRACTOR ELECTS TO START WORK IN 2022 THE CONTRACT DURATION WILL BE 161 CALENDAR DAYS WITH AN ANTICIPATED NOTICE TO PROCEED IN SEPTEMBER 2022. WORK THAT STARTS IN 2022 WILL HAVE AN ANTICIPATED WORK STOPPAGE IN LATE FALL 2022 WITH A WORK RESTART IN APRIL 2023. IF THE CONTRACTOR ELECTS TO COMPLETE ALL CONSTRUCTION PHASES IN 2023 THE CONTRACT DURATION SHALL BE 99 CALENDAR DAYS WITH AN ANTICIPATED NOTICE TO PROCEED IN APRIL 2023.
7. THE CONTRACTOR MUST SUBMIT A PAVING PLAN FOR APPROVAL BY THE RPR PRIOR TO BEGINNING ANY PAVING OPERATIONS.
8. THE CONTRACTOR MUST PLACE LOW PROFILE BARRICADES AND REQUIRED CONSTRUCTION SIGNS PRIOR TO EACH PHASE. MAINTAIN AND REMOVE THEM AT THE END OF EACH PHASE ACCORDINGLY UNLESS OTHERWISE NOTED.
9. THE CONTRACTOR MUST INSTALL 'CONSTRUCTION AHEAD' SIGNS AT THE LOCATIONS SHOWN ON THE PHASING PLANS PRIOR TO ANY CONSTRUCTION ACTIVITIES. REFER TO THE G-200 SERIES FOR ALL CONSTRUCTION SAFETY DETAILS FOR 'CONSTRUCTION AHEAD' SIGN DETAIL. ALL CONSTRUCTION SIGNS SHALL BE INCIDENTAL TO G-004-1 MAINTENANCE AND PROTECTION OF TRAFFIC.
10. AFTER EACH CONSTRUCTION PHASE, A PRE-OPENING INSPECTION IS REQUIRED AND WILL BE PERFORMED WITH THE CONTRACTOR, AIRPORT OPERATIONS, AND THE RPR. THIS INSPECTION IS TO ENSURE THAT ALL FAA STANDARDS ARE MET

- BEFORE THE RE-OPENING OF ANY RUNWAY, TAXIWAY, AND MOVEMENT AREA. ALL AREAS MUST BE CLEAR OF FOREIGN OBJECT DEBRIS (FOD). THE CONTRACTOR SHALL FOLLOW STANDARDS IN FAA AC 150/5370-2G, OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION AND FAA AC 150/5370-13A, OFF-PEAK CONSTRUCTION OF AIRPORT PAVEMENTS USING HOT-MIX ASPHALT. REFER TO RSA AND TOFA NOTES FOR REOPENING REQUIREMENTS.
11. THE CONTRACTOR SHALL APPLY THE PERMANENT PAVEMENT MARKINGS THIRTY DAYS AFTER THE COMPLETION OF THE PAVEMENT CONSTRUCTION. THE PAVEMENT SURFACE MUST BE PREPARED PRIOR TO PAVEMENT MARKING APPLICATION AS STATED IN THE P-620 SPECIFICATION. THE TEMPORARY PAVEMENT MARKINGS SHALL BE APPLIED IN ONE 50% APPLICATION COAT. THE PERMANENT PAVEMENT MARKINGS APPLICATION WILL USE A 100% APPLICATION RATE. THE TWO APPLICATIONS OF PAINT WILL BE PAID FOR ONCE UNDER THE ASSOCIATED PAY ITEMS.
 12. THE CONTRACTOR MUST MAINTAIN SECURITY FOR THE AIRPORT AT ALL TIMES. THE PERIMETER SECURITY FENCE MUST REMAIN CONTINUOUS AT ALL TIMES DURING CONSTRUCTION ACTIVITIES.

LEGEND

- RSA — RSA — RUNWAY SAFETY AREA
- ROFA — ROFA — RUNWAY OBJECT FREE AREA
- POFZ — POFZ — PRECISION OBSTACLE FREE ZONE
- GS — GS — GLIDE SLOPE CRITICAL AREA
- CONTRACTOR STAGING AREA
- APPROACH LIGHT SYSTEM LIGHTS
- PHASE 1 - SEE SHEET G-101
- PHASE 2 - SEE SHEET G-102
- PHASE 3 - SEE SHEET G-103
- PHASES 4, 5, AND 6 - SEE SHEET G-104
- PHASES 7 AND 8 - SEE SHEET G-105
- PHASE 9 - SEE SHEET G-106
- PHASE 10 - SEE SHEET G-107

PHASE	GENERAL PHASE CONSTRUCTION DESCRIPTION	DURATION CALENDAR DAYS	RUNWAY IMPACTS				CONSTRUCTION SCHEDULE - MONTHS									
			RUNWAY 17 - 35		RUNWAY 6 - 24		2022		WINTER	2023						
			STATUS	ILS	STATUS	ILS	1	2		1	2	3	4	5	6	
1	RUNWAY 17 END REHABILITATION / RUNWAY 17 MALSR REHABILITATION	14	CLOSED	OFF	OPEN	ON			WINTER WORK STORAGE	<div></div>						
2	RUNWAY/RUNWAY INTERSECTION REHABILITATION	7	TEMPORARY RUNWAY	OFF	CLOSED	OFF				<div></div>						
3	REMAINING RUNWAY REHABILITATION / RUNWAY 35 ALSF-2 REHABILITATION	62	CLOSED	OFF	OPEN	ON				<div></div>						
4	TEMPORARY PAVEMENT MARKING OPERATIONS	3 NIGHT WORK	CLOSED	OFF	OPEN	ON								<div></div>		
RUNWAY 17-35 RE-OPENED / RUNWAY FLIGHT CHECK																
5	RUNWAY GROOVING OPERATIONS	10 NIGHT WORK	CLOSED DURING THE WORK SHIFT	OFF	OPEN	ON									<div></div>	
6	FINAL PAVEMENT MARKING OPERATIONS	3 NIGHT WORK	CLOSED DURING THE WORK SHIFT	OFF	OPEN	ON								<div></div>		
7	BASE BID REATINING WALL REHABILITATION WORK	21	CLOSED DURING PHASES 3 AND 4	OFF DURING PHASE 3 AND 4	OPEN	ON	<div></div>				<div></div>					
8	ADD. ALT.-3 RETAINING WALL REHABILITATION / DRAINAGE IMPROVEMENTS	65	CLOSED DURING PHASES 3 AND 4	OFF DURING PHASE 3 AND 4	OPEN	ON	<div></div>				<div></div>					
9	ADD. ALT.-5 EMH DRAINAGE IMPROVEMENTS	62	CLOSED	OFF	OPEN	ON					<div></div>					
10	RECONSTRUCT AND REHABILITATE A PORTION OF THE SERVICE ROAD	21	CLOSED DURING PHASES 3 AND 4	OFF DURING PHASE 3 AND 4	OPEN	ON	<div></div>				WORK RESTRICTED BY PERMIT-SEE G-107				<div></div>	
RUNWAY PAVEMENT CURING TIME WORK STORAGE																

PROJECT DESIGNER:

Jacobs

2 Executive Park Drive
Suite 205
Boston, MA 02110
PHONE: (603) 666-7181
FAX: (603) 666-7185

SCALE: 1"=400'

DATE: MARCH 2022

DESIGNED BY: DJA

DRAWN BY: DJA

CHECKED BY: JAM

APPROVED: JWG

MANCHESTER • BOSTON
REGIONAL AIRPORT

REHABILITATE RUNWAY 17-35

GENERAL CONSTRUCTION SAFETY AND PHASING PLAN AND NOTES

BY: DJA

REVISIONS
DESCRIPTION
ADDENDUM - 1

DATE: 3/30/2022

REV. NO. 1


PROJ. NO.: E2X89205
JE FILE:

DRAWING NO.

G-100

ISSUED FOR BID - NOT FOR CONSTRUCTION

Jacobs - \\mnh101\job\2021\LE2X89205 - MHT RW 17-35\700 CADD\G105 - Phases 7-8 CSPP.dwg [G-105] March 30, 2022 - 11:17 am [damorell]



PHASE 7 (BASE BID WALL/RIP-RAP REHABILITATION) NOTES:

SCHEDULE

1. THE CONTRACTOR MUST COMPLETE ALL WORK ASSOCIATED WITH THIS CONSTRUCTION PHASE WITHIN **21** CONSECUTIVE CALENDAR DAYS.

2. THIS PHASE MAY START IN THE FALL OF 2022. THIS PHASE MAY NOT RUN CONCURRENTLY WITH THE FUTURE RECONSTRUCTION OF TAXIWAY K. TAXIWAY K CONSTRUCTION IS BY OTHERS AND IS ANTICIPATED TO BE COMPLETED IN AUGUST 2022. THIS PHASE MAY NOT RUN CONCURRENTLY WITH PHASE 1 AND 2 OF THIS PROJECT.

4. THE CONTRACTOR MUST COORDINATE ALL ASSOCIATED WORK WITHIN THE AIRPORT PROPERTY LIMITS WITH THE AIRPORT. THE CONTRACTOR MUST COORDINATE WITH THE AIRPORT OPERATIONS DURING HAULING ACTIVITIES.

IMPACTS TO OPERATIONS

1. WORK WITHIN THE TOFA WILL REQUIRE MOVEMENT AREA CLOSURES. MOVEMENT AREA CLOSURES:
- TAXIWAY A CLOSED FROM TAXIWAY F TO TAXIWAY A2
2. WORK OUTSIDE OF THE TOFA DO NOT REQUIRE THE MOVEMENT AREA CLOSURES.

GENERAL NOTES

1. SEE SHEET G-100 FOR GENERAL SAFETY AND PHASING NOTES.
2. A 'NO ENTRY' SIGN MUST BE INSTALLED ON THE LOW PROFILE BARRICADES AT THE PAVEMENT LIMITS FOR THE CONSTRUCTION PHASE. REFER TO THE G-200 SERIES OF DRAWINGS FOR 'NO ENTRY' SIGN DETAIL AND INSTALLATION REQUIREMENTS.
3. WHILE THE CONSTRUCTION AREA IS CLOSED FOR THIS PHASE, THE BARRICADES AND 'NO ENTRY' SIGN MUST REMAIN IN POSITION IN THE PROPER LOCATION AT ALL TIMES DURING THE WORK SHIFT.
4. REFER TO RSA AND TOFA NOTES ON SHEET G-100 FOR THE MOVEMENT AREA REOPENING REQUIREMENTS.
5. ALL CONSTRUCTION BARRICADES, CONSTRUCTION SIGNS, AND LIGHTED RUNWAY CLOSURE MARKERS SHALL BE INCIDENTAL TO G-004-1 MAINTENANCE AND PROTECTION OF TRAFFIC.
6. THE CONTRACTOR MUST BLANK OUT EXISTING GUIDANCE SIGNS DURING THIS PHASE. REFER TO DRAWING E-710 FOR THE SIGNS TO BE BLANKED OUT AND THE REQUIREMENTS FOR THIS WORK.
7. FOR ADDITIONAL INFORMATION ON THE WORK ASSOCIATED WITH THIS PHASE REFER TO VOLUME 3 OF THIS PROJECT.

MAJOR WORK ITEMS

1. MAJOR WORK ELEMENTS IN THIS PHASE INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - A. INSTALLATION OF BARRICADES, 'NO ENTRY' SIGNS, AND TAXIWAY CLOSURE MARKERS AS SHOWN ON THIS SHEET
 - B. RIP-RAP REHABILITATION OPERATIONS
 - C. EXISTING MECHANICALLY STABILIZED EARTH WALL REPAIRS

LEGEND

- RSA — RSA — RUNWAY SAFETY AREA
- ROPA — ROPA — RUNWAY OBJECT FREE AREA
- ROPFZ — ROPFZ — PRECISION OBSTACLE FREE ZONE
- GS — GS — GLIDE SLOPE CRITICAL AREA
- PHASE 1 - SEE SHEET G-101
- PHASE 2 - SEE SHEET G-102
- PHASE 3 - SEE SHEET G-103
- PHASES 4, 5, AND 6 - SEE SHEET G-104
- PHASES 7 AND 8 - SEE SHEET G-105
- PHASE 9 - SEE SHEET G-106
- APPROACH LIGHT SYSTEM LIGHTS
- CONSTRUCTION SIGNAGE
- CONSTRUCTION HAUL ROUTE
- CONTRACTOR STAGING AREA
- TEMPORARY SECURITY GATE
- ⊠ 'NO ENTRY' SIGN
- ▨ LOW PROFILE CONSTRUCTION BARRICADES
- ✕ LIGHTED RUNWAY CLOSURE MARKER
- ✕ TAXIWAY CLOSURE MARKER
- TEMPORARY RUNWAY END LIGHTS

PHASE 8 (ADD. ALT.-3 WALL REHABILITATION / DRAINAGE IMPROVEMENTS) NOTES:

SCHEDULE

1. THE CONTRACTOR MUST COMPLETE ALL WORK ASSOCIATED WITH THIS CONSTRUCTION PHASE WITHIN **65** CONSECUTIVE CALENDAR DAYS.

2. THIS PHASE MAY START IN THE FALL OF 2022. THIS PHASE MAY NOT RUN CONCURRENTLY WITH THE FUTURE RECONSTRUCTION OF TAXIWAY K. TAXIWAY K CONSTRUCTION IS BY OTHERS AND IS ANTICIPATED TO BE COMPLETED IN AUGUST 2022. THIS PHASE MAY NOT RUN CONCURRENTLY WITH PHASE 1 AND 2 OF THIS PROJECT.

4. THE CONTRACTOR MUST COORDINATE ALL ASSOCIATED WORK WITHIN THE AIRPORT PROPERTY LIMITS WITH THE AIRPORT. THE CONTRACTOR MUST COORDINATE WITH THE AIRPORT OPERATIONS DURING HAULING ACTIVITIES.

IMPACTS TO OPERATIONS

1. WORK WITHIN THE TOFA WILL REQUIRE MOVEMENT AREA CLOSURES. MOVEMENT AREA CLOSURES:
- TAXIWAY A CLOSED FROM TAXIWAY E TO TAXIWAY A2
 - TAXIWAY F CLOSED FROM TAXIWAY A TO RUNWAY 17-35
2. WORK OUTSIDE OF THE TOFA DO NOT REQUIRE THE MOVEMENT AREA CLOSURES.

GENERAL NOTES

1. SEE SHEET G-100 FOR GENERAL SAFETY AND PHASING NOTES.
2. A 'NO ENTRY' SIGN MUST BE INSTALLED ON THE LOW PROFILE BARRICADES AT THE PAVEMENT LIMITS FOR THE CONSTRUCTION PHASE. REFER TO THE G-200 SERIES OF DRAWINGS FOR 'NO ENTRY' SIGN DETAIL AND INSTALLATION REQUIREMENTS.
3. WHILE THE CONSTRUCTION AREA IS CLOSED FOR THIS PHASE, THE BARRICADES AND 'NO ENTRY' SIGN MUST REMAIN IN POSITION IN THE PROPER LOCATION AT ALL TIMES DURING THE WORK SHIFT.
4. REFER TO RSA AND TOFA NOTES ON SHEET G-100 FOR THE MOVEMENT AREA REOPENING REQUIREMENTS.
5. ALL CONSTRUCTION BARRICADES, CONSTRUCTION SIGNS, AND LIGHTED RUNWAY CLOSURE MARKERS SHALL BE INCIDENTAL TO G-004-1 MAINTENANCE AND PROTECTION OF TRAFFIC
6. THE CONTRACTOR MUST BLANK OUT EXISTING GUIDANCE SIGNS DURING THIS PHASE. REFER TO DRAWING E-710 FOR THE SIGNS TO BE BLANKED OUT AND THE REQUIREMENTS FOR THIS WORK.
7. FOR ADDITIONAL INFORMATION ON THE WORK ASSOCIATED WITH THIS PHASE REFER TO VOLUME 3 OF THIS PROJECT.

MAJOR WORK ITEMS

1. MAJOR WORK ELEMENTS IN THIS PHASE INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - A. INSTALLATION OF BARRICADES, 'NO ENTRY' SIGNS, AND TAXIWAY CLOSURE MARKERS AS SHOWN ON THIS SHEET
 - B. STORM DRAINAGE IMPROVEMENTS
 - C. EXISTING MECHANICALLY STABILIZED EARTH WALL REPAIRS

PROJECT DESIGNER:

Jacobs

2 Executive Park Drive
Suite 205
Boston, MA 02110
PHONE: (603) 666-7181
FAX: (603) 666-7185

SCALE: 1"=400'

DATE: MARCH 2022

DESIGNED BY: DJA

DRAWN BY: DJA

CHECKED BY: JAM

APPROVED: JWG

MANCHESTER • BOSTON
REGIONAL AIRPORT

REHABILITATE RUNWAY 17-35

PHASES 7 AND 8 CONSTRUCTION
SAFETY AND PHASING PLAN & NOTES

REV NO.

DATE

DESCRIPTION

BY

3/30/2022

ADDENDUM - 1

DJA

PROJ. NO.: E2X89205


JE FILE:

DRAWING NO.

G-105

ISSUED FOR BID - NOT FOR CONSTRUCTION

Jacobs - \\mnh101\job\2021\E2X89205 - MHT RW 17-35\700 CADD\G106 - Phase 9 CSPP.dwg [G-106] March 30, 2022 - 11:56am [damorell]



PHASE 9 CONSTRUCTION SAFETY AND PHASING PLAN

LEGEND

- RSA — RSA — RUNWAY SAFETY AREA
- OFA — OFA — RUNWAY OBJECT FREE AREA
- POFA — POFA — PRECISION OBSTACLE FREE ZONE
- GS — GS — GLIDE SLOPE CRITICAL AREA
- PHASE 1 - SEE SHEET G-101
- PHASE 2 - SEE SHEET G-102
- PHASE 3 - SEE SHEET G-103
- PHASES 4, 5, AND 6 - SEE SHEET G-104
- PHASES 7 AND 8 - SEE SHEET G-105
- PHASE 9 - SEE SHEET G-106
- APPROACH LIGHT SYSTEM LIGHTS
- CONSTRUCTION SIGNAGE
- CONSTRUCTION HAUL ROUTE
- CONTRACTOR STAGING AREA
- TEMPORARY SECURITY GATE
- ⊞ 'NO ENTRY' SIGN
- ▨ LOW PROFILE CONSTRUCTION BARRICADES
- ✕ LIGHTED RUNWAY CLOSURE MARKER
- ✕ TAXIWAY CLOSURE MARKER
- TEMPORARY STAKE MOUNTED RUNWAY END LIGHTS
- TAXI ROUTE

PHASE 9 NOTES:

SCHEDULE

- THE CONTRACTOR MUST COMPLETE ALL WORK ASSOCIATED WITH THIS CONSTRUCTION PHASE WITHIN 62 CONSECUTIVE CALENDAR DAYS.
- THERE ARE 16 LOCATIONS THAT HAVE PHASE 9 ASSOCIATED WORK. WORK AT THESE LOCATIONS WILL BE CONDUCTED DURING TWO OTHER PROJECT PHASES AS FOLLOWS:
 - TWO (2) LOCATIONS MUST RUN CONCURRENTLY WITH PHASE 1 OF CONSTRUCTION - SEE PHASE 9 CONSTRUCTION PHASING PLAN ABOVE.
 - FOURTEEN (14) LOCATIONS MUST RUN CONCURRENTLY WITH PHASE 3 OF CONSTRUCTION - SEE PHASE 9 CONSTRUCTION PHASING PLAN ABOVE.
- THE CONTRACTOR MUST COORDINATE ALL ASSOCIATED WORK WITHIN THE AIRPORT PROPERTY LIMITS WITH THE AIRPORT. THE CONTRACTOR MUST COORDINATE WITH AIRPORT OPERATIONS DURING HAULING ACTIVITIES.
- DURING THIS PHASE THE CONSTRUCTION SAFETY AND PHASING SET-UP FOR PHASE 3 OF CONSTRUCTION WILL BE IN PLACE FOR THE RUNWAY WORK. DURING THE WEEKLY CONSTRUCTION MEETING THE CONTRACTOR MUST PROVIDE A WEEKLY SCHEDULE THAT OUTLINES THE SPECIFIC ELECTRICAL MANHOLES THAT ARE INTENDED TO BE WORKED ON FOR THE FOLLOWING WEEK. DURING THE WEEKLY PROJECT MEETING THE EXACT ACCESS TO THE WORK AREAS WILL BE DISCUSSED SO THAT THE PROPER ESCORTING REQUIREMENTS CAN BE IDENTIFIED AND ESTABLISHED.
- ANY WORK THAT IS INSIDE THE TOFA OF AN ACTIVE TAXIWAY WILL REQUIRE A MOVEMENT AREA CLOSURE FOR THAT WORK.
- BARRICADES MUST BE PLACED AROUND EACH ACTIVE WORK AREA. THE EXACT POSITIONS OF THE BARRICADES MUST BE REVIEWED AND APPROVED BY THE RPR.
- REFER TO THE 600 SERIES OF DRAWINGS FOR THE ELECTRICAL MANHOLE DRAINAGE IMPROVEMENTS.

IMPACTS TO OPERATIONS


- MOVEMENT AREA CLOSURES:
 - RUNWAY 17-35 CLOSED
 - TAXIWAY A CLOSED FROM TAXIWAY E TO RUNWAY 35 END
 - TAXIWAY A1 AND A2 CLOSED
 - TAXIWAY F CLOSED
 - TAXIWAY H CLOSED FROM TAXIWAY E TO RUNWAY 17-35
 - TAXIWAY D CLOSED FROM TAXIWAY A TO RUNWAY 17-35
 - TAXIWAY A3 CLOSED FROM TAXIWAY A TO RUNWAY 17-35
 - TAXIWAY E CLOSED (DURING SUB-PHASE 3 B)
 - TAXIWAY B CLOSED (DURING SUB-PHASE 3 A)
 - TAXIWAYS K1 AND K2 CLOSED

GENERAL NOTES

- SEE SHEET G-100 FOR GENERAL SAFETY AND PHASING NOTES.
- A 'NO ENTRY' SIGN MUST BE INSTALLED ON THE LOW PROFILE BARRICADES AT THE PAVEMENT LIMITS FOR THE CONSTRUCTION PHASE. REFER TO THE G-200 SERIES OF DRAWINGS FOR 'NO ENTRY' SIGN DETAIL AND INSTALLATION REQUIREMENTS.
- WHILE THE CONSTRUCTION AREA IS CLOSED FOR THIS PHASE, THE BARRICADES AND 'NO ENTRY' SIGN MUST REMAIN IN POSITION IN THE PROPER LOCATION AT ALL TIMES 24 HOURS A DAY.
- REFER TO RSA AND TOFA NOTES ON SHEET G-100 FOR THE MOVEMENT AREA REOPENING REQUIREMENTS.
- ALL CONSTRUCTION BARRICADES, CONSTRUCTION SIGNS, AND LIGHTED RUNWAY CLOSURE MARKERS SHALL BE INCIDENTAL TO G-004-1 MAINTENANCE AND PROTECTION OF TRAFFIC.
- THE CONTRACTOR MUST BLANK OUT EXISTING GUIDANCE SIGNS DURING THIS PHASE. REFER TO DRAWING E-710 FOR THE SIGNS TO BE BLANKED OUT AND THE REQUIREMENTS FOR THIS WORK.

MAJOR WORK ITEMS

- MAJOR WORK ELEMENTS IN THIS PHASE INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - INSTALLATION OF BARRICADES, 'NO ENTRY' SIGNS, AND TAXIWAY CLOSURE MARKERS AS SHOWN ON THIS SHEET
 - INSTALL REQUIRED SEDIMENT AND EROSION CONTROL MEASURES
 - CONDUCT THE ELECTRICAL MANHOLE DRAINAGE IMPROVEMENTS
 - TOPSOIL AND SEED DISTURBED AREAS



PROJECT DESIGNER:
Jacobs
2 Executive Park Drive
Suite 205
Boston, MA 02110
PHONE: (603) 666-7181
FAX: (603) 666-7185

PROJECT NO.: E2X89205
JE FILE:

DRAWING NO.
G-106


MANCHESTER • BOSTON
REGIONAL AIRPORT
REHABILITATE RUNWAY 17-35

PHASE 9 CONSTRUCTION SAFETY
AND PHASING PLAN AND NOTES

SCALE: 1"=400'	DATE: MARCH 2022	DESIGNED BY: DJA	DRAWN BY: DJA	CHECKED BY: JAM	APPROVED: JWG
REV. NO.	DATE	DESCRIPTION	BY	DATE	DESCRIPTION
1	3/30/2022	ADDENDUM - 1	DJA		

ISSUED FOR BID - NOT FOR CONSTRUCTION


Jacobs - \\mh1h101\job\2021\E2X89205 - MHT RW 17-35\700 CADD\G201_G203 - CSPP Details.dwg [G-203] March 31, 2022 - 11:35am [damorell]



CONSTRUCTION SIGN GENERAL NOTES:

- CONTRACTOR TO FURNISH, INSTALL, SECURE AND MAINTAIN SIGNS.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.

1 NO SMOKING SIGN DETAIL
N.T.S.




SAFETY CONE (FOR TURF AREAS)

TRAFFIC & SAFETY CONE NOTES:

- CONTRACTOR TO SECURE AND MAINTAIN SAFETY & TRAFFIC CONES.
- CONES & BALLAST TO BE PROVIDED BY CONTRACTOR AND WILL REMAIN PROPERTY OF THE CONTRACTOR AFTER THE PROJECT IS COMPLETED.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.


5 TRAFFIC & SAFETY CONE DETAIL
N.T.S.




CONSTRUCTION SIGN GENERAL NOTES:

- CONTRACTOR TO FURNISH, INSTALL, SECURE AND MAINTAIN SIGNS.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.

2 TEMPORARY HAUL ROAD STOP SIGN DETAIL
N.T.S.




CHANNELIZER CONE (FOR PAVED AREAS)



CONSTRUCTION SIGN GENERAL NOTES:

- CONTRACTOR TO FURNISH, INSTALL, SECURE AND MAINTAIN SIGNS.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.


3 NO CONSTRUCTION VEHICLES SIGN DETAIL
N.T.S.



GENERAL SECURITY FENCE NOTES:

- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM M-001-1.
- THE MAXIMUM OPENING BENEATH THE GATE IS 5 INCHES. THE MAXIMUM GAPS IN ANY PART OF THE THE FENCE GATE IS 4".


6 TEMPORARY 12' DOUBLE SWING SECURITY GATE
N.T.S.



CONSTRUCTION SIGN GENERAL NOTES:

- CONTRACTOR TO FURNISH, INSTALL, SECURE AND MAINTAIN SIGNS.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.

9 'ONE LANE ROAD AHEAD' SIGN DETAIL
N.T.S.



CONSTRUCTION SIGN GENERAL NOTES:

- CONTRACTOR TO FURNISH, INSTALL, SECURE AND MAINTAIN SIGNS.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.

4 ENTRANCE SIGN DETAIL
N.T.S.

GENERAL CONSTRUCTION SIGNAGE NOTES:

- SIGN PANELS MUST BE CONSTRUCTED OF MATERIALS OF DURABILITY APPROPRIATE FOR THE LENGTH OF TIME THE SIGN IS TO BE USED MEETING THE REQUIREMENTS OF THE MANUFACTURER OF THE RETROREFLECTIVE SHEETING TO BE USED.
- LETTERING MUST BE APPLIED BY DIRECT APPLIED CHARACTER OR SCREEN PROCESS.
- BACKGROUND COLOR OF SIGNS MUST BE RED, MEETING THE REQUIREMENTS OF ASTM D 4956, "SPECIFICATION FOR RETROREFLECTIVE SHEETING FOR TRAFFIC CONTROL", FOR TYPE III OR TYPE IV SHEETING.
- COST OF FURNISHING AND MAINTAINING THIS ITEM SHALL BE INCLUDED IN THE CONTRACTORS BID UNIT COST FOR ITEM G-004-1.

PROJECT DESIGNER:

Jacobs

2 Executive Park Drive
Suite 205
North Attleboro, MA 01910
PHONE: (603) 666-7181
FAX: (603) 666-7185

SCALE: NTS

DATE: MARCH 2022

DESIGNED BY: DJA

DRAWN BY: DJA

CHECKED BY: JAM

APPROVED: JWG

MANCHESTER • BOSTON
REGIONAL AIRPORT

REHABILITATE RUNWAY 17-35

CONSTRUCTION SAFETY AND
PHASING DETAILS – 3

BY: DJA

REV. NO. 1

DATE: 3/30/2022

DESCRIPTION: ADDENDUM – 1

PROJ. NO.: E2X89205

JE. FILE:

DRAWING NO.

G-203

ISSUED FOR BID - NOT FOR CONSTRUCTION

MANCHESTER-BOSTON REGIONAL AIRPORT (MHT)

MANCHESTER, NEW HAMPSHIRE

CONSTRUCTION PLANS FOR

REHABILITATE RUNWAY 17-35

AIP No. 3-33-0011-XXX-2022

CITY BID NO. FY22-805-49

VOLUME 4

RECONSTUCT AND REHABILITATE A PORTION OF THE SERVICE ROAD



One Airport Road, Suite 300
Manchester, New Hampshire 03103
www.flymanchester.com

AUTHORITY/OWNER




150 Dow Street
Manchester, NH 03101-1227
(603) 669-5555
www.hoyletanner.com

PROJECT DESIGNER

ISSUED FOR BID
MARCH 2022

Drawing Number	Sheet Title	Sheet #
G1.0	TITLE SHEET	1
G1.1	GENERAL PLAN	2
SV1.1	EXISTING CONDITIONS PLAN SHEET 1 OF 4	3
SV1.2	EXISTING CONDITIONS PLAN SHEET 2 OF 4	4
SV1.3	EXISTING CONDITIONS PLAN SHEET 3 OF 4	5
SV1.4	EXISTING CONDITIONS PLAN SHEET 4 OF 4	6
GE1.1	GEOMETRY SHEET 1 OF 4	7
GE1.2	GEOMETRY SHEET 2 OF 4	8
GE1.3	GEOMETRY SHEET 3 OF 4	9
GE1.4	GEOMETRY SHEET 4 OF 4	10
GE2.1	TYPICAL SECTIONS AND PAVEMENT DETAILS	11
GD1.1	GRADING AND DRAINAGE PLAN SHEET 1 OF 2	12
GD1.2	GRADING AND DRAINAGE PLAN SHEET 2 OF 2	13
PR1.1	PROPOSED PROFILE AND ALIGNMENT OF UNNAMED STREAM	14
WI1.1	WETLAND IMPACT PLAN SHEET 1 OF 2	15
WI1.2	WETLAND IMPACT PLAN SHEET 2 OF 2	16
W2.1	WETLAND IMPACT DETAILS	17
ER1.1	EROSION CONTROL DETAILS SHEET 1 OF 2	18
ER1.2	EROSION CONTROL DETAILS SHEET 2 OF 2	19
ER2.1	EROSION AND SEDIMENT CONTROL NOTES	20
FE1.1	FENCE DETAILS	21
XS1.1	SERVICE ROAD CROSS SECTIONS SHEET 1 OF 12	22
XS1.2	SERVICE ROAD CROSS SECTIONS SHEET 2 OF 12	23

XS1.3	SERVICE ROAD CROSS SECTIONS SHEET 3 OF 12	24
XS1.4	SERVICE ROAD CROSS SECTIONS SHEET 4 OF 12	25
XS1.5	SERVICE ROAD CROSS SECTIONS SHEET 5 OF 12	26
XS1.6	SERVICE ROAD CROSS SECTIONS SHEET 6 OF 12	27
XS1.7	SERVICE ROAD CROSS SECTIONS SHEET 7 OF 12	28
XS1.8	SERVICE ROAD CROSS SECTIONS SHEET 8 OF 12	29
XS1.9	SERVICE ROAD CROSS SECTIONS SHEET 9 OF 12	30
XS1.10	SERVICE ROAD CROSS SECTIONS SHEET 10 OF 12	31
XS1.11	SERVICE ROAD CROSS SECTIONS SHEET 11 OF 12	32
XS1.12	SERVICE ROAD CROSS SECTIONS SHEET 12 OF 12	33
B1.1	BORING LOGS	34



G1.0
SHEET 1 OF 34

SURVEY NOTES:
THE GROUND SURVEY WAS CONDUCTED JAN. 5, 2017 AND JAN. 19, 2017
USING HORIZONTAL CONTROL HORIZONTAL AND VERTICAL DATUM BASED
ON CONTROL PROVIDED BY MHT. CONTROL PROVIDED BASED ON N.H.
STATE PLANE COORDINATE SYSTEM, N.A.D. 83, AND N.A.V.D. 88
VERTICAL.

DATUM CONTROL POINTS				
POINT #	RAW DESCRIPTION	ELEVATION	NORTHING	EASTING
1	REBAR FND MHT-F 2003	219.913	159567.9070	1045317.0280
2	STEEL PIN SET 7	223.342	158855.4513	1045429.3146
3	STEEL PIN SET 6	222.022	158715.5577	1045785.0226
4	STEEL PIN SET 3	223.550	157742.1343	1046199.1624
6	STEEL PIN 10	223.210	1157047.6661	1046490.9387
8	MNS	229.876	156279.5204	1047739.4720

NGS MONUMENT DATA				
NAME	DESC.	LATITUDE	LONGITUDE	ELEV.
MHT C	PAC	42°56'14.43799"N	071°26'19.58501"W	220.1
MHT D	SAC	42°55'59.61662"N	071°26'40.23127"W	218.8
MHT E	SAC	42°56'00.14444"N	071°26'01.08406"W	225.2
MHT F	PAC	42°56'15.39195"N	071°26'19.03427"W	220.0
MHT G	SAC	42°55'59.64499"N	071°26'00.45014"W	224.9

DATA: NGS 2016. NAD 83 (2011) and NAVD 88

NOTES:

TOPOGRAPHIC INFORMATION AND UTILITY INFORMATION IS A
COMPILATION OF AERIAL SURVEY, AS-BUILT, AND GROUND
SURVEY INFORMATION.

THE COORDINATE VALUES LISTED IN THE TABLES ABOVE ARE BASED
ON THE NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM AND
HAVE A POSITIONAL ACCURACY OF ±0.05' NORTH AND ±0.05' EAST.

THESE COORDINATE VALUES SUPERCEDE ANY PRIOR COORDINATE
VALUES GIVEN FOR THESE POINTS.


IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY
AND MAINTAIN THE ACCURACY FOR THE HORIZONTAL AND
VERTICAL CONTROL SHOWN ON THIS PLAN. ANY DISCREPENCIES
SHALL BE REPORTED TO THE ENGINEER.

THE ENGINEER OR OWNER SHALL DESIGNATE ADDITIONAL PARKING
AREAS AS NECESSARY FOR CONTRACTOR'S PERSONNEL.
CONTRACTOR SHALL BE RESPONSIBLE FOR NECESSARY UPGRADES,
SAFETY, MAINTENANCE, RESTORATION & SHUTTLE SERVICES
CONTRACTOR IS RESPONSIBLE FOR AIRPORT APPROVED VEHICLE
IDENTIFICATION. I.E. STICKERS, ETC.. ANY AND ALL WORK ASSOCIATED
WITH PARKING IS CONSIDERED INCIDENTAL TO PROJECT.

DATUM CONTROL POINTS				
POINT #	RAW DESCRIPTION	ELEVATION	NORTHING	EASTING
1	REBAR FND MHT-F 2003	219.913	159567.9070	1045317.0280
2	STEEL PIN SET 7	223.342	158855.4513	1045429.3146
3	STEEL PIN SET 6	222.022	158715.5577	1045785.0226
4	STEEL PIN SET 3	223.550	157742.1343	1046199.1624
6	STEEL PIN 10	223.210	1157047.6661	1046490.9837
8	MNS	229.876	156279.5204	1047739.4720

NGS MONUMENT DATA				
NAME	DESC.	LATITUDE	LONGITUDE	ELEV.
MHT C	PAC	42°56'14.43799"N	071°26'19.58501"W	220.1
MHT D	SAC	42°55'59.61662"N	071°26'40.23877"W	218.8
MHT E	SAC	42°56'00.14444"N	071°26'01.01426"W	225.2
MHT F	PAC	42°56'15.39195"N	071°26'19.03427"W	220.0
MHT G	SAC	42°55'59.64499"N	071°26'00.45014"W	224.9

DATA: NGS 2016. NAD 83 (2011) and NAVD 88



ENGINEER'S SEAL



150 Dow Street
Manchester, NH 03101
(603) 669-5555
www.hoyletanner.com



DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE



SERVICE ROAD IMPROVEMENTS

SERVICE ROAD IMPROVEMENTS

GENERAL PLAN

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

DESCRIPTION	BY
-------------	----

DATE _____

DATE _____

DATE _____

DATE _____

PROJ. No.: 030089.00

FILE: MHT-G101

AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

G1.1

SHEET 2 OF 34



MATCHLINE – SEE SHEET SV1.2

DRAINAGE TABLE					
STRUCTURE	RIM EL.	INV. IN	INV. IN	INV. OUT	SUMP EL.
CB 1	229.4'	18" RCP (N) EL. 224.6'		18" RCP (S) EL. 224.6'	EL. 221.4'
CB 2	227.5'	24" RCP (E) EL. 223.8'		24" RCP (E) EL. 223.4'	EL. 220.9'
CB 3	229.5'			15" RCP (E) EL. 224.7'	EL. 221.5'
CB 4	225.9'				EL. 200.6'±
CB 5	230.0'			15" RCP (E) EL. 225.4'	EL. 222.3'
CB 6	229.1'	12" RCP (E) EL. 224.7'		15" RCP (S) EL. 224.6'	EL. 221.2'
CB 7	228.0'	15" RCP (E) EL. 221.9'		15" RCP (E) EL. 221.9'	*
CB 8	235.5'	12" RCP (SW) EL. 230.8'		15" RCP (E) EL. 228.5'	EL. 226.2'
CB 9	230.4'	18" RCP (NW) EL. 225.7'		18" RCP (SE) EL. 225.6'	EL. 224.4'
CB 10	270.0'			12" HDPE (E) EL. 265.8'	EL. 263.5'
CB 11	230.7'	24" RCP (S) EL. 222.9'		24" RCP (N) EL. 222.8'	EL. 220.3±
CB 12	247.2'	12" RCP (W) EL. 243.4'		12" HDPE (NE) EL. 243.3'	EL. 243.1'
CB 13	259.1'	12" HDPE (NE) EL. 255.3'	36" HDPE (S) EL. 250.4'	24" RCP (NW) EL. 245.0'	EL. 243.1'±

*COULD NOT OPEN STRUCTURE, INFORMATION MAY BE INCOMPLETE


DRAINAGE TABLE					
STRUCTURE	RIM EL.	INV. IN	INV. IN	INV. OUT	SUMP EL.
DMH 1	229.6'	24" HDPE (N) EL. 222.8'		24" HDPE (S) EL. 222.6'	EL. 222.1'
DMH 2	230.7'	24" HDPE (N) EL. 223.8'		24" HDPE (S) EL. 223.7'	EL. 223.4'
DMH 3	231.9'	24" RCP (N) EL. 223.2'		24" RCP (S) EL. 223.1'	EL. 222.8'
DMH 4	232.7'	4" PVC (N) EL. 224.8'	24" RCP (W) EL. 223.3'	24" RCP (SE) EL. 223.2'	EL. 222.7'
DMH 5	253.9'	24" RCP (SE) EL. 243.0'		24" RCP (NW) EL. 242.9'	EL. 242.1'

SEWER TABLE			
STRUCTURE	RIM EL.	INV. IN	INV. OUT
SMH A31	242.9'	18" CLAY (E) EL. 232.2'	18" CLAY (E) EL. 232.1'
SMH 1	248.3'	18" PVC (E) EL. 231.1'	18" PVC (N) EL. 230.9'
SMH 2	235.9'	18" PVC (S) EL. 226.0'	24" CLAY (N) EL. 225.7'
SMH 3	240.5'	24" CLAY (S) EL. 220.8'	24" CLAY (N) EL. 220.8'
SMH 4	231.4'	24" CLAY (S) EL. 216.4'	24" CLAY (N) EL. 216.2'
SMH 5	223.4'	24" CLAY (S) EL. 207.2'	24" CLAY (N) EL. 207.0'
SMH 6	223.1'	18" PVC (N) EL. 207.0'	18" PVC (S) EL. 207.0'
SMH 7	225.7'	18" PVC (N) EL. 208.3'	18" PVC (S) EL. 208.3'
SMH 8	226.5'	18" PVC (N) EL. 208.5'	18" PVC (S) EL. 208.4'
SMH 9	231.7'	18" PVC (N) EL. 209.7'	18" PVC (S) EL. 209.6'
SMH 10	235.6'	18" PVC (N) EL. 211.5'	18" PVC (S) EL. 211.4'
SMH 11	230.8'	18" PVC (N) EL. 212.8'	18" PVC (S) EL. 212.7'


JURISDICTIONAL WETLANDS WERE DELINEATED BY A CERTIFIED WETLAND SCIENTIST SEPARATELY FROM THE SURVEY AND CAN BE FOUND ON DWG NO W11.1 AND WITHIN THE WETLAND REPORT.

DRAWING NOTES

- THIS PLAN DEPICTS FIELD EVIDENCE AS LAST OBSERVED BY PROMISED LAND SURVEY, LLC (PLS) IN SEPTEMBER OF 2019.
- HORIZONTAL DATUM IS REFERENCED TO NH NAD83 – PER DIGITAL DRAWING RECIEVED FROM HOYLE, TANNER, ASSOC., INC. FROM AN E.C. MITCHELL SURVEY OF 2017.
- VERTICAL DATUM IS NAVD88 – PER DIGITAL DRAWING RECIEVED FROM HOYLE, TANNER, ASSOC., INC. FROM AN E.C. MITCHELL SURVEY OF 2017.
- UNDERGROUND UTILITIES, IF SHOWN, ARE APPROXIMATE AND ARE BASED ON OBSERVED FIELD EVIDENCE. ADDITIONAL UNDERGROUND UTILITIES MAY EXIST. CONTACT DIG SAFE (811) PRIOR TO ANY EXCAVATION OR CONSTRUCTION ACTIVITY.
- RIGHT OF WAY AND BOUNDARY LINE INFORMATION, IF SHOWN HEREON, IS APPROXIMATE AND IS BASED ON FIELD EVIDENCE IN CONJUNCTION WITH PLAN INFORMATION OBTAINED FROM THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. AS SUCH, THIS PLAN DOES NOT REPRESENT A BOUNDARY SURVEY.
- BOUNDARY MONUMENTS, AS SHOWN, SHOULD NOT BE UTILIZED FOR VERTICAL CONTROL; VERTICAL CONTROL HAS BEEN ESTABLISHED/PROVIDED.
- THE SURFACE AND FAULT LINES GENERATED/PROVIDED BY PLS REPRESENT THE SURFACE MODEL INTENDED FOR USE. THIS SURFACE TAKES INTO ACCOUNT THOSE POINTS WHICH SHOULD NOT BE UTILIZED FOR VERTICAL LOCATION AND SITE FAULT LINES. AS SUCH, ANY SURFACE GENERATED BEYOND WHAT HAS BEEN PROVIDED IS AT THE DISCRETION OF THE CREATOR AND PLS ASSUMES NO RESPONSIBILITY FOR ITS CREATION OR USAGE.
- IF THERE APPEARS TO BE ANY DISCREPANCIES IN HORIZONTAL OR VERTICAL CONTROL IT IS THE DUTY OF THE CONTRACTOR/DESIGNER TO NOTIFY PLS IN ORDER TO DETERMINE THE BEST SOLUTION. ANY PROGRESS IN SITE WORK WITHOUT SEEKING RESOLUTION TO SAID ISSUES IS NOT THE RESPONSIBILITY OF PLS.
- IF THERE APPEARS TO BE ANY DISCREPANCIES IN INVERT INFORMATION WITHIN DRAINAGE, SEWER, OR OTHER STRUCTURES IT IS THE DUTY OF THE CONTRACTOR/DESIGNER TO IMMEDIATELY NOTIFY PLS IN ORDER TO DETERMINE THE BEST SOLUTION. ANY PROGRESS IN OR ON SITE WORK WITHOUT SEEKING IMMEDIATE RESOLUTION TO SAID ISSUES IS NOT THE RESPONSIBILITY OF PLS.
- DUE TO THE UNSECURED USE OF ELECTRONIC FILES AND THE INABILITY OF PLS TO ESTABLISH CONTROLS OVER THEIR USE, PLS ASSUMES NO RESPONSIBILITY FOR ANY CONSEQUENCES ARISING OUT OF THE USE OF THE DATA. IT IS THE SOLE RESPONSIBILITY OF THE RECIPIENT TO CHECK THE VALIDITY OF ALL INFORMATION CONTAINED HEREIN. IF SIGNED AND SEALED DRAWINGS ARE PROVIDED AS PART OF THIS SURVEY, THE RECIPIENT(S) SHALL AT ALL TIMES REFER TO SUCH SIGNED AND SEALED DRAWINGS DURING ALL PHASES OF THE PROJECT UNLESS OTHERWISE DIRECTED, OR UPATED DRAWINGS HAVE BEEN PROVIDED. THE RECIPIENT SHALL ASSUME ALL RISKS AND LIABILITIES RESULTING FROM THE USE OF THIS DATA, AND THE RECIPIENT AGREE(S) TO WAIVE ANY AND ALL CLAIMS AND LIABILITY AGAINST PLS AND ITS SUB CONSULTANTS RESULTING IN ANY WAY FROM THE USE OF THE ELECTRONIC FILES.
- USE OF THIS DRAWING & INFORMATION IS TO BE CONSTRUED AS ACCEPTANCE OF THE TERMS AND CONDITIONS AS INTENDED ABOVE.



PROMISED LAND SURVEY, LLC
P.O. BOX 447
DERRY, NH 03038
(603) 432-2112



ENGINEER'S SEAL

PROJECT DESIGNER

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SJS

150 Down South
Rte 101
Box 6031
Derry, NH 03038
www.hoyletanner.com

HOYLE
TANNER

Hoyle Tanner & Associates © 2021

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

EXISTING CONDITIONS PLAN
SHEET 1 OF 4

DATE: MARCH 2022
SCALE: AS SHOWN

REV.	DATE	DESCRIPTION

DO NOT SCALE DRAWING




PROJ. No.: 030089.00

FILE: MHT-SV101

AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
SV1.1

SHEET 3 OF 34



PROMISED LAND SURVEY, LLC
P.O. BOX 447
DERRY, NH 03038
(603) 432-2112

ENGINEER'S SEAL

PROJECT DESIGNER

HOYLE
TANNER

150 Bow Street
Andover, NH 03001
(603) 689-5555
www.hoyletanner.com

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SLS

150 Bow Street
Andover, NH 03001
(603) 689-5555
www.hoyletanner.com

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

EXISTING CONDITIONS PLAN
SHEET 2 OF 4


DATE: MARCH 2022
SCALE: AS SHOWN

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			



PROJ. No.: 030089.00
FILE: MHT-SV101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
SV1.2

SHEET 4 OF 34



MATCHLINE – SEE SHEET SV1.4



PROMISED LAND SURVEY, LLC
P.O. BOX 447
DERRY, NH 03038
(603) 432-2112

REVISIONS			BY
REV. NO.	DATE	DESCRIPTION	
△			
△			
△			
△			
△			
		DO NOT SCALE DRAWING	

PROJ. No.:	030089.00
FILE:	MHT-SV101
AIP No.:	3-33-0011-XXX-2022

DRAWING NO.
SV1.3
SHEET 5 OF 34

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

EXISTING CONDITIONS PLAN
SHEET 3 OF 4

SCALE: AS SHOWN	DATE: MARCH 2022
-----------------	------------------

**CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE**



PROJECT DESIGNER







150 Dow Street
Manchester, NH 03101
(603) 669-5555
www.hoyletanner.com

DESIGNED BY JCC	DRAWN BY RPH	CHECKED BY SLS
--------------------	-----------------	-------------------

ENGINEER'S SEAL

MATCHLINE — SEE ABOVE





MATCHLINE — SEE SHEET SV1.3



PROMISED LAND SURVEY, LLC
P.O. BOX 447
DERRY, NH 03038
(603) 432-2112

MATCHLINE — SEE BELOW

ENGINEER'S SEAL		PROJECT DESIGNER		CITY OF MANCHESTER DEPARTMENT OF AVIATION MANCHESTER, NEW HAMPSHIRE		MANCHESTER-BOSTON REGIONAL AIRPORT SERVICE ROAD IMPROVEMENTS		EXISTING CONDITIONS PLAN SHEET 4 OF 4		DATE: MARCH 2022	
DESIGNED BY JCC		DRAWN BY RPH		CHECKED BY SLS		PROJECT DESIGNER		CITY OF MANCHESTER DEPARTMENT OF AVIATION MANCHESTER, NEW HAMPSHIRE		MANCHESTER-BOSTON REGIONAL AIRPORT SERVICE ROAD IMPROVEMENTS	
HOYLE TANNER		MANCHESTER-BOSTON REGIONAL AIRPORT SERVICE ROAD IMPROVEMENTS		EXISTING CONDITIONS PLAN SHEET 4 OF 4		DATE: MARCH 2022		SCALE: AS SHOWN		DATE: MARCH 2022	
SHEET 6 OF 34		DRAWING NO. SV1.4		PROJECT NO. 030089.00		FILE: MHT-SV101		AIP No.: 3-33-0011-XXX-2022		DRAWING NO. SV1.4	



PROJECT DESIGNER
HOYLE TANNER
150 Bow Street
Andover, MA 01810
(603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021
CHECKED BY: SLS
DRAWN BY: RPH
DESIGNED BY: JCC


CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
GEOMETRY SHEET 1 OF 4
SCALE: AS SHOWN
DATE: MARCH 2022

REVISIONS		BY	DATE	DESCRIPTION
REV.	NO.			
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				

PROJ. No.: 030089.00
FILE: MHT-GE101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
GE1.1
SHEET 7 OF 34
REV



ENGINEER'S SEAL
STATE OF NEW HAMPSHIRE
SUZANNE SHEPARD
No. 11946
LICENSED PROFESSIONAL ENGINEER
3/27/2022

150 Bow Street
Andover, MA 01810
Tel: (603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021
DESIGNED BY JCC
DRAWN BY RPH
CHECKED BY SLS


PROJECT DESIGNER
HOYLE
TANNER

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT



MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
GEOMETRY SHEET 2 OF 4
DATE: MARCH 2022
SCALE: AS SHOWN

REVISIONS
BY
DESCRIPTION
DATE
REV.
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000
1001
1002
1003
1004
1005
1006
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851
1852
1853
1854
1855
1856
1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097

MATCHLINE — SEE SHEET GE1.2



MATCHLINE — SEE SHEET GE1.4



PROJECT DESIGNER

HOYLE TANNER

150 Down Street
Andover, MA 01810
(603) 689-5555
www.hoyletanner.com

DESIGNED BY: JCC
DRAWN BY: RPH
CHECKED BY: SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

GEOMETRY SHEET 3 OF 4

SCALE: AS SHOWN
DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1	3/24/2022	ISSUED FOR BIDDING	JCC
2	3/24/2022	REVISED TO ADD NOTES	JCC
3	3/24/2022	REVISED TO ADD NOTES	JCC
4	3/24/2022	REVISED TO ADD NOTES	JCC


PROJ. No.: 030089.00
FILE: MHT-GE101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

GE1.3



SHEET 9 OF 34

MATCHLINE – SEE SHEET GE1.3




MATCHLINE – SEE BELOW

MATCHLINE – SEE ABOVE



ENGINEER'S SEAL



150 Bow Street
Manchester, NH 03101
Tel: (603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021

**HOYLE
TANNER**

PROJECT DESIGNER

**CITY OF MANCHESTER
DEPARTMENT OF AVIATION**
MANCHESTER, NEW HAMPSHIRE

**Manchester-Boston
REGIONAL AIRPORT**

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

GEOMETRY SHEET 4 OF 4

SCALE: AS SHOWN DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1	3/27/2022	ISSUED FOR PERMIT	JCC
2	3/27/2022	REVISED TO ADD NOTES	JCC
3	3/27/2022	REVISED TO ADD NOTES	JCC
4	3/27/2022	REVISED TO ADD NOTES	JCC
5	3/27/2022	REVISED TO ADD NOTES	JCC

PROJ. No.: 030089.00


FILE: MHT-GE101

AIP No.: 3-33-0011-XXX-2022


DRAWING NO.

GE1.4



SHEET 10 OF 34




**TYPICAL SECTION OF SERVICE ROAD
FULL DEPTH CONSTRUCTION**
NOT TO SCALE



**TYPICAL SECTION OF SERVICE ROAD
MILL AND INLAY**
NOT TO SCALE



ENGINEER'S SEAL



PROJECT DESIGNER
HOYLE
TANNER

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT


MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

TYPICAL SECTIONS
AND PAVEMENT DETAILS


REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

PROJ. No.: 030089.00
FILE: MHT-GE201
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
GE2.1
SHEET 11 OF 34



MATCHLINE — SEE SHEET GD1.2



PROJECT DESIGNER
HOYLE TANNER
150 Bow Street
Andover, MA 01913
(603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021
CHECKED BY: SLS
DRAWN BY: RPH
DESIGNED BY: JCC



CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
GRADING AND DRAINAGE PLAN
SHEET 1 OF 2
DATE: MARCH 2022
SCALE: AS SHOWN

REVISIONS		BY	DATE
REV.	DESCRIPTION		

PROJ. No.: 030089.00
FILE: MHT-GD101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
GD1.1
SHEET 12 OF 34



PROJECT DESIGNER

**HOYLE
TANNER**

150 Bow Street
Andover, MA 01810
(603) 689-5555
www.hoyletanner.com

DESIGNED BY: JCC
DRAWN BY: RPH
CHECKED BY: SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

**GRADING AND DRAINAGE PLAN
SHEET 2 OF 2**

SCALE: AS SHOWN
DATE: MARCH 2022



REV.	DATE	DESCRIPTION	BY

PROJ. No.: 030089.00
FILE: MHT-GD101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
GD1.2

SHEET 13 OF 34

DWG: H:\030089 MHT RW 35 Perimeter Rd\2-CADD\0-Contract\MHT-PR101.dwg Mar 29, 2022 - 5:54pm



ENGINEER'S SEAL

3/27/2022

PROJECT DESIGNER

HOYLE
TANNER


CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE


Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
PROPOSED PROFILE
AND ALIGNMENT OF
UNNAMED STREAM
DATE: MARCH 2022
SCALE: AS SHOWN

REVISIONS
BY
DATE
REV
NO
DESCRIPTION
DATE
REV
NO
DESCRIPTION

PROJ. No.: 030089.00
FILE: MHT-PR101
AP No.: 3-33-0011-XXX-2022
DRAWING NO.
PR1.1
SHEET 14 OF 34





WETLAND IMPACTS			
SYMBOL	IMPACT TYPE	AREA (SF)	LENGTH (LF)
A	PERMANENT BANK OF STREAM	41	
B	PERMANENT BED OF STREAM	75	15
C	PERMANENT BANK OF STREAM	199	
D	TEMPORARY BANK OF STREAM	60	
E	TEMPORARY BED OF STREAM	76	14
F	TEMPORARY BANK OF STREAM	75	
G	TEMPORARY BED OF STREAM	7923	1125
H	TEMPORARY BANK OF STREAM	6989	
I	TEMPORARY BANK OF STREAM	7657	

SUMMARY OF IMPACTS:

TOTAL TEMPORARY IMPACTS = 22,780 SF
TOTAL PERMANENT IMPACTS = 315 SF
TOTAL LINEAR FOOT = 1,154 LF

TOTAL IMPACTS = 23,095 SF

ENVIRONMENTAL PROTECTION NOTES:

1. THIS PROJECT SHALL BE SUBJECT TO AVOIDANCE AND MINIMIZATION MEASURES TO PROTECT THE HABITAT OF THE NORTHERN LONG-EARED BAT. MEASURES APPLICABLE TO THIS PROJECT INCLUDE TIME-OF-YEAR {TOY} RESTRICTIONS FOR TREES > 3" DIAMETER BREAST HEIGHT (DBH). THE CONTRACTOR SHALL NOT CONDUCT ANY TREE CUTTING AND CLEARING ACTIVITIES FROM JUNE 1 THROUGH JULY 31.

2. THE PROJECT SHALL BE SUBJECT TO AVOIDANCE AND MINIMIZATION MEASURES TO PROTECT GRASSLAND BIRDS. MEASURES INCLUDE NO STAGING OR DRIVING EQUIPMENT THROUGH GRASSY AREAS DURING BIRD BREEDING FROM MAY 1 THROUGH JULY 31.


3. CONTRACTOR SHALL AVOID THE USE OF WELDED PLASTIC OR BIODEGRADABLE PLASTIC NETTING OR THREAD (E.G. POLYPROPYLENE) IN EROSION CONTROL MATTING. EROSION CONTROL MEASURES MUST BE ORGANIC AND WILDLIFE FRIENDLY. THE CONTRACTOR IS REQUIRED TO NOTIFY NEW HAMPSHIRE FISH & GAME (NHFG) OF THE TYPE OF PRODUCT TO BE USED AT THE SITE. CONTACT BRETT FERRY, NHFG AT Brett.Ferry@wildlife.nh.gov

4. THERE IS THE POTENTIAL TO ENCOUNTER BLANDING'S TURTLE, A STATE LISTED SPECIES WITHIN THE PROJECT AREA. IF BLANDING'S TURTLES ARE FOUND LAYING EGG IN THE WORK AREA, PLEASE CONTACT MELISSA DOPERALSKI AT 603-479-1129 OR JOSH MEGYESY AT 978-578-0802 FOR FURTHER INSTRUCTIONS. A FACT SHEET HAS BEEN PROVIDED IN THE PROJECT SPECIFICATIONS FOR IDENTIFICATION PURPOSES.

MAP/LOT	PROPERTY ADDRESS	OWNER NAME	MAILING ADDRESS	CITY	STATE	ZIP
028-019-0	27 NAVIGATOR RD	MANCHESTER AIRPORT AUTHORITY	1 AIRPORT RD, SUITE 300	MANCHESTER	NH	3103
028-019-1	33 REAR INDUSTRIAL DR					
028-018-0	11 PETTENGILL RD					
014-012-0	104 HARVEY RD	CITY OF MANCHESTER	1 AIRPORT RD, SUITE 300	MANCHESTER	NH	3103
014-014-0	98 HARVEY RD					
014-013-3	1 PLANEVIEW DR					
014-015-0	90 HARVEY RD					
014-017-1	88 HARVEY RD					
014-017-2	88 HARVEY RD					
014-019-0	80 84 HARVEY RD					
014-045-1	12 PETTENFILL RD	NEW HAMPSHIRE, STATE OF	PO BOX 483	CONCORD	NH	03301-0483
013-043-0	0 RR ROCKINGHAM RD					
014-008-0	106 HARVEY RD	GLENBERVIE INC	47690 EAST ANCHOR COURT	PLYMOUTH	MI	48170
028-022-29	11 RICKER AV					
014-013-2	100 HARVEY RD	THREE MENDZELA LLC	PO BOX 6323	MANCHESTER	NH	3108

LEGEND

- TEMPORARY IMPACTS
 PERMANENT IMPACTS



ENGINEER'S SEAL

150 Bow Street
Manchester, NH 03101
Tel: (603) 689-5555
www.hoyletanner.com

**HOYLE
TANNER**

Hoyle Tanner & Associates © 2021

PROJECT DESIGNER

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SJS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

WETLAND IMPACT PLAN
SHEET 2 OF 2

DATE: MARCH 2022
SCALE: AS SHOWN

BY

REVISIONS

DESCRIPTION

DATE

REV

DO NOT SCALE DRAWING

PROJ. No.: 030089.00


FILE: MHT-W101

AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
W11.2

SHEET 16 OF 34

REV




PIPE HEADWALL
NOT TO SCALE

NOTE:


ALL REINFORCED CONCRETE SHALL BE DESIGNED AND CONSTRUCTED TO SUPPORT H2O LOADING. THE CONTRACTOR IS REQUIRED TO SUPPLY SHOP DRAWINGS AND MANUFACTURERS' CERTIFICATIONS TO THE ENGINEER FOR REVIEW PRIOR TO INSTALLATION.

WALL THICKNESS AND DIMENSIONS MAY CHANGE SLIGHTLY TO MEET STRUCTURAL AND CONTRACTIBILITY REQUIREMENTS AS DETERMINED BY THE CONTRACTOR AND MANUFACTURER. ENGINEER TO REVIEW ALL FINAL DIMENSIONS THROUGH SHOP DRAWINGS.



NOTE: SEE DRAWING PR1.1 FOR PROFILE OF UNNAMED STREAM.

PROFILE OF PIPE AND STREAM
NOT TO SCALE




* PIPE DIA.	TRENCH WIDTH
UP TO 12"	36"
12" TO 24"	I.D. PLUS 24"
GREATER THAN 24"	2 X I.D.

WHERE DIFFERENT FROM THAT INDICATED ON THIS DETAIL, CONTRACTOR SHALL FOLLOW MANUFACTURER RECOMMENDATIONS FOR PIPE TRENCH, BEDDING, AND BACKFILL

CONTRACTOR SHALL SHORE TRENCH SIDES WHEN REQUIRED OR AS ORDERED BY THE ENGINEER


TYPICAL PIPE TRENCH DETAIL
NOT TO SCALE



NOTES:

1. GRATE SHALL BE AS PER MANUFACTURER'S RECOMMENDATION AND SHALL BE INSTALLED SUCH THAT REMOVAL IS POSSIBLE FOR MAINTENANCE.
2. ACCESS SHALL ONLY BE POSSIBLE FOR AIRPORT PERSONNEL AND SHALL BE SECURED BY PADLOCK OR OTHER APPROVED MEANS.

GRATE DETAIL
NOT TO SCALE




NOTE:

SEE VEGETATED SWALE DETAIL FOR ADDITIONAL INFORMATION REGARDING EROSION CONTROL BLANKET INSTALLATION.

THE INSTALLATION OF EROSION CONTROL BLANKET IS CONSIDERED INCIDENTAL TO OTHER PAY ITEMS WITHIN THIS CONTRACT.

CROSS SECTION OF STREAM
NOT TO SCALE



CROSS SECTION OF PIPE
NOT TO SCALE

ENGINEER'S SEAL

SUZANNE L. SHEPARD
No. 11946
PROFESSIONAL ENGINEER
3/27/2022

PROJECT DESIGNER

HOYLE
TANNER

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

WETLAND IMPACT DETAILS

DATE: MARCH 2022

SCALE: AS SHOWN

REVISIONS

REV.	DATE	DESCRIPTION
1		
2		
3		
4		
5		


PROJ. No.: 030089.00

FILE: W1201


AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
W12.1


SHEET 17 OF 34



HAY BALE INLET PROTECTION
AT CATCH BASIN
NOT TO SCALE




CONTINUOUS CONTAINED BERM INLET
PROTECTION AT CATCH BASIN
NOT TO SCALE



- CONSTRUCTION SPECIFICATIONS
- BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.
 - EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4".
 - BALES SHALL BE SECURELY ANCHORED IN PLACE BY STAKES OR REBARS DRIVEN THROUGH THE BALES. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARDS PREVIOUSLY LAID BALE TO FORCE BALES TOGETHER.
 - INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
 - BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.


HAY BALE SEDIMENT BARRIER DETAIL
NOT TO SCALE



MAINTENANCE:
CONTRACTOR TO CLEAN AFTER EVERY STORM. IF THE BARRIER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PASSES FILTERED WATER, THE SEDIMENT SHALL BE REMOVED AND THE BARRIER SHALL BE REPLACED. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.


THE DEVICE SHALL BE USED FOR IN PAVEMENT CATCH BASINS LOCATED IN MILLED AREAS AND TRENCH DRAINS AND SHALL BE REMOVED WHEN THE DRAINAGE AREA HAS BEEN ADEQUATELY STABILIZED.

FILTER FABRIC INLET PROTECTION
AT CATCH BASIN
NOT TO SCALE




NOTE:
CONTINUOUS CONTAINED BERMS CONSIST OF A SYNTHETIC TUBULAR NETTING FILLED WITH EROSION CONTROL MIX OR OTHER FILTER MATERIAL AND SHALL BE INSTALLED PER MANUFACTURERS INSTRUCTION.

CONTINUOUS CONTAINED BERM
SEDIMENT BARRIER DETAIL
NOT TO SCALE




- NOTE:
- SPACING OF WOOD FENCE POST NOT TO EXCEED 6'-0".
 - SILT FENCE SHALL BE INSTALLED BEFORE ANY EARTH REMOVAL OR EXCAVATION TAKES PLACE.
 - SILT FENCE SHALL BE INSPECTED WEEKLY OR AFTER RAIN. ANY SEDIMENT ACCUMULATED HIGHER THAN 1 FOOT ABOVE EXISTING GRADE SHALL BE REMOVED, ANY DAMAGED SECTIONS SHALL BE REPAIRED OR REPLACED.

SILT FENCE SEDIMENT BARRIER DETAIL
NOT TO SCALE



NOTE: CONCRETE BLOCK HEIGHT SHALL BE 24" INCHES (MIN.)

BLOCK & CRUSHED STONE INLET
PROTECTION AT CATCH BASIN
NOT TO SCALE



STONE CHECK DAM DETAILS
NOT TO SCALE

EROSION CONTROL MIX BERMS SEDIMENT BARRIER

EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE PROJECT SITE. IT MUST CONSIST PRIMARILY OF ORGANIC MATERIAL, SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR ACCEPTABLE MANUFACTURED PRODUCTS. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS WILL NOT BE ACCEPTABLE AS THE ORGANIC COMPONENT OF THE MIX.

COMPOSITION
EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS (SUBMITTAL REQUIRED):


- THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80 AND 100%, DRY WEIGHT BASIS.
- PARTICLE SIZE BY WEIGHT SHALL BE 100 % PASSING A 6" SCREEN AND A MINIMUM OF 70 %, MAXIMUM OF 85%, PASSING A 0.75" SCREEN.
- THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED.
- LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.
- SOLUBLE SALTS CONTENT SHALL BE < 4.0 MMHOS/CM.
- THE PH SHOULD FALL BETWEEN 5.0 AND 8.0.

INSTALLATION
THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL CONTOUR. IT MAY BE NECESSARY TO CUT TALL GRASSES OR WOODY VEGETATION TO AVOID CREATING VOIDS AND BRIDGES THAT WOULD ENABLE FINES TO WASH UNDER THE BARRIER THROUGH THE GRASS BLADES OR PLANT STEMS.


ON SLOPES LESS THAN 5% OR AT THE BOTTOM OF STEEPER SLOPES (2:1) UP TO 20 FEET LONG, THE BARRIER MUST BE A MINIMUM OF 12" HIGH, AS MEASURED ON THE UPHILL SIDE OF THE BARRIER, AND A MINIMUM OF TWO FEET WIDE. ON LONGER OR STEEPER SLOPES, THE BARRIER SHOULD BE WIDER TO ACCOMMODATE THE ADDITIONAL RUNOFF.

FROZEN GROUND, OUTCROPS OF BEDROCK AND VERY ROOTED FORESTED AREAS ARE LOCATIONS WHERE BERMS OF EROSION CONTROL MIX ARE MOST PRACTICAL AND EFFECTIVE. OTHER BMPs SHOULD BE USED AT LOW POINTS OF CONCENTRATED RUNOFF, BELOW CULVERT OUTLET APRONS, AROUND CATCH BASINS AND CLOSED STORM SYSTEMS, AND AT THE BOTTOM OF STEEP PERIMETER SLOPES THAT ARE MORE THAN 50 FEET FROM TOP TO BOTTOM (I.E., A LARGE UP GRADIENT CONTRIBUTING WATERSHED).

ENGINEER'S SEAL



PROJECT DESIGNER
HOYLE
TANNER



CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
EROSION CONTROL DETAILS
SHEET 1 OF 2
DATE: MARCH 2022
SCALE: NOT TO SCALE

REVISIONS	BY	DATE	DESCRIPTION
REV. 1			
REV. 2			
REV. 3			
REV. 4			

PROJ. No.: 030089.00

FILE: BDL-ER201

AIP No.: 3-33-0011-XXXX-2022

DRAWING NO.

ER1.1

SHEET 18 OF 34

TOPSOIL AND SEEDING

1. TOPSOIL

SUITABLE TOPSOIL STRIPPED FROM THE SITE, FROM THE AIRPORT STOCKPILE OR FROM OFF-SITE SHALL MEET THE REQUIREMENTS OF SPECIFICATION SECTION T-905, TOPSOILING.

2. SEEDING

USE PERMANENT SEED MIXES AND RATES BETWEEN 5/15 AND 9/30. USE TEMPORARY SEED MIXES FOR PERIODS LESS THAN 12 MONTHS. IF USING TEMPORARY SEED MIXES BETWEEN 10/01 AND 5/15, RE-SEED WITH PERMANENT SEED MIX AFTER 5/15

3. REGULAR SEED MIX

KIND OF SEED	LBS PER ACRE	MINIMUM GERMINATION %	MINIMUM PURITY %
TALL FESCUE (FESTUCA ARUNDINACEA)	72	85	96
SALTY ALKALI (PUCCINELLIA TENUIFLORA)	36	85	96
RELIANT HARD FESCUE/CREEPING RED FESCUE	12	85	96
TOTAL	120		

4. WETLAND SEED MIX
NHDOT ITEM 644.62 SEED MIX:

KIND OF SEED	LBS PER ACRE	MINIMUM PURITY %	MINIMUM GERMINATION %
UPLAND BENTGRASS (AGROTIS PERENNAS)	2	95	85
AMERICAN MANNAGRASS (GLYCERIA GRANDIS)	2	95	85
WOOLGRASS (SCRIPUS CYPERINUS)	3	95	85
FOX SEDGE (CAREX VULPINOIDEA)	2	95	85
FRINGE SEDGE (CAREX CRINITA)	3	95	70
SOFT RUSH (JUNCUS EFFUSUS)	2	95	85
FOWL MANNAGRASS (GLYCERIA STRIATA)	2	95	85
TOTAL	16		

5. TEMPORARY SEED

KIND OF SEED	LBS PER ACRE	MINIMUM PURITY %	MINIMUM GERMINATION %
ANNUAL OR PERENNIAL RYEGRASS	40	85	80


6. LIME AND FERTILIZER

APPLY LIME AND FERTILIZER AT THE RATES SPECIFIED IN SECTION T-901, SEEDING.


7. MULCH

MULCH AND EROSION CONTROL MATTING SHALL BE AS SPECIFIED IN SECTION P-156 TEMPORARY AIR AND WATER POLLUTION, SOIL EROSION AND SILTATION CONTROL.

STRAW OR HAY (ANCHORED)	70 - 90 LBS	PROTECTED AREAS
STRAW OR HAY (ANCHORED)	185 - 275 LBS	WINDY AREAS
SHREDDED OR CHOPPED	185 - 275 LBS	MODERATE TO HIGH VELOCITY
EROSION CONTROL BLANKET	AS REQUIRED	AREAS AND SLOPES STEEPER THAN 3:1




PLAN VIEW



ELEVATION VIEW

FILTER BAG DISCHARGE DETAIL

NOT TO SCALE




VEGETATED SWALE DETAIL


NOT TO SCALE

NOTES:

1. PRIOR TO PLACING EROSION CONTROL BLANKET, PREPARE THE SOIL BY RAKING AREA FREE OF CLODS AND LARGE STONES.
2. SEED, MULCH AND FERTILIZER SHALL BE DISTRIBUTED AS SPECIFIED OVER THE PREPARED SOIL PRIOR TO PLACING THE EROSION CONTROL BLANKET.
3. EROSION CONTROL BLANKET SHALL CONSIST OF HAY, JUTE MESH, OR OTHER AND BE APPROVED BY ENGINEER.
4. ALL SEAMS SHALL BE OVERLAPPED A MINIMUM OF 3" AND SECURE WITH STAPLES SPACED 18"-24" ON CENTER.
5. TO SECURE BLANKET TO GROUND, STAPLE PER MANUFACTURERS RECOMMENDATIONS.
6. OVERLAP EROSION CONTROL BLANKET IN DIRECTION OF FLOW ONLY.
7. WHERE SWALE SIDE SLOPES ARE FLATTER THAN 6:1 OR WHERE GRADE BREAKS ARE SUBSTANTIALLY HIGHER THAN THE SWALE BOTTOM, EROSION CONTROL BLANKET MAY BE TUCKED INTO THE SLOPE APPROXIMATELY 1' ABOVE SWALE BOTTOM. OTHERWISE, WELL-DEFINED CHANNELS SHALL BE PROTECTED TO THE TOP OF SLOPE AS SHOWN.



SECTION A-A




PLAN VIEW

CONSTRUCTION EXIT DETAIL

NOT TO SCALE

PER NH DES ENV-WQ 1506.09 SEDIMENT CONTROL METHODS: TEMPORARY CONSTRUCTION EXITS. TEMPORARY CONSTRUCTION EXIT(S), ALSO CALLED ANTI-TRACKING PADS, SHALL BE USED ONLY AS FOLLOWS:

- (a) THE MINIMUM STONE USED SHALL BE 3-INCH CRUSHED STONE;
- (b) THE MINIMUM LENGTH OF THE PAD SHALL BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJECT SITE;
- (c) THE PAD SHALL EXTEND THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS GREATER;
- (d) THE PAD SHALL SLOPE AWAY FROM THE EXISTING ROADWAY;
- (e) THE PAD SHALL BE AT LEAST 6 INCHES THICK;
- (f) A GEOTEXTILE FILTER FABRIC SHALL BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE BELOW THE PAD;
- (g) THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.



PROJECT DESIGNER
HOYLE TANNER
150 Bow Street
Manchester, NH 03101
(603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021
DESIGNED BY KJF
DRAWN BY JLC
CHECKED BY NEG

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
EROSION CONTROL DETAILS
SHEET 2 OF 2
SCALE: NOT TO SCALE
DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			

PROJ. No.: 030089.00
FILE: MHT-ER102
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
ER1.2
SHEET 19 OF 34
REV

SITE STABILIZATION AND 5 ACRE DISTURBANCE LIMIT

1. THE NH DES (DEPARTMENT OF ENVIRONMENTAL SERVICES) AOT (ALTERATION OF TERRAIN) PERMIT AND REGULATIONS HAS A STIPULATION THAT NO MORE OF 5 ACRES OF UNSTABILIZED EARTH DISTURBANCE MAY OCCUR AT ANY GIVEN TIME ON A PROJECT. HOWEVER, IT IS PERMITTED WHEN THE CONTRACTOR PROVIDES, AND IS REPSONSIBLE FOR PROVIDING AN "ENVIRONMENTAL MONITOR". THE FOLLOWING ARE THE CONDITIONS THAT APPLY:
- a. THE PERMITTEE SHALL EMPLOY THE SERVICES OF AN ENVIRONMENTAL MONITOR ("MONITOR"). THE MONITOR SHALL BE A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL OR A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE AND SHALL BE EMPLOYED TO INSPECT THE SITE FROM THE START OF ALTERATION OF TERRAIN ACTIVITIES UNTIL THE ALTERATION OF TERRAIN ACTIVITIES ARE COMPLETED AND THE SITE IS CONSIDERED STABLE*.

b. DURING THIS PERIOD, THE MONITOR SHALL INSPECT THE SUBJECT SITE AT LEAST ONCE A WEEK, AND IF POSSIBLE, DURING ANY ½ INCH OR GREATER RAIN EVENT (I.E. ½ INCH OF PRECIPITATION OR MORE WITHIN A 24 HOUR PERIOD). IF UNABLE TO BE PRESENT DURING SUCH A STORM, THE MONITOR SHALL INSPECT THE SITE WITHIN 24 HOURS OF THIS EVENT.

c. THE INSPECTIONS SHALL BE FOR THE PURPOSES OF DETERMINING COMPLIANCE WITH THE PERMIT. THE MONITOR SHALL SUBMIT A WRITTEN REPORT TO THE DEPARTMENT WITHIN 24 HOURS OF THE INSPECTIONS. THE REPORTS SHALL DESCRIBE, AT A MINIMUM, WHETHER THE PROJECT IS BEING CONSTRUCTED IN ACCORDANCE WITH THE APPROVED SEQUENCE, SHALL IDENTIFY ANY DEVIATION FROM THE CONDITIONS OF THIS PERMIT AND THE APPROVED PLANS, AND IDENTIFY ANY OTHER NOTED DEFICIENCIES.

d. THE MONITOR SHALL PROVIDE TECHNICAL ASSISTANCE AND RECOMMENDATIONS TO THE CONTRACTOR ON THE APPROPRIATE BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROLS REQUIRED TO MEET THE REQUIREMENTS OF RSA 485–A:17 AND ALL APPLICABLE DES PERMIT CONDITIONS.

e. WITHIN 24 HOURS OF EACH INSPECTION, THE MONITOR SHALL SUBMIT A REPORT TO DES VIA EMAIL (TO STACEY HERBOLD AT: STACEY.HERBOLD@DES.NH.GOV).
2. SHOULD THE CONTRACTOR ELECT TO DISTURB MORE THAN 5 ACRES AT ANY GIVEN TIME ON THIS PROJECT, THE CONTRACTOR SHALL NOTIFY THE ENGINEER WELL IN ADVANCE OF THE START OF THE PROJECT AND MAKE NECESSARY ARRANGEMENTS WITH THE DES. THE CONTRACTOR IS OBLIGATED TO PROVIDE THE MONITOR AND PAY FOR ALL COSTS ASSOCIATED WITH THE MONITOR AND MONITORING WORK AS REQUIRED BY THE DES. THE COSTS INCURRED TO PROVIDE THIS SERVICE WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCIDENTAL TO THE PROJECT COSTS. THIS IN NO WAY RELIEVES THE CONTRACTOR FROM THIER OBLIGATION TO ADHERE TO ALL DES REQUIREMENTS, BEST PRACTICES FOR SITE STABILIZATION, SILTATION AND EROSION CONTROL, OR ANY OTHER REQUIREMENTS OF THIS CONTRACT.

*SITE STABILIZATION IS DEFINED BY NH DES ADMINISTRATIVE RULES:

- Env–Wq 1505.03, (WARM WEATHER), AN AREA SHALL BE CONSIDERED STABILE IF ONE OF THE FOLLOWING HAS OCCURRED:

(A) BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED

(B) A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED

(C) A MINIMUM OF 3 INCHES OF NON–EROSIVE MATERIAL SUCH ASS STONE OR RIPRAP HAS BEEN INSTALLED

(D) OR EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED

• Env–Wq 1505.05 (COLD WEATHER):

(A) TO ADEQUATELY PROTECT WATER QUALITY DURING COLD WEATHER AND DURING SPRING RUNOFF, THE ADDITIONAL STABILIZATION TECHNIQUES SPECIFIED IN THIS SECTION SHALL BE EMPLOYED DURING THE PERIOD FROM NOVEMBER 30 THROUGH MAY 1.

(B) THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LIMITED TO ONE ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED IN THIS SECTION PRIOR TO ANY THAW OR SPRING MELT EVENT. THE ALLOWABLE AREA OF EXPOSED SOIL MAY BE INCREASED IF A WINTER CONSTRUCTION PLAN, DEVELOPED BY A QUALIFIED ENGINEER OR A CPESC SPECIALIST, IS REVIEWED AND APPROVED BY THE DEPARTMENT.

(C) ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30, OR WHICH ARE DISTURBED AFTER NOVEMBER 30, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING OR TACKIFIER, OR 2 INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV–WQ 1506.05(D) THROUGH (H).

(D) ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30, OR WHICH ARE DISTURBED AFTER NOVEMBER 30, SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED AND ANCHORED EROSION CONTROL BLANKET OR WITH A MINIMUM 4 INCH THICKNESS OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV–WQ 1506.05(D) THROUGH (H).

(E) INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX, MEETING THE CRITERIA OF ENV–WQ 1506.05(D) THROUGH (H), SHALL NOT OCCUR OVER SNOW OF GREATER THAN ONE INCH IN DEPTH.

(F) INSTALLATION OF EROSION CONTROL BLANKETS SHALL NOT OCCUR OVER SNOW OF GREATER THAN ONE INCH IN DEPTH OR ON FROZEN GROUND.

(G) ALL PROPOSED STABILIZATION IN ACCORDANCE WITH (C) OR (D), ABOVE, SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS.
- (H) ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30, OR WHICH ARE DISTURBED AFTER NOVEMBER 30, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS, AS DETERMINED BY THE OWNER'S ENGINEERING CONSULTANT.

(I) AFTER NOVEMBER 30, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM 3 INCH LAYER OF BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, 2006, ITEM NO. 304.1 OR 304.2.
- EROSION CONTROL NOTES
1. ALL EARTHWORK SHALL BE CONFINED TO THE LIMITS OF WORK AS SHOWN ON CONTRACT DRAWINGS.

2. TEMPORARY FILLS SHALL REMAIN WITHIN WETLAND IMPACT AREAS SHOWN IN THE WETLAND PERMIT. A GEOTEXTILE FABRIC SHALL BE PLACED UNDER ALL TEMPORARY FILLS TO MINIMIZE DISRUPTION TO NATIVE SOILS AND VEGETATION.

3. WATER DIVERSION WILL BE USED TO COMPLETE WORK IN THE DRY. CONTRACTOR'S MEANS AND METHODS WILL DETERMINE IF WORK IS PERFORMED IN PHASES OR SIMULTANEOUSLY.

4. CONTRACTOR SHALL RETAIN SEDIMENT ON–SITE AND CONTROL DEWATERING PRACTICES:

4.1. TEMPORARY SEDIMENT BASINS SHALL BE SIZED TO RETAIN ON SITE, THE VOLUME OF A 2–YEAR 24–HOUR STORM EVENT FOR ANY AREA OF DISTURBANCE OR 3,600 CUBIC FEET OF STORMWATER RUNOFF ER ACRE OF DISTURBANCE, WHICHEVER IS GREATER.

4.2. CONSTRUCT AND STABILIZE DEWATERING INFILTRATION BASINS OR BAGS PRIOR TO ANY EXCAVATION THAT MAY REQUIRE DEWATERING.

4.3. TEMPORARY SEDIMENT BASINS SHALL BE PLACED AND STABILIZED AT LOCATIONS WHERE CONCENTRATED FLOW (CHANNELS AND PIPES) DISCHARGE TO THE SURROUNDING ENVIRONMENT FROM ARES OF UNSTABILIZED EARTH DISTURBING ACTIVITIES.

4.4. SEDIMENT FROM DEWATERING INFILTRATION BASINS OR BAGS SHALL BE DISPOSED OF PER NHDES REGULATIONS.

5. AFTER COMPLETION OF IN–WATER WORK, CONTRACTOR SHALL REMOVE ALL WATER DIVERSION STRUCTURES AND RESTORE ALL DISTURBED AREAS TO PRE–CONSTRUCTION CONDITIONS.

6. SILT FENCES OR EROSION CONTROL MIX BERMS SHALL BE INSTALLED WHERE SHOWN ON THE PLANS, ON THE DOWNHILL SIDE OF STOCKPILES OF TOPSOIL AND OTHER SOIL MATERIALS AND IN OTHER LOCATIONS AS REQUIRED, TO PREVENT SILT AND SEDIMENTATION FROM ENTERING EXISTING DRAINAGE CHANNELS.

7. PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE.

8. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT MAY NOT EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREA IS STABILIZED, UNLESS AN ENVIRONMENTAL MONITOR IS USED. (REFER TO SITE STABILIZATION NOTES, THIS DWG.)

9. ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER EVERY ½ INCH OF RAINFALL.

10. ANY DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED WITHIN 45 DAYS, OR TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE.

11. DUST CONTROL: ALL VEHICLE TRAFFIC AREAS AND EXPOSED SURFACES SHALL BE MOISTENED PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST.

12. SLOPE STABILITY: ALL SLOPES SHALL BE INSPECTED FREQUENTLY FOR SIGNS OF FAILURE, SLIPPING, AND/OR EROSION. ANY DAMAGE SHALL BE REPAIRED IMMEDIATELY.

13. CONTRACTOR EROSION CONTROL MEASURES ARE NOT LIMITED TO THOSE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PERFORM ANY AND ALL ADDITIONAL MEASURES TO CONTROL EROSION.

14. SEDIMENT CONTROL AROUND CATCH BASINS SHALL BE INSTALLED WHERE INDICATED, AND PER THE DETAIL.
- OVERWINTER CONSTRUCTION AND STABILIZATION
1. AT A MINIMUM: ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

2. THE CONTRACTOR SHALL COMPLY WITH THE OVERWINTER CONSTRUCTION AND STABILIZATION REQUIREMENTS IN THE MAINE EROSION CONTROL AND SEDIMENT CONTROL BMP MANUAL.

3. THE WINTER CONSTRUCTION PERIOD IS FROM NOV 1 TO APR 15.

4. USE BERMS SEEDED ACCORDING TO TOPSOILING AND SEEDING NOTE 4 FOR SEDIMENT BARRIERS.

5. APPLY TEMPORARY SEED AND MULCH AT TWICE THE NORMAL RATE ACCORDING TO TOPSOILING AND SEEDING NOTES 4 AND 5.

6. MULCH STOCKPILES OF SOIL/SUBSOIL OVER WINTER WITH HAY OR STRAW AT TWICE NORMAL RATE.

7. DO NOT PLACE PERMANENT SEED BETWEEN OCT 16 AND APR 15. PROTECT FINE GRADED AREAS WITH MULCH OR TEMPORARY SEED AND MULCH UNTIL FINAL TREATMENT.

8. CONSTRUCT AND STABILIZE STONE–LINED DITCHES AND CHANNELS BY NOV 15. CONSTRUCT AND STABILIZE GRASS–LINE DITCHES AND CHANNELS BY SEP 1. INSTALL A SOD OR STONE LINER IF DITCHES AND CHANNELS CANNOT BE STABILIZED BY THESE DATES.

9. DISTURBED SOILS WITH SLOPES LESS THAN 15% MUST BE SEEDED AND MULCHED BY SEP 15. IF NOT STABILIZED BY THIS DATE, USE TEMPORARY VEGETATION, SOD, OR MULCH.
- HYDRANTS
1. CONTRACTOR MAY USE EXISTING HYDRANT FOR DUST AND MILLING.

2. HYDRANTS ARE LOCATED OUTSIDE AIRPORT SECURED AREA. CONTRACTOR MAY UTILIZE WITH WATER DISTRICT'S PERMISSION. WATER DISTRICT TO INSTALL METER AND PROPER BACKFLOW EQUIPMENT.

3. CONTRACTOR SHALL UTILIZE A WATER TRUCK TO TRANSPORT INTO PROJECT AREA.

4. CONTRACTOR TO PAY FOR WATER USE INCIDENTAL TO THE PROJECT.
- STATE OF NEW HAMPSHIRE
SUZANNE SHEPARD
No. 11944
LICENSED PROFESSIONAL ENGINEER
3/27/2022

150 Bowdoin Ave.
Manchester, NH 03101
(603) 688-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021

HOYLE
TANNER

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SJS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER–BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

EROSION AND SEDIMENT
CONTROL NOTES

DATE: MARCH 2022

REVISIONS

BY

DESCRIPTION

DATE

REV.

NO.

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT–ER201

AIP No.: 3–33–0011–XXX–2022

DRAWING NO.

ER2.1

SHEET 20 OF 34

REV



1. FULL TENSION OF THE WILDLIFE "SKIRT" IS NOT RECOMMENDED, CONTRACTOR SHALL TENSION WILDLIFE SKIRT ENOUGH TO CONFORM WITH EXISTING TERRAIN.
2. MAINTAIN SECURITY FENCE INTEGRITY AT ALL TIMES. DO NOT LEAVE EXCAVATION UNDER FENCE FABRIC WHICH WOULD PERMIT ACCESS.
3. DEPTH OF EXCAVATION SHALL BE INSPECTED AND APPROVED BY THE ENGINEER PRIOR TO PLACEMENT OF THE CHAIN LINK FENCE FABRIC.
4. END JOINTS BETWEEN ADJACENT SECTIONS OF WIRE FABRIC SHALL BE LAPPED 4' AND TIED WITH GALVANIZED WIRE TIES AT 2'-0" O.C. AND AT EDGES.

NOT TO SCALE



NOTES

1. ALL CORNER AND INTERMEDIATE BRACE OR PULL POSTS SHALL HAVE TWO BRACES.
2. THE MAXIMUM SPACING BETWEEN INTERMEDIATE POSTS IS 500'



NOTE:
ALL SIGN LETTERING, FONTS,
COLORS, SIZES AND GRAPHICS ARE
TO BE APPROVED BY THE OWNER
PRIOR TO PROCUREMENT OF SIGNS.

SIGN 'A' TO BE INSTALLED ALONG
EVERY 200 FT. LENGTH OF
PROPOSED FENCE.



NOT TO SCALE



SERVICE ROAD IMPROVEMENTS

REFERENCE DETAILS

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

REV. NO.	DATE	DESCRIPTION	BY
△			
△			
△			
△			
△		DO NOT SCALE DRAWING	

J. No.: 030089.00



MHT-GE202

No.: 3-33-0011-XXX-2022

DRAWING NO.

E1.1

EET 21 OF 34



ENGINEER'S SEAL

PROJECT DESIGNER

HOYLE
TANNER

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester Regional Airport

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 1 OF 12

SCALE: NOT TO SCALE

DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1	3/24/2022	ISSUED FOR PERMIT	JCC
2	3/24/2022	REVISED	JCC
3	3/24/2022	REVISED	JCC
4	3/24/2022	REVISED	JCC

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101



AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.1

SHEET 22 OF 34

REV



ENGINEER'S SEAL

PROJECT DESIGNER

**HOYLE
TANNER**

150 Down Rock
Ave.
Manchester, NH 03101
(603) 689-5555
www.hoyletanner.com

Hoyle Tanner & Associates © 2021

CHECKED BY
SLS

DRAWN BY
RPH

DESIGNED BY
JCC

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester Regional Airport

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 2 OF 12

DATE: MARCH 2022

SCALE: NOT TO SCALE

REVISIONS

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101



AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.2

SHEET 23 OF 34

REV



ENGINEER'S SEAL

SUZANNE SHEPARD
No. 11946
LICENSED PROFESSIONAL ENGINEER
3/24/2022

PROJECT DESIGNER

HOYLE TANNER

DESIGNED BY JCC
DRAWN BY RPH
CHECKED BY SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 3 OF 12

SCALE: NOT TO SCALE
DATE: MARCH 2022




REVISIONS		BY
REV.	DATE	DESCRIPTION
1		
2		
3		
4		

DO NOT SCALE DRAWING

PROJ. No.: 030089.00
FILE: MHT-XS101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.3

SHEET 24 OF 34



PROJECT DESIGNER

HOYLE TANNER

150 Bow Street
Andover, MA 01810
(603) 689-5555
www.hoyletanner.com

Hoyle Tanner & Associates © 2021

CHECKED BY: SLS

DRAWN BY: RPH

DESIGNED BY: JCC

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 4 OF 12

SCALE: NOT TO SCALE

DATE: MARCH 2022

REVISIONS		BY
REV.	DATE	DESCRIPTION
1		
2		
3		
4		

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101



AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.4

SHEET 25 OF 34

REV



ENGINEER'S SEAL



150 Bowdoin
Ave.
Durham, NH 03824
(603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021

PROJECT DESIGNER
**HOYLE
TANNER**



CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
SERVICE ROAD CROSS SECTIONS
SHEET 5 OF 12
SCALE: NOT TO SCALE
DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			

PROJ. No.: 030089.00
FILE: MHT-XS101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.5
SHEET 26 OF 34



ENGINEER'S SEAL

PROJECT DESIGNER

CHECKED BY: SLS

DRAWN BY: RPH

DESIGNED BY: JCC

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 6 OF 12

SCALE: NOT TO SCALE

DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1	3/24/2022	ISSUED FOR PERMIT	JCC
2	3/24/2022	REVISED	JCC
3	3/24/2022	REVISED	JCC
4	3/24/2022	REVISED	JCC

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101




AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.6

SHEET 27 OF 34

REV



PROJECT DESIGNER

HOYLE TANNER

150 Bowdoin Ave.
Andover, MA 01810
(603) 689-5555
www.hoyletanner.com

DESIGNED BY: JCC
DRAWN BY: RPH
CHECKED BY: SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 7 OF 12

SCALE: NOT TO SCALE
DATE: MARCH 2022



REVISIONS		BY
REV.	DATE	DESCRIPTION
1		
2		
3		
4		

DO NOT SCALE DRAWING

PROJ. No.: 030089.00
FILE: MHT-XS101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.7

SHEET 28 OF 34



ENGINEER'S SEAL

PROJECT DESIGNER

HOYLE
TANNER

150 Down Rock
Ave.
Manchester, NH 03101
(603) 689-5555
www.hoyletanner.com

Hoyle Tanner & Associates © 2021

CHECKED BY
SLS

DRAWN BY
RPH

DESIGNED BY
JCC

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester Regional Airport

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 8 OF 12

DATE: MARCH 2022

SCALE: NOT TO SCALE

REVISIONS

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101



AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.8

SHEET 29 OF 34

REV



ENGINEER'S SEAL

PROJECT DESIGNER

HOYLE
TANNER

150 Down Rock
Ave.
Manchester, NH 03101
(603) 689-5555
www.hoyletanner.com

Hoyle Tanner & Associates © 2021

CHECKED BY
SLS

DRAWN BY
RPH

DESIGNED BY
JCC

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 9 OF 12

DATE: MARCH 2022

SCALE: NOT TO SCALE

REV.	DATE	DESCRIPTION	BY
1	3/24/2022	ISSUED FOR PERMIT	SS
2	3/24/2022	REVISED TO ADD STATION 74+00	SS
3	3/24/2022	REVISED TO ADD STATION 73+50	SS
4	3/24/2022	REVISED TO ADD STATION 74+00	SS

DO NOT SCALE DRAWING

PROJ. No.: 030089.00

FILE: MHT-XS101



AIP No.: 3-33-0011-XXX-2022

DRAWING NO.

XS1.9

SHEET 30 OF 34


REV



ENGINEER'S SEAL



150 Down Rock
Andover, NH 03811
(603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021





CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE
Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS
SERVICE ROAD CROSS SECTIONS
SHEET 10 OF 12
SCALE: NOT TO SCALE
DATE: MARCH 2022

REV.	DATE	DESCRIPTION	BY
1	3/24/2022	ISSUED FOR PERMIT	JCC
2	3/24/2022	REVISED TO ADD WETLANDS	JCC
3	3/24/2022	REVISED TO ADD ORDINARY HIGH WATER	JCC
4	3/24/2022	REVISED TO ADD PROPOSED GROUND	JCC

PROJ. No.: 030089.00
FILE: MHT-XS101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.10
SHEET 31 OF 34



ENGINEER'S SEAL

PROJECT DESIGNER

**HOYLE
TANNER**

150 Down Rock
Ave.
Manchester, NH 03101
(603) 689-5555
www.hoyletanner.com

Hoyle Tanner & Associates © 2021

DESIGNED BY
JCC

DRAWN BY
RPH

CHECKED BY
SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

Manchester-Boston
REGIONAL AIRPORT

MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 11 OF 12

DATE: MARCH 2022

SCALE: NOT TO SCALE

DO NOT SCALE DRAWING

REVISIONS

REV.	DATE	DESCRIPTION	BY
1			
2			
3			
4			



PROJ. No.: 030089.00

FILE: MHT-XS101

AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.11


SHEET 32 OF 34



ENGINEER'S SEAL



150 Down Rock
Andover, NH 03811
Tel: (603) 689-5555
www.hoyletanner.com
Hoyle Tanner & Associates © 2021



MANCHESTER-BOSTON REGIONAL AIRPORT
SERVICE ROAD IMPROVEMENTS

SERVICE ROAD CROSS SECTIONS
SHEET 12 OF 12

SCALE: NOT TO SCALE DATE: MARCH 2022


REV.	DATE	DESCRIPTION	BY
1	3/24/22	ISSUED FOR PERMIT	JCC
2			
3			
4			

DO NOT SCALE DRAWING

PROJ. No.: 030089.00
FILE: MHT-XS101
AIP No.: 3-33-0011-XXX-2022

DRAWING NO.
XS1.12

SHEET 33 OF 34



CLIENT: Hoyle, Turner & Associates, Inc.
PROJECT NO.: 19-123
PROJACCT: Reconstruct Runway 35 End at Service Road
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

Drilling Information
LOCATION: See Exploration Location Plan
LOGGED BY: Antonio Santiago
DILLING CO.: S. W. Cole Explorations, LLC
DRILLER: Sam Shaw
REG TYPE: Truck Mounted Auger
AUGER ID/D: N/A / 4.12 in
HAHAMMER TYPE: Safety / N/A
HAHAMMER WEIGHT (lbs): 140
HAHAMMER DRILL (inch): 30
WATER LEVEL DEPTHS (ft): No free-water observed.

GENERAL NOTES:

KEY TO NOTES AND SYMBOLS:
Wt. Level
@ = at time of Drilling
C = Completion of Drilling
A = After Drilling

O = Split Spaced Sample
U = Thin Wallbed Tube Sample
R = Rock Core Sample
V = Field Vane Shear

Pen. = Penetration Length
Rec. = Recovery Length
bf = Blow Core Foot
mp = Minute per Foot


WCR = Weight of Rods
WCR4 = Weight of Hammer
RQD = Rock Quality Designation
PQ = Preconsolidation Designation

S₁ = Field Vane Shear Strength, kips/sq. ft.
S₂ = Unconfined Compressive Strength, kips/sq. ft.
Q = Friction Angle (Estimated)
N/A = Not Applicable

SAMPLE INFORMATION										H ₂ O Depth	Remarks
Elev. (ft)	Depth (ft)	Casing (in/ft)	Sample No.	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD	Lab / Field Test Date	Grain Size	Sample Description & Classification		
			1S	0.3-1	8/8			0.3	3.34 inches Asphalt Pavement (Bonded)		
			1D	1-1.5	6/3	50		1.0	Dark brown, silty gravelly SAND some clay (PLL) (SM)		
									Brown, sandy gravel some gravel some silt (SW-SM)		
Auger Refusal at 3.0 foot Probable bedrock or boulder.											

Drilling lines represent approximate boundaries between soil types. Transfers may be gradual. Water level readings from both inside and outside of casing, adjusted to same datum, shall be used only if one or other factors more than those present at the time substantially agree.

BORING NO.: B-1



CLIENT: Hoyte, Trimmer & Associates, Inc.
PROJECT: Reconstruct Runway 25 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, N.H.

BORING LOG
SHEET: 1 of 1
PROJECT NO: 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

Drilling Information
LOCATION: See Exploration Location Plan
DRILLING METHOD: S. W. Cole Explorations, LLC
RIG TYPE: Truck Mounted Auger
HAMMER TYPE: Safety
HAMMER EFFICIENCY FACTOR:
WATER LEVEL DEPTHS (ft): No free-water observed.
GENERAL NOTES:

ELEVATION (FT): N/A
DRILLER: Sam Shaw
AUGER ID/D: N/A 4.12 in
HAMMER WEIGHT (lbs): 140
HAMMER DROP (inch): 30

TOTAL DEPTH (FT): 3.5
LOGGED BY: Antonio Santiago
DRILLING METHOD: Solid Stem Auger
SAMPLER: Standard Split-Spoon
CASING ID/D: N/A N/A
CORE BARREL:

Penetration Length
Recovery Length
Blows per Foot
Rate per Foot

WCR = Weight of Rods
WCH = Weight of Hammer
RQD = Rock Quality Designation
MP = Penetration Meter

S_v = Field Vane Shear Strength, kips/sq.ft.
S_c = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

KEY TO NOTES AND SYMBOLS:
Water Level
End of Drilling
Completion of Drilling
After Casing

D = Split Spoon Sample
U = Thin Wall Test Sample
R = Rock Core Sample
V = Field Vane Shear

Penetration Length
Recovery Length
Blows per Foot
Rate per Foot

WCR = Weight of Rods
WCH = Weight of Hammer
RQD = Rock Quality Designation
MP = Penetration Meter

S_v = Field Vane Shear Strength, kips/sq.ft.
S_c = Unconfined Compressive Strength, kips/sq.ft.
Ø = Friction Angle (Estimated)
N/A = Not Applicable

SAMPLE INFORMATION									
Elev. (ft)	Depth (ft)	Casing (ft)	Sample No.	Depth (ft)	Pen / Rec. (in)	Count or RQD	Field / Lab Test Data	Grain Log	Remarks
			1S	0.3-1	8/8		w = 7.5 %	0.3	3 1/2 inches Asphalt Pavement (Delaminated)
			1D	1-2	12/8	28-50	w = 7.3 %	1.0	Dark brown, silty gravelly SAND some clay (FLL) (SM) Dense, brown gravelly silty SAND trace clay (TLL) (SM)

Auger Refusal at 3.5 feet
 Probable bedrock or boulder.

Stratification lines represent approximate boundary between sand and silt. Transitions may be gradual. Water level readings have been made at times and under conditions similar to those present at the time logs were made. No other factors than those present at the time of observation were made.

BORING NO.: B-2

[illegible]

BORING LOG

BORING NO.: B-4
SHEET: 1 of 1
PROJECT NO.: 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

CLIENT: Hoyte, Tanner & Associates, Inc.

PROJECT: Manchester Turnway 25 End of Service Road

LOCATION: Manchester-Boston Regional Airport, Manchester, N

Drilling Information

LOCATION: See Exploration Location Plan

ELEVATION (FT): N/A

TOTAL DEPTH (FT): 6.6

LOGGED BY: Antonio Santiago

DRILLING CO.: S. W. Cole Explorations, LLC

DRILLER: Sam Shaw

DRILLING METHOD: Solid Stem Auger

RIG TYPE: Truck Mounted Auger

AUGER ID/D: N/A 4 1/2 in

SAMPLER: Standard Split-Spoon

HAMMER TYPE: Safety

HAMMER WEIGHT (lba): 140

CASING ID/D: N/A N/A

CORE BARREL:

HAMMER EFFICIENCY FACTOR:

HAMMER DROP (inch): 30

WATER LEVEL DEPTH (ft): No free-water observed.

GENERAL NOTES:


KEY TO NOTES AND SYMBOLS: **Water Level** = At time of drilling **S** = Split Spoon Sample **Pen** = Penetration Length **WOR** = Weight of Rods **S_c** = Field Vane Shear Strength, kips/sq ft
AND SYMBOLS: **W** = 24 inch of drilling **U** = Thin Wall Test Sample **Rec** = Recovery Length **WDR** = Weight of Hammer **S_c** = Unconfined Compressive Strength, kips/sq ft
A = Completion of Drilling **R** = Rock Core Sample **tot** = Blows per Foot **RQD** = Rock Quality Designation **Q** = Friction Angle (Estimated)
V = After Drilling **V** = Field Vane Shear **mpf** = Minutes per Foot **mpf** = Minutes per Foot **N/A** = Not Applicable

SAMPLE INFORMATION									
Elev. (ft)	Depth (ft)	Casing (ft)	Sample No.	Depth (ft)	Pen / Rec. (ft)	Blow Count or RQD	Lab / Field Test Date	Grain Log	Remarks
			1S	0.3-1.5	14/14			0.3	3 inches Asphalt Pavement (Deconstructed) Dark brown, SAND and GRAVEL some silt trace clay (FILL) (SM)
			1D	1.5-3.5	24/14	13.35-32.48		1.6	Dense, gray silt SAND some clay some gravel (SC-SM)
			2D	4-4.8	9/6	48-50/37			

Auger Refusal at 5.0 feet
 Probable bedrock or boulder.

Stratification (see nonconformity approximately 10 feet below top of logs). Transitions may be gradual. Water level readings have been made at three and under conditions not stated in this log. No groundwater was encountered other than those present at the time measurements were made.

BORING NO.: B-4

	BORING LOG		BORING NO.: B-5								
	CLIENT: Hoyte Tanner & Associates, Inc. PROJECT: Manchester Runway 35 End of Service Road LOCATION: Manchester-Boston Regional Airport, Norwood, MA		SHEET: 1 of 1 PROJECT NO: 19-1233 DATE START: 5/5/2020 DATE FINISH: 5/5/2020								
Drilling Information LOCATION: See Exploration Location Plan ELEVATION (FT): N/A TOTAL DEPTH (FT): 10.0 LOGGED BY: Antonio Santiago DRILLING CO.: S. W. Cole Explorations, LLC DRILLER: Sam Shaw DRILLING METHOD: Solid Stem Auger RIG TYPE: Truck-Mounted Auger AUGER IDOD: N/A 1-1/2 in SAMPLER: Standard Split-Spoon CORE BARREL:											
HAMMER TYPE: Safety HAMMER WEIGHT (lbs): 140 CASING ID/OD: N/A N/A HAMMER EFFICIENCY FACTOR: HAMMER DROP (in/s): 30											
WATER LEVEL DEPTHS (ft): 0 - 6 ft Soil samples subsurface below 6 feet.											
GENERAL NOTES:											
<table border="0" style="width: 100%; font-size: 0.8em;"> <tr> <td style="width: 25%; vertical-align: top;"> KEY NOTES AND SYMBOLS: 1 = at time of drilling 2 = Completion of Drilling 3 = After Drilling </td> <td style="width: 25%; vertical-align: top;"> D = Split Spoon Sample U = Unsplit Tied Tube Sample R = Rock Core Sample V = Field Vane Shear </td> <td style="width: 25%; vertical-align: top;"> Pen. = Penetration Length Rec. = Recovery Length tot = Blows per Foot rpt = Minutes per Foot </td> <td style="width: 25%; vertical-align: top;"> WCR = Weight of Rod WDR = Weight of Hammer RQD = Rock Quality Designation 1 = Photocolorization Detector 2 = Not Applicable </td> </tr> <tr> <td></td> <td></td> <td></td> <td> S_v = Field Vane Shear Strength, kips/sq ft S_u = Uncorrected Compressive Strength, kips/sq ft F_r = Friction Angle (Estimated) N/A = Not Applicable </td> </tr> </table>				KEY NOTES AND SYMBOLS: 1 = at time of drilling 2 = Completion of Drilling 3 = After Drilling	D = Split Spoon Sample U = Unsplit Tied Tube Sample R = Rock Core Sample V = Field Vane Shear	Pen. = Penetration Length Rec. = Recovery Length tot = Blows per Foot rpt = Minutes per Foot	WCR = Weight of Rod WDR = Weight of Hammer RQD = Rock Quality Designation 1 = Photocolorization Detector 2 = Not Applicable				S _v = Field Vane Shear Strength, kips/sq ft S _u = Uncorrected Compressive Strength, kips/sq ft F _r = Friction Angle (Estimated) N/A = Not Applicable
KEY NOTES AND SYMBOLS: 1 = at time of drilling 2 = Completion of Drilling 3 = After Drilling	D = Split Spoon Sample U = Unsplit Tied Tube Sample R = Rock Core Sample V = Field Vane Shear	Pen. = Penetration Length Rec. = Recovery Length tot = Blows per Foot rpt = Minutes per Foot	WCR = Weight of Rod WDR = Weight of Hammer RQD = Rock Quality Designation 1 = Photocolorization Detector 2 = Not Applicable								
			S _v = Field Vane Shear Strength, kips/sq ft S _u = Uncorrected Compressive Strength, kips/sq ft F _r = Friction Angle (Estimated) N/A = Not Applicable								
SAMPLE INFORMATION											
Elev. (ft)	Depth (ft)	Casing Pen. (feet)	Sample No.	Depth (ft)	Pen./Rec. (in)	Blows Count or RQD	Field / Lab Test Date	Coring Log	Sample Description & Classification	H/P Depth	Remarks
			1S	0-3.15	14/14				3 1/2 inches Asphalt Pavement (Bonded)		
			1D	1-5.35	24/14	20-23:40-32		w ~6.2%	Dark brown, gravelly SAND some silt trace clay (FLL) (SW-SM)		
								w ~6.9%	Dense, brown SAND some gravel some silt (FLL) (SM)		
			2D	4-6	24/16	15-25:30-20			Dense, brown silty SAND trace gravel trace clay (SM)		
	5							w ~6.8%			
			3D	6-8	24/12	22-24:30-28					✓
			4D	8-10	24/14	25-26:29-29					
	10										
Bottom of Exploration at 10.0 feet											
Soil is loose, silty sand, trace clay, silt, gravel, 5-10%											
Foundation (time dependent approximate) boundary between soil types, transitions may be gradual and may change from time to time made at stress and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.											
BORING NO.:										B-5	

		BORING LOG		BORING NO. B-6							
		CLIENT: Hoyts, Turner & Associates, Inc.		SHEET: 1 of 1							
		PROJECT: Reconstruct Runway 25 End of Service Road		PROJECT NO.: 19-1233							
		LOCATION: Manchester-Boston Regional Airport, Manchester, NH		DATE START: 5/5/2020							
		DATE FINISH: 5/5/2020									
Drilling Information											
LOCATION: See Exploration Location Plan		ELEVATION (FT): N/A		TOTAL DEPTH (FT): 9.6							
DRILLING CO.: S. W. Cole Explorations, LLC		DRILLER: Sam Shaw		LOGGED BY: Antonio Santiago							
RIG TYPE: Truck Mounted Jacker		AUGER I/D: N/A 14.12 IN		DRILLING METHOD: Solid Stem Auger							
HAMMER TYPE: Safety		HAMMER WEIGHT (lb): 140		SAMPLER: Standard Split-Spoon							
HAMMER EFFICIENCY FACTOR: _____		HAMMER DROP (inch): 30		CORE BARREL: _____							
WATER LEVEL DEPTHS (ft): _____ 0.0 ft Soil Sample substituted below 8' feet											
GENERAL NOTES:											
KEY TO NOTES AND SYMBOLS:											
 D = Split Spoon Sample U = Thin Water Table Sample R = Rock Core Sample V = Field Core Shear Pen = Penetration Length Rec = Recovery Length tot = Blow per Foot rpm = Minute per Foot WCR = Weight of Rods WCR = Weight of Hammer R2D = Rock Quality Designation R2 = Penetration Indicator S _v = Field Vane Shear Strength, kips/sq. ft. S _u = Unconfined Compressive Strength, kips/sq. ft. α = Friction Angle (Estimated) N/A = Not Applicable											
SAMPLE INFORMATION											
Elev. (ft)	Depth (ft)	Coring Pen. (in)	Sample No.	Depth (ft)	Pen./ Rec. (in)	Blow Count or RQD	Field / Lab Test Data	Grain Size Classification	Sample Description & Classification	H2O Depth	Remarks
			1S	0-3.15	14/14			0.3	3 inches Asphalt Pavement (Bonded) Dark brown, gravelly SAND some silt trace clay (FLL) (SM)		
			1D	15.33	21/12	20-22- 300"	w ≈ 1.1%	1.5	Dense to Loose, brown gravelly silt SAND trace clay (FLL) (SM)		
			2D	4-4.8	9/3	6-50/3"	w ≈ 6.7%				
	5		3D	6-8	24/8	22-6/8					
			4D	8-9.6	19/14	20-22- 300"		7.0	Medium dense to dense, brown gravelly SAND some silt (SW-SM)		
Split Spoon Refusal at 9.6 feet Probable bedrock or boulder.											
Qualification lines represent approximate boundaries between soil types. Transitions may be gradual and/or abrupt. Results may vary due to other factors than those present at the time measurements were made.											
BORING NO. B-6											

BORING LOG

BORING NO.: B-7
SHEET: 1 of 1
PROJECT NO.: 19-1233
DATE START: 5/5/2020
DATE FINISH: 5/5/2020

CLIENT: Hoyle, Tanner & Associates, Inc.

PROJECT: Reconstruct Runway 25 End of Service Road
LOCATION: Manchester-Boston Regional Airport, Manchester, NH

Drilling Information

LOCATION: See Exploration Location Plan

DRILLING CO.: S. W. Cole Explorations, LLC

RIG TYPE: Truck Mounted Auger

HAMMER TYPE: Safety

HAMMER EFFICIENCY FACTOR: 32

WATER LEVEL DEPTH (ft): 32 6 ft Soil sample saturated below 6' soil

GENERAL NOTES:

KEY TO NOTES
 Water Level
 32 = 2 ft time of drilling
 32 = Completion of Drilling
 32 = After Drilling
 D = Split Spoon Sample
 U = Thin Water Taste Sample
 R = Rock Core Sample
 V = Field Vane Shear
 Pen = Penetration Length
 Rec = Recovery Length
 tot = Blows per Foot
 mgt = Minutes per Foot
 WOR = Weight of Rods
 WCH = Weight of Hammer
 RCD = Rock Quality Designation
 PQ = Photoacoustic Detector
 S_v = Field Vane Shear Strength, kips/sq ft
 S_u = Unconfined Compressive Strength, kips/sq ft
 β = Friction Angle (Estimated)
 N/A = Not Applicable


SAMPLE INFORMATION											
Elev. (ft)	Depth (ft)	Corrns. (per)	Sample No.	Depth (ft)	Pen./ Rec. (in.)	Blow Count or RQD	Flow / Lab Test Data	Sample Description & Classification	H ₂ O Depth		
5	1S	X	0-32	20/20	w ≈ 7 %	0.3	3 1/2 inches Asphalt Pavement (Bonded)	Dark brown, gravelly silt SAND trace (FLL) (SM)	▽		
	1D		2-4	24/14		2.0	Dense, brown silt SAND some gravel trace clay (FLL) (SM)				
	2D		4-6	24-4	w ≈ 6.6 %	3.5	Medium dense loose, brown silt SAND some gravel (SM)				
	3D		6-8	24/8							
	4D		8-10	24/0							
10											

Bottom of Exploration at 10.0 feet

Modification lines represent appropriate boundary between soil types, transitions may be made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

BORING NO.: B-7

ENGINEER'S SEAL

PROJECT DESIGNER	 HOYLE TANNER	150 New Street Manchester, NH 03101 (603) 669-5555 www.hoyletanner.com	DESIGNED BY	DRAWN BY	CHECKED BY
			JCC	RPH	SLS

CITY OF MANCHESTER
DEPARTMENT OF AVIATION
MANCHESTER, NEW HAMPSHIRE

 **Manchester-Boston**
REGIONAL AIRPORT

BORING LOGS	
AS SHOWN	DATE: MARCH 2022

REVISIONS			
REV. NO.	DATE	DESCRIPTION	BY
△			
△			
△			
△			

DO NOT SCALE DRAWING

PROJ. No.:	030089.00
FILE:	MHT-B101
A/P No.:	3-33-0011-XXX-2022
DRAWING NO.	
B1.1	
SHEET 29	OF 34
<div style="border: 1px solid black; padding: 2px; display: inline-block;"> REV </div>	